

TECTONICS AND SEDIMENTATION OF A
LATE PROTEROZOIC DAMARAN
CONVERGENT CONTINENTAL MARGIN,
KHOMAS HOCHLAND, CENTRAL NAMIBIA

Peter Alfred Kukla

A Dissertation Submitted to the Faculty of Science,
University of the Witwatersrand, Johannesburg,
for the Degree of Doctor of Philosophy

Johannesburg, 1990

ABSTRACT

The Late Proterozoic Damara Orogen (750-450 Ma; in Namibia forms part of the Pan-African mobile belt system which dissects southern Africa. The Khomas Trough in the inland branch of the orogen comprises thick multiply deformed metagreywackes and pelites of the Kuiseb Formation. Minor lithologies are graphite schists, calc-silicates and scapolite schists. The Matchless Amphibolite occurs structurally emplaced within the sequence and contains tholeiitic, mid-ocean ridge type metavolcanic rocks, including pillow lava and breccias, as well as ultramafic lithologies and metagabbroic lenses. Pelagic graphite schists, pelitic schists and a marble unit are intercalated within the metabasic rocks. Original sedimentary structures, turbidite facies, the vertical facies distribution of progradational and retrogradational cycles, and the lateral extent of major sedimentary units indicate that psammitic parts of the sedimentary protoliths have been deposited as turbidites on an elongate submarine fan. Geochemical signatures suggest that an active continental margin source to the north-east of the present-day Khomas Trough supplied the vast amounts of clastic sediment. The regional structural pattern is characterized by five phases of deformation with folds verging consistently to the south-east. The structural regime is markedly heterogeneous and is associated with thrusting which developed elongate thrust slices traceable laterally for at least 150 kilometres. Metamorphic index minerals

indicate lower to upper amphibolite facies conditions but partial melting occurred in some areas along the northern margin of the Khomas Trough.

These features are explained in a tectono-sedimentary model which involves the evolution of a Late Proterozoic accretionary prism, here named the Khomas Hochland accretionary prism, within a convergent continental margin setting. Rift initiation took place along old tectonic weakness zones between the Congo and Kalahari Cratons. This was followed by the formation of oceanic crust in the Khomas Sea which was an appreciably sized oceanic basin with a width of hundreds of kilometres minimum. Subsequent convergence and north-west directed subduction of oceanic crust beneath the Congo Craton produced an oceanic trench which contained the westward prograding elongate submarine fan. Pelagic sedimentation occurred contemporaneously within the basin. Basalts including a high proportion of pillow lavas and associated massive sulphide ore deposits formed at the mid-ocean ridge. The accretionary prism evolved through the offscraping of the trench sediments together with some pelagics from the oceanic plate and the accretion against the Congo cratonic margin. Early folding and thrusting occurred within the prism during this accretionary stage. Continental collision of the Congo and Kalahari Cratons resulted in the formation of a northerly steepening thrust pile with an overall imbricate fan geometry. Subsequent phases of compressional deformation involved initially south-eastward directed thrusting and folding which was followed at a late stage

by right-lateral strike-slip dislocation along the Okahandja Lineament. The Matchless Amphibolite has most probably been emplaced during the obduction of the accretionary prism onto the Kalahari Craton. Thermal relaxation subsequent to subduction led to a prolonged amphibolite facies regional metamorphism with the peak occurring late in the deformational history. Heterogeneous geothermal gradients in the Khomas Trough are interpreted to be due to differential uplift. The post-tectonic Donkerhoek Granite intruded along the Okahandja Lineament which is interpreted to represent the former backstop of the accretionary prism.

Lithologies, structural styles, time sequence of events and the size of the Khomas Hochland accretionary prism may be compared with the Palaeozoic Southern Uplands accretionary prism of Scotland, the Cretaceous Chugach terrain in Alaska and the Shumagin region of the modern Aleutian Trench. Several aspects such as the inferred width of the Khomas Sea, the scarcity of arc magmatics to the north, the lack of recognition of fore-arc basin deposits, early compressional stresses, extensive sediment loading, and the intercalation of metabasalts, turbidites, pelagics and massive sulphide deposits all point to the shallow subduction of young, buoyant and hot oceanic crust. A comparison to the southern Peru - Chile Trench may be drawn.

DECLARATION

I declare that this dissertation is my own, unaided work. It is being submitted for the degree of Doctor of Philosophy in the University of the Witwatersrand, Johannesburg. It has not been submitted before for any degree or examination in any other University.

Peter A. Kukla

(Peter A. Kukla)

12th day of December, 1990

ACKNOWLEDGEMENTS

This thesis is the result of a research project funded by the Geological Survey of Namibia on the "Tectonic setting of the Kuiseb Formation in the south-western part of the Damara Orogen, Namibia". I am grateful to my supervisor Dr. I. G. Stanistreet for his encouragement, his great support and his neverending willingness for discussions. Special thanks are extended to Prof. M. Okrusch of the Mineralogy Institute of the University of Würzburg/Germany for his offer to take up this project, for his challenging criticism and for his great support during my research leaves to his department. He is also thanked for the application to the Deutsche Forschungsgemeinschaft (DFG) which provided additional funds. The Foundation for Research Development (FRD) is also thanked for additional funds. I thank Dr. K. J. Maiden for the original initiation of this project.

Special thanks are extended to Dr. E. G. Charlesworth of the University of the Witwatersrand for his enthusiastic supervision of the structural geology.

The work has benefited from discussions with Prof. T. S. McCarthy, Dr. F. M. Meyer, Dr. T. Wallmach, Mr. A. B. Cadle, Mr. G. Henry, Mr. S. Master, Mr. R. Boer and Ms. G. Drennan, all members of the Department of Geology, University of the Witwatersrand. This department is also thanked for logistical and financial support and for the use of in-house facilities.

The project has much benefited from discussions with Prof. M. Okrusch, Mr. H. Häussinger, and Mr. R. Böhn at the Mineralogy Institute, University of Würzburg. Mr. H. Häussinger is thanked for providing a computer-program which helped to process microprobe analyses. Prof. P. Richter and Mrs. R. Baur are thanked for their support during geochemical studies at this department, and Dr. U. Schüssler is thanked for his assistance during the microprobe analyses. Many thanks to Mrs. A. Kirchner for her administrative assistance.

Special thanks to Dr. R. McG. Miller of the Geological Survey of Namibia for his generous support during the field work and the fruitful discussions. I am also thankful for the discussions and field trips with Mr. R. Swart, Mr. K. H. Hoffmann, Dr. B. Hoal and Dr. J. D. Ward of the survey and their technical staff is thanked for supplying logistic support.

Prof. B. T. Verhagen of the Schonland Research Centre for Nuclear Sciences, University of the Witwatersrand, is thanked for the stable isotope analyses carried out in his laboratory.

The work has also benefited from discussions with Mr. D. Corbett and Mr. L. Kruger, Gold Fields Namibia, Mr. R. Schneeweiss, Rössing Uranium Ltd., and Dr. T. Smalley. Many thanks go to Dudley Corbett for the dedication of his "calc-silicate song", developed on the fire over long thoughts on the Kuiseb schists.

Special thanks are addressed to the Larner families in the Khomas Hochland whose hospitality and support were fabulous. In particular Hardus and Anita Myburgh (Okasume), Mr. and Mrs. Jacob (Kaan Dam), Mrs. Johnston (Kaan) and Dieter Langner (Keises) are thanked for their friendship.

Thanks also to Ms. J. Wilmot for her administrative help, to Mrs. N. Day for her assistance in providing the geochemical data, to Mrs. L. Whitfield for the line drawings and to Mr. M. Hudson for the photographic work. Messrs. M. Miles, C. J. M. Kitching, A. Mathebula and the late Mr. J. Molotsi are thanked for technical support and the preparation of thin and polished sections.

I am deeply indebted to my wife and "colleague" Christine for her great scientific and moral support during this project, and for always being a cheerful partner during our joint field work in the Khomas Hochland which also included heat, frost, flash floods and beautiful wildlife.

CONTENTS

	Page
Abstract	II
Acknowledgements	VI
Contents	IX
List of tables	XIV
List of figures	XV
 1. INTRODUCTION	 1
1.1 Preamble	1
1.2 Location	2
1.3 Objectives of study	3
1.4 Previous work	4
1.5 Methods of investigation	6
 2. GEOLOGICAL SETTING	 9
2.1 Pre-Damara Basement	11
2.2 Stratigraphy of the Damara Sequence and its radiometric ages	13
2.2.1 Overview of the Damara Stratigraphy	13
2.2.2 Stratigraphy of the Central Zone and the Southern Margin Zone	16
2.2.3 Stratigraphy of the Khomas Trough	21
2.3 Deformation, crustal structure and metamorphism of the Damara Sequence	24
 3. SEDIMENTOLOGY	 28
3.1 Introduction	28
3.2 Description of lithotypes	28
3.2.1 Quartz-plagioclase-mica schist (psammite)/ greywacke	28

	Page
3.2.2	Mica-quartz-plagioclase schist (pelite and metasilstone)/mudstone and siltstone 29
3.2.3	Graphitic mica-quartz-plagioclase schist/ carbonaceous mudstone 29
3.2.4	Marble and tremolite schist/carbonate 30
3.2.5	Calc-silicate rock/impure carbonate 30
3.3	Geochemical characterization of psammites, pelites and metasilstones 31
3.4	Sedimentary structures and palaeocurrents 36
3.5	Turbiditic and pelagic facies 45
3.5.1	Medium- to very thick-bedded psammite facies (facies class 1) 47
3.5.2	Very thick- to thin-bedded graded psammite/pelite facies (facies class 2) 50
3.5.3	Thin-laminated metasilstone facies (facies class 3) 54
3.5.4	Very thick- to thin-bedded pelite facies (facies class 4) 55
3.5.5	Impure metacarbonate facies (facies class 5) 57
3.5.6	Thin- to very thick-bedded graphite schist facies (facies class 6) 61
3.5.7	Marble and tremolite schist facies (facies class 7) 66
3.6	Vertical facies sequences and sedimentary cycles 69
3.7	Facies models 79
3.8	Depositional setting of the Khomas Trough 81
3.8.1	Previous sedimentation models 81
3.8.2	Geochemical constraints on the source area of Kuiseb metagreywackes 82
3.8.3	Interpretation of elongate submarine fan and basin plain depositional environments 85

	Page
3.8.4 Discussion of other possible depositional environments	91
3.9 Palaeoenvironmental synthesis	92
4. STRUCTURAL GEOLOGY OF THE KHOMAS TROUGH	99
4.1 Introduction	99
4.2 Structural characteristics of domains	101
4.2.1 Domain A	105
4.2.2 Domain B	111
4.2.3 Domain C	122
4.2.4 Domain D	131
4.2.5 Late fractures	137
4.3 Contact relationships of metasediments and migmatites with the Donkerhoek Granite	137
4.4 The recognition of heterogeneous strain and thrusting	141
4.4.1 Heterogeneous strain	141
4.4.2 Major high-strain zones	141
4.4.3 Summary and conclusions	156
4.5 Kinematic interpretation and time sequence of deformational events	160
4.5.1 D ₁ phase of deformation	161
4.5.2 D ₂ phase of deformation	162
4.5.3 D ₃ phase of deformation	164
4.5.4 Later phases of deformation	165
4.5.5 Strike-slip displacement along the northern margin of the Khomas Trough	166
4.5.6 Aspects of strain determinations	167

	Page
4.5.7 Consideration of previous studies: a correlation of deformation events in the Khomas Trough	171
4.6 Structural evolution of the Khomas Trough fold-and-thrust belt	173
5. THE MATCHLESS AMPHIBOLITE	176
5.1 General setting of the Matchless Amphibolite	176
5.2 Lithologies, mineral assemblages and textures	177
5.3 Stratigraphic and structural relationships	181
5.3.1 Stratigraphy	181
5.3.2 Structure	183
5.4 Classification of metabasic rocks	189
5.5 Tectonic setting of the Matchless Amphibolite with special regard to the development of the Khomas Trough	195
6. METAMORPHISM	200
6.1 Introduction	200
6.2 Mineral textures and relationships to structural elements	200
6.2.1 Pelites	201
6.2.2 Calcareous lithologies	209
6.3 Mineral assemblages	210
6.4 Mineral compositions	219
6.5 The P-T evolution of metamorphism	223
6.5.1 Qualitative estimation of P-T conditions	223
6.5.2 Geothermometry and geobarometry	228
6.5.3 Summary of the P-T conditions in the Khomas Trough	233

	Page
7. TECTONICS AND SEDIMENTATION OF A LATE PROTEROZOIC CONVERGENT CONTINENTAL MARGIN	237
7.1 Previous geodynamic models for the evolution of the inland branch of the Damara Orogen	237
7.2 The tectono-sedimentary evolution of the Khomas Trough	239
7.2.1 Rifting and spreading phase	239
7.2.2 Early subduction phase	241
7.2.3 Accretion phase	243
7.2.4 Collision phase	247
7.2.5 Ancient and modern analogues	252
8. REFERENCES	255
APPENDIX I (XRF-analyses of metasediments)	276
APPENDIX II (XRF-analyses of metabasites)	280
APPENDIX III (microprobe-analyses)	281
APPENDIX IV (list of candidate's publications)	286

LIST OF TABLES

	Page
2.1. Lithostratigraphy of the Damara Sequence	13
2.2. Lithostratigraphy of the Southern Margin Zone	17
3.1. Average geochemical compositions of psammites and pelites of the Kuiseb Formation	32
3.2. Stable isotope data for graphite schists and marble in the Khomas Trough	63
3.3. Comparison of chemical compositions of Kuiseb greywackes with greywackes from various tectonic settings	83
3.4. Comparison of tectonic settings, sizes, thicknesses and shapes of modern and ancient submarine fans	98
4.1. Summary of planar fabrics and folds encountered in domains A-D along the study traverse	102
4.2. Comparison of the structural subdivision of the study traverse in this study and an earlier study of Kukla et al. (1988)	104
4.3. Summary of the symbols used for various structural elements	106
4.4. Compilation of strain data derived from deformed pillow structures of the Matchless Amphibolite	169
4.5. Proposed correlation of deformation phases of various studies in the Khomas Trough	172
6.1. Modal compositions of selected pelites, scapolite schists and psammites of the Khomas Trough	202
6.2. Relative timing of deformation phases and metamorphic crystallization in the western Khomas Trough	204
6.3. Geothermometric and geobarometric data	230

LIST OF FIGURES

	Page
1.1. Location of the study area	3
1.2. Detailed location of the study traverse	7
2.1. Map of Pan-African orogenic belts	10
2.2. Tectono-stratigraphic zones of the Damara Orogen	12
2.3. Rock relationships of the Khomas Trough and adjacent areas	18
2.4. Landsat image of the central and western Khomas Trough	23
3.1. Geochemical variation diagrams of major elements (A) and minor elements (B) against Zr	33/34
3.2. Geochemical grid for clastic sedimentary protoliths	36
3.3. Sedimentary measured sections	38/39
3.4. Photographs (A-F) of sedimentary structures	41
3.5. Photographs (A-D) of sedimentary structures	43
3.6. Rose diagram showing palaeocurrent data	44
3.7. Summary of the turbidite facies classification	47
3.8. Photographs (A-F) showing turbidite facies	52
3.9. Photographs (A-E) showing turbidite facies and pelagic facies	60
3.10. $\delta^{13}\text{C}$ (A) and $\delta^{18}\text{O}$ (B) stable isotope data	65
3.11. $\delta^{13}\text{C}$ (A) and $\delta^{18}\text{O}$ (B) stable isotope data	68
3.12. Sedimentary measured sections along the study traverse showing facies distribution	70
3.13. Sedimentary measured sections	72/73
3.14. Photographs (A-D) of facies sequences	74
3.15. Map of major sedimentary cycles and non-cyclic sequences in relation to marker units	76

	Page
3.16. Photographs (A-G) showing sedimentary cycles	78
3.17. Major element plot (K_2O/Na_2O versus SiO_2) distinguishing tectonic provenances	84
3.18. Map (A) and schematic profile (B) of depositional palaeoenvironments in the Khomas Trough	89
3.19. Palaeoenvironmental model of the Khomas Trough	94
3.20. Map of ancient and modern submarine fan systems	97
4.1. Map of geographical locations of structural domains A-D	103
4.2. Structural profile across the Khomas Trough	105
4.3. Structural data of domain A	108
4.4. Microtextures in domain A	109
4.5. Photograph of D_5 kink band in domain A	111
4.6. Structural data of domain B	112
4.7. Photographs (A-F) of fabrics and folds in domain B	114
4.8. Microtextures and folding in domain B	115
4.9. Map and data of D_2 downward-facing localities	118
4.10. Map and sketches of downward-facing structures	119
4.11. Sketch of large-scale D_2 folding in domain B	121
4.12. Structural data of domain C	123
4.13. Photographs (A-G) of planar fabrics and folds in domain C	125
4.14. Sketch, photograph and stereoplot of open asymmetric D_2 fold in domain C	126
4.15. Sketch, photograph and stereoplot of open asymmetric D_2 fold in domain C	128
4.16. Sketch, photograph and stereoplot of tight to isoclinal SE verging D_2 folds	129
4.17. Structural sketches (A-E) showing D_2 and D_3 features of the southern scapolite schist	130

	Page
4.18. Structural data for domain D	132
4.19. Photographs (A-F) of planar fabrics and folds in domain D	134
4.20. Structural profile of style of folding in the southern part of domain D	136
4.21. Photographs (A-F) of contact relationships between metasediments, migmatites and granitic phases	139
4.22. Structural profile across the Khomas Trough	142
4.23. Photographs (A-D) of high-strain zones in the southern Khomas Trough	143
4.24. Structural data of the Matchless Amphibolite	145
4.25. Photographs (A-D) of shearing and thrusting at the Matchless Amphibolite	146
4.26. Pre-D ₂ thrust fault in domain B	147
4.27. Model for the development of downward-facing structures	149
4.28. Geological features of the graphite schist in the centre of the Khomas Trough	151
4.29. Shearing and thrusting at the southern scapolite schist occurrence	153
4.30. Structural profile across the northern scapolite schist occurrence	154
4.31. Photograph (A) and stereoplot (B) of D ₃ shear zone	156
4.32. Strain measurements of pillow structures shown in Flinn diagram	170
5.1. Photographs (A-H) of geological features of the Matchless Amphibolite	179
5.2. Map and detailed measured sections of the Matchless Amphibolite	182
5.3. Structural data of the Matchless Amphibolite	184
5.4. Detailed measured section of the Matchless Amphibolite	185

	Page
5.5. Profile of décollement zone in the lower part of the Matchless Amphibolite	186
5.6. Sketch of structural interposition of sheared metagabbros, amphibolites and chlorite schists	187
5.7. Post-D ₂ thrusting within pillow lava sequence	188
5.8. Variation diagram K ₂ O + Na ₂ O versus SiO ₂	190
5.9. Variation diagram TiO ₂ versus Zr	191
5.10. Variation diagram SiO ₂ versus Cr	192
5.11. Triangular variation diagram Ti-Zr-Y	193
5.12. Variation diagram Zr/Y versus Zr	194
6.1. Photographs (A-H) of lithologies, mineral textures and deformational features	208
6.2. Map of metamorphic assemblage zones and sample localities	211
6.3. P-T diagram showing stability fields and mineral assemblages for assemblage zones (1) to (4)	214
6.4. Photographs (A-H) showing mineral assemblages	218
6.5. Scapolite compositions	223
6.6. P-T diagram of scapolite stability conditions	226
6.7. Petrogenetic grid for the KFMASH system	232
7.1. Palaeoenvironments during early continental convergence	242
7.2. Tectonic setting during accretion	244
7.3. Palaeoenvironments during late continental convergence	247
7.4. Tectonic setting during continental collision	248

1. INTRODUCTION

1.1 Preamble

Geoscientific investigations in Precambrian orogenic belts are seriously hampered by penetrative deformation, metamorphic recrystallization and the lack of biostratigraphic control. In metasedimentary sequences this may result in the obliteration of delicate sedimentary structures which are essential for palaeoenvironmental interpretations. Consequently, sedimentary facies analysis, which provides together with structure and other geoscientific approaches one of the most important tools in looking into the evolution of these orogenic belts, has not been undertaken in many Precambrian orogens.

The Damara Orogen is one of the best preserved Late Proterozoic orogenic belts worldwide and therefore crucial for the understanding of later Precambrian tectonics. Nevertheless, palaeoenvironmental studies in this belt and especially in the important southern part have so far mainly concentrated on stratigraphic aspects. In this respect the Damara Orogen is no different from other Precambrian belts. In acknowledging this problem this study introduces a sedimentary facies analysis to this area and together with results obtained from other geoscientific disciplines attempts a multidisciplinary approach to provide an insight into the evolution of the orogen as a whole.

1.2 Location

Rocks assigned to the Late Proterozoic Damara Sequence in Namibia are exposed within a NNW-trending coastal branch and a NE-trending inland branch (Fig. 1.1). The Khomas Trough of the southern inland branch extends from the Namib desert in the south-west to the Kalahari desert in the north-east. Figure 1.1 shows important geographical features including the Khomas Hochland. The Late Proterozoic Damaran rocks are well exposed at the western end of the Khomas Hochland which represents the immediate interior of the "Great Escarpment" originating from erosional processes (Ward, 1987) associated with the Cretaceous breakup of Gondwanaland. This area consequently provides good surface exposure whereas the outcrop situation deteriorates rapidly towards the east because of the undissected flat erosional topography associated with the Cretaceous Kalahari basin (Fig. 1.1).

The main study area is a north-south trending traverse near the Great Escarpment about 120 kilometres west of Windhoek (Figs. 1.1 and 1.2). Access to the outcrops is via auxiliary gravel farm roads or by foot from the nearest farm road.




Fig. 1.1: Location of the study area in the inland branch of the Damara Orogen in Namibia.

1.3 Objectives of study

The Late Proterozoic Khomas Trough comprises metasedimentary and metabasic rocks of the Kuiseb Formation and its evolution plays an important role in our understanding of the Damara orogenic belt as a whole. The present study attempts to characterize the metasedimentary and metabasic rocks encountered by means of

sedimentological, structural, petrographical, mineralogical and geochemical methods. This leads to the modelling of the geotectonic evolution of the Khomas Trough with particular focus on the sedimentary palaeoenvironments and the structural evolution of this area during the Pan-African orogeny in Namibia.

1.4 Previous work

Pioneering publications on the geology of the Khomas Trough are those of Gevers (1963) and Martin (1965). Lithostratigraphic aspects of the Kuiseb Formation in the Khomas Trough have been catalogued by the South African Committee for Stratigraphy (SACS, 1980), Miller (1983b) and by Hoffmann (1983). Structural studies in parts of the eastern Khomas Trough were undertaken by Gevers (1963), Smith (1965), Hälbig (1970, 1977), Porada and Wittig (1975), Kasch (1975, 1983c) and Blaine (1977). Miller (1979), Sawyer (1981, 1983) and Preussinger (1987, 1990) studied the structural geology of selected areas in the western Khomas Trough and in the vicinity of the Okahandja Lineament. No detailed facies analysis of the Kuiseb Formation has been undertaken in this part of the southern Damara Orogen prior to this study although preserved sedimentary features (e.g. graded bedding) have been reported from limited areas by Miller (1979), Downing (1983) and Preussinger et al. (1987). Initial studies on the thermal evolution of the Damara Orogen as a whole have been undertaken by Hoffer (1977, 1983), Behr et al. (1983) and Hartmann et al. (1983). Sawyer (1981), Kasch (1983b, 1987) and

Preussinger (1990) studied the metamorphism of certain areas in the western and eastern Khomas Trough. Geochemical studies of metasediments and amphibolites have been undertaken by Miller et al. (1983), Schneider (1983), Schmidt and Wedepohl (1982), Breitskopf and Maiden (1987) and Phillips et al. (1989). The nature of the massive sulphide deposits associated with the Matchless Member of the Kuiseb Formation has been studied by Killick (1983), Klemm et al. (1987, 1989), Breitskopf and Maiden (1988), Preussinger (1990) and Klemm and Okrusch (1990). Little geochronological work has been undertaken and this has mainly concentrated on the post-tectonic Donkerhoek Granite and the Kuiseb Formation migmatites (Kröner and Hawkesworth, 1977; Blaxland et al., 1979; Kukla, Kramm et al., 1990; Kukla, in prep.) as well as on some metasediments (Hawkesworth et al., 1983; Haack, 1983; Kukla, in prep.). Kröner (1982) obtained a Rb/Sr isochron from rocks associated with the Matchless Member. A seismic line has been shot and interpreted by Green (1983) and Baier et al. (1983) in the eastern Khomas Trough.

Geotectonic models for the evolution of the Damara Orogen as a whole which incorporate the Khomas Trough have been proposed by several authors. In summary, the discussion on the geodynamic evolution of the inland branch has concentrated on whether or not oceanic crust has formed, to be subsequently subducted during continental convergence. Aulacogen-related models have been favoured by Martin and Porada (1977), Porada (1983) and Kröner (1982). Limited ocean models have been proposed by Miller (1986).

and Breitskopf (1986) and major ocean models by Blaine (1977), Hartnady (1978), Kasch (1979, 1983a), Barnes and Sawyer (1980) and Downing and Coward (1981).

1.5 Methods of investigation

The main study area is a 80 km long traverse along ephemeral river valleys (Kaan, Amsas, Koam and Davetsaub rivers) north to south across the Khomas Hochland west of Windhoek (Fig. 1.2). Only the deeply incised river beds associated with the Khomas Hochland Escarpment provide detailed outcrop. Outside these exposure is obscured by weathering and gravel cover. In order to trace important stratigraphic and structural marker horizons these have been mapped along strike from the Namib desert in the west into the Khomas Hochland further east. Important information of large scale structures has additionally been obtained from Landsat images and aerial photographs.

To gain further regional constraints, the field areas of Sawyer (1981) and Preussinger (1987) in the Gorob district of the Namib desert as well as the Okahandja - Windhoek profile of Hälbich (1977) have been studied for comparison.

In order to unravel the sedimentological and structural evolution of the Kuiseb Formation, a large number of detailed profiles and sequences were measured along the 80 km long study traverse. Since no work on the sedimentology and the depositional palaeo-

environments has been undertaken previously, lithotypes were mapped and characterized, original sedimentary structures were documented and a detailed facies analysis was carried out.




Fig. 1.2: Map of the study traverse showing important marker units, major ephemeral rivers and farm boundaries.

A large number of structural data were collected. These were processed together with thin section information in order to interpret the structural evolution and associated compressional directions.

A total number of 132 samples of metasediments and 14 samples of amphibolites and metagabbros were analysed by X-ray fluorescence (XRF) analysis for major and trace elements. A sample of marble was analysed by X-ray diffraction (XRD) to identify calcite and dolomite contents.

Mineralogical and petrographic studies were based on about 200 thin sections. Selected samples from different metamorphic zones were chosen for microprobe analyses which were carried out during research leave at the Mineralogy Institute of the University of Würzburg, Germany.

With regard to the origin of the graphite schists and a marble horizon of the Kuiseb Formation several samples were analysed for carbon (C^{13}) and oxygen (O^{18}) isotope contents at the Schonland Research Centre for Nuclear Sciences at the University of the Witwatersrand.

2. GEOLOGICAL SETTING

The Damara Orogen forms part of the Pan-African mobile belt system (Clifford, 1967; Shackleton, 1976; Miller, 1983a; Martin, 1983) which largely surrounds but also dissects the African continent (Fig. 2.1). Two structural types of Pan-African belts have been recognized: (1) belts with thermally and tectonically rejuvenated, older Precambrian basement suggested for the cases of the Zambezi and Mozambique Belts (Martin, 1983; Muhongo, 1990); and (2) Late Proterozoic "geosynclines" which have passed through a stage of subsidence and sediment accumulation. The Damara Orogen belongs to the latter type. It consists of a NNW-trending, 150 km wide coastal branch and a NE-trending, 400 km wide inland branch (Figs. 2.1 and 2.2). Most of the geological research has concentrated on the more easily accessible and more completely preserved inland branch.

The southern extension of the Damara Orogen is formed by the Gariep Belt and the Malmesbury Belt (Fig. 2.1; Miller, 1983b; Hartnady et al., 1985). Geophysical features suggest that the inland branch extends further to the east into the Katanga and Zambezi Belts (Reeves, 1978; Hartnady et al., 1985) to form a triple junction with the Mozambique Belt in eastern Africa (Fig. 2.1). It has been suggested that the western limit of the Damara Orogen is represented by the Ribeira Orogen of Brazil (Peada, 1979) but regional and geochronological constraints also indicate that the more southerly Dom Feliciano Belt may be regarded as

Damara equivalent (Cordani et al., 1990).




Fig. 2.1: Pan-African orogenic belts and terranes of basement rejuvenation (modified from Porada, 1983).

The Damara Orogen has been subdivided into several tectono-stratigraphic zones mainly on the basis of stratigraphy, structure, metamorphic grade, magmatic rocks and radiometric age (Miller, 1983a). These are from north to south (Fig. 2.2): the Kaoko Zone (KZ) (in the coastal branch), the Northern Platform (NP), Northern Zone (NZ), Central Zone (CZ), Okahandja Lineament Zone (OLZ), Southern Zone (SZ), Southern Margin Zone (SMZ) and Southern Foreland (SF) in the inland branch. The OLZ and SZ are together often referred to as the Khomas Trough (e.g. Martin, 1965; Martin and Porada, 1977), a terminology which is also used in this study. Zone boundaries are in most cases major thrusts, faults and lineaments as indicated in Figure 2.2.

2.1 Pre-Damara Basement

The pre-Damara basement is largely granitic and is exposed to the north and south of the orogen as well as in several inliers in the centre (Fig. 2.2). Radiometric ages are very variable, however, showing the oldest ages in the order of 2000 Ma in the Central Zone (1955 $\pm$ 20 Ma representing U-Pb zircon dates by Briquet et al., 1980) and the youngest ages in the order of 1000 Ma in the southern part of the orogen (961 $\pm$ 23 Ma representing a Rb/Sr whole rock date of Esquevin and Menendez, 1975 in the eastern Khomas Trough; 1049 $\pm$ 28 Ma Rb/Sr whole rock date of Pfurr et al., 1990 in the Southern Margin Zone).




Fig. 2.2: Tectono-stratigraphic zones of the Damara Orogen (from Miller, 1983b).

2.2 Stratigraphy of the Damara Sequence and its radiometric ages

2.2.1 Overview of the Damara Stratigraphy

The stratigraphy in the inland branch shows a marked asymmetrical arrangement of rock types. This is indicated in Table 2.1 which shows subdivisions and correlations as suggested by the South

Table 2.1: Lithostratigraphy of the Damara Sequence (from Martini, 1983, based on SACS, 1980).

NORTH				CENTRE				SOUTH			
GROUP	SUBGROUP	FORMATION	LITHOLOGY (MAX. THICKNESS)	GROUP	SUBGROUP	FORMATION	LITHOLOGY (MAX. THICKNESS)	GROUP	SUBGROUP	FORMATION	LITHOLOGY (MAX. THICKNESS)
MULDEN		OWANING	Shale, mud, silstone, sandstone (1000 m)					NAMA GROUP PARTIALLY ?			
		SONGAM	Shale dolomite lenses								
		YONKHA	Quartzite, conglomerate, arkose, argillite (2000 m)								
UNCONFORMITY IN NW											
OTAVI	TSONGAS	HUTTENBERG	Dolomite with chert shale, limestone, stromatolite, dolite (600 m)	KHOMAS	KARIBIB	KARIBIB	Quartz-biotite schist, biotite-garnet-coniferite schist, amphibole schist, quartzite, marble, calcareous rock (3000 m)	KHOMAS	KUSUBA	KUSUBA	Biotite schist, biotite-quartzite, graphitic schist, calcareous rock, amphibolite (metachess member) (10000 m)
		BLANDS-HOLE	Dolomite with chert stromatolite (1100 m)			KARIBIB	Marble, biotite schist, quartz schist, calcareous rock (700 m)			AUAS	Quartzite, schist, marble, amphibolite, metabasite (1800 m)
		ALAREMBO	Dolomite, limestone, slump breccia (950 m)			CHROG	Mudite, marble, quartzite (700 m)			CHROS	Pebbly schist, mudite, quartzite, schist, metabasite, amphibolite, calcareous rock (1850 m)
		CHIKOS	Mudite dolomite, limestone, sandstone, metabasite, dolite chert (700 m)								
	LOCAL DISCORDANCE			LOCAL DISCORDANCE				EUPH	? HAROS	BLAU-KRANS	Graphitic schist, quartzite, quartzite schist, conglomerate, metabasite (1700 m)
	AREHAB	AREHAB	Dolomite, limestone, rock, shale (450 m) stromatolite	UGAB	AC16HNC		Marble, quartzite, conglomerate, biotite schist, biotite-hornblende schist, calcareous rock (700 m)				Quartzite schist (2000 m)
		GAUSE	Dolomite, limestone, dolite chert, sandstone (750 m)								
		REED AUAS	Dolomite, limestone, stromatolite, arkose, greywacke (525 m)							CORONA	Dolomite schist, conglomerate (500 m)
	LOCAL DISCORDANCE			LOCAL DISCORDANCE				LOCAL DISCORDANCE			
	NOSIB		VANANTO	Mudite, full, metabasite	NOSIB		KHAN	Calcareous rock, amphibolite-gneiss gneiss and quartzite (1100 m)	NOSIB		PUMP-CHAUS
		ATKAYOLD	Rhyolite, full, agglomerate, andesite, apodolite, basaltite (5000 m)			ETUSIB	Quartzite, arkose, conglomerate schist, rhyolite (3500 m)			KANZAS	Quartzite, arkose, conglomerate (5700 m)
		HABE	Quartzite, arkose, conglomerate								

African Committee for Stratigraphy (SACS, 1980). Most important in interpreting the Damara Sequence is the occurrence of a number of unconformities which define several unconformity-bound sequences within the stratigraphic column (Table 2.1).

The earliest sediments and volcanic rocks of the Damara Sequence belong to the Nosib Group (Table 2.1) which discordantly overlies pre-Damara basement. The Nosib Group comprises a wide spectrum of mainly fluviatile deposits and alkalic to acid volcanic rocks. Thick and widespread rhyolites of the Naauwpoort Formation in the Northern Zone are considered to represent a time marker for the early evolution, i.e. rifting, of the orogen (Miller, 1983b) at 750 ± 65 Ma (U-Pb zircon ages, Miller and Burger, 1983). The initiation of rifting is considered by Miller (1983b) to pre-date the Oas Syenite which intruded Nosib sediments at 840 ± 12 Ma (Rb-Sr whole rock age, Kröner, 1982). The sequences of the Nosib Group show rapid changes in rock types and depositional facies within and across tectono-stratigraphic zones (Table 2.1).

The Nosib Group is unconformably overlain by the Otavi Group in the north and the Swakop Group in the centre and south (Table 2.1). The Abenab, Ugab and Kudis Subgroups still show a considerable variety of rock types and facies. Calcareous sequences predominate in the north and more clastic sequences in the south (Table 2.1). The unconformity at the base of the Chuos Formation is of regional importance and this formation is the most

important chronostratigraphic marker within the orogen (Tables 2.1 and 2.2). Above the Chuos unconformity sedimentary sequences are much more coherent and laterally extensive. Thick carbonates are developed in the north (Tsumeb Subgroup), thinner carbonates with some amphibolites and clastics in the centre (Khomas Subgroup of the Central Zone) and mostly clastic sequences with some amphibolites in the south (Khomas Subgroup of the Southern and Southern Margin Zones).

The Otavi Group is unconformably overlain on the Northern Platform by thick clastic sediments of the Mulden Group (Miller, 1983b). Carbonate and mixed clastic-carbonate sequences of the zones further south are overlain by clastic sediments of the Khomas Subgroup which represents the youngest stratigraphic unit (Table 2.1).

There are few geochronological constraints on the depositional history of the Damara Sequence. Most radiometric ages have been derived from pre-, syn-, and post-tectonic magmatic rocks, mostly granite intrusions. Mineral dates from metasedimentary rocks give a spectrum of "ages" from about 530 to <200 Ma reflecting metamorphic processes and isotopic re-equilibrations (e.g. Miller, 1983b; Miller and Grote, 1988; Haack and Martin, 1983; Kukla, in prep.). Damaran sediments have been intruded by post-tectonic granites and the Rb-Sr whole rock age of 458 ± 8 Ma (Kröner and

Hawkesworth, 1977) of the youngest of these intrusions, the Rössing alaskite in the Central Zone, is considered to mark the end of the Pan-African events in Namibia (Miller, 1983b).

2.2.2 Stratigraphy of the Central Zone and the Southern Margin Zone

The Khomas Trough of the Damara Sequence is framed to the north by the Central Zone and to the south by the Southern Margin Zone (Fig. 2.2; Table 2.2). A rock relationships diagram illustrates the local stratigraphies within the tectono-stratigraphic framework of the southern Damara Orogen (Fig. 2.3). The stratigraphy of the Southern Margin Zone is based on Hoffmann (1983) who has revised the SACS (1980) stratigraphy subsequent to detailed mapping in this area (Table 2.2). To underline important stratigraphic changes, time-equivalent sequences are described across the zones in the following. The sequences are unconformity-bound and the important chronostratigraphic marker is the Chuos Formation of the Swakop Group.

(a) The Nosib Group

In the Central Zone, sediments of the Nosib Group rest unconformably on Abbabis basement gneisses, schists, amphibolites and marbles (Smith, 1965) with an approximate age of 2000 Ma (Briqueu et al., 1980). Extensive fluviatile deposits of the Etusis Formation are represented by metamorphosed quartzites, arkoses and conglomerates (Fig. 2.3) which underlie and interfinger with

feldspathic quartzites and quartz-biotite schists of the Khan Formation (Smith, 1965; Jacob, 1974).

In the Southern Margin Zone (Fig. 2.3), quartzites, arkoses and conglomerates of the Kantsas Formation were deposited on about 1050 Ma old basement gneisses and amphibolites. The basement close to the boundary with the Khomas Trough has been structurally emplaced and contains serpentinite bodies (Barnes, 1982).

Table 2.2: Comparison of lithostratigraphic classifications of the Southern Margin Zone by Hoffmann (1983) and SACS (1980), (from Hoffmann, 1983).

HOFFMANN (1983)			SACS (1980) SWA GEOLOGICAL MAP (1980)		
GROUP	SUBGROUP	FORMATION	GROUP	SUBGROUP	FORMATION
SWAKOP	KHOIASI	KUSEB	SWAKOP	KHOIASI	KUSEB
		KLEINE KUPPE			AUAS
	VAALGRAB	GOMAB RIVER			
		MAHONDA			
		MELROSE			
		CHUOS			CHUOS
	KUDIS	HAKOS and AUAS		KUDIS	BLAURANS
		BLAURANS			HAKOS
		CORONA			CORONA
NOSE		KANTSAS and DURUCHAUS	NOSE		KANTSAS and DURUCHAUS

1: Allochthonous nappes
2: Paratechthonic Senne-Diepsiek Thrust Zone




Fig. 2.3: Rock relationships of the Khomas Trough and adjacent areas in the Damara Orogen. Stratigraphic contacts are emphasised in their palinspastic context. Correlations and terminology of the Southern Margin Zone and the southern and northern Central Zone are after Hoffmann (1983), Henry et al. (1990) and Badenhorst (1987) respectively.

As a facies of the Kamtsas Formation, the Duruchaus Formation (Martin, 1965; Hälbig, 1970; Schalk, 1970) comprises fine-grained psammites, pelites, carbonates, meta-evaporites and some conglomerates (Löffler and Porada, 1987; Hoffmann, 1987) and it

has been interpreted to represent playa-sabkha type, lacustrine (Behr et al., 1983) as well as fluvial (Löffler and Porada, 1987) deposits.

(b) The Swakop Group

This Group has been subdivided into the Ugab and the Khomas Subgroups in the Central Zone which have been correlated with the Kudis and the Vaalgras + Khomas Subgroups of the Southern Margin Zone respectively (Hoffmann, 1983; Tables 2.1 and 2.2). The only stratigraphic unit in the Khomas Trough is the Kuiseb Formation of the Swakop Group (Fig. 2.3).

Both the Ugab and Kudis Subgroups are characterized by a considerable lithological variability. The former contains dolomite, quartzite, quartz-biotite schist, calc-silicate rocks, gneisses and amphibolites of the Rössing Formation in the Central Zone (Fig. 2.3). The time-equivalent Kudis Subgroup of the Southern Margin Zone comprises marbles (Corona Formation), quartz-mica schists and graphite schists (Blaukrans Formation), interbedded quartzites and graphite schists (Hakos Formation), and thick quartzites with interbedded graphite layers of the Auas Formation. This succession has been interpreted by Hoffmann (1983) to represent progressively deepening marine environments.

The Khomas Subgroup in the Central Zone comprises the Chuos, Karibib, Tinkas and Kuiseb Formations (Fig. 2.3). The Chuos Formation has long been recognized and was interpreted early on

as being glacial in origin (Gevers, 1931). It shows a major discordance at its base and Henry et al. (1986) report that Chuos metasediments rest in places on Khan, Etusis and basement rocks. Rock types developed are mainly glacial diamictites and minor feldspar-quartzites, marbles and iron formations (Henry et al., 1986; Badenhorst, 1987). The overlying shelf sequence of the Karibib Formation consists predominantly of dolomitic marble; schist and marl are subordinate. Towards the Khomas Trough the Karibib marbles interfinger with calc-silicates and fine-grained graphitic schists of the Tinkas Formation which outcrops along the Okahandja Lineament in the south-western Central Zone. Porada and Wittig (1983) have interpreted this succession as calcareous slope turbidites. An amphibolitic unit has been described from stratigraphic positions within the Karibib Formation (Smith, 1965) and the Tinkas Formation just north of the Otjimbingwe Granite (De Kock, 1985). The uppermost unit in the Central Zone is the Kuiseb Formation which comprises pelites, metagreywackes and calc-silicates.

The Khomas Subgroup of the Southern Margin Zone has been subdivided by Hoffmann (1983) into the Vaalgras Subgroup comprising the Chuos, Melrose, Mahonda, Gomab River and Kleine Kuppe Formations which are structurally overlain by Khomas Subgroup sediments (Tables 2.1 and 2.2). The Chuos Formation in this zone has been used for correlation across the Khomas Trough. Hoffmann (1983) reports pebble-bearing, semi-pelitic, light grey mica schists, pelitic schists, quartzites, metabasic rocks and

iron formations which conformably overlies rocks of the Kudis Subgroup. This is in contrast to the unconformity in this position suggested by SACS (Table 2.2; 1980). The Melrose Formation consists of green garnet-chlorite schists and subordinate quartzites, calcareous schist and marble which occasionally interfinger with quartzites, schists, amphibolites and marbles of the Mahonja Formation. The Gomab River Formation occurs as a small unit at the northern boundary of the Southern Margin Zone. It comprises dark amphibole schist, minor mica schist and marble and the former "Red Band Quartzite" (De Kock, 1934; Hälbig, 1970) which has been named "Hartelust Rhyolite Member" by Miller (1983b). The Kleine Kuppe Formation consists of intercalated, thin-bedded micaceous quartzites and schists as well as occasional thin amphibolite bands. Hoffmann (1983) interprets the Vaalgras Subgroup to represent slope (Chuoss Formation) and ocean basin (Melrose and Kleine Kuppe Formations) deposits. Contacts with the overlying Kuiseb Formation pelites and metagreywackes are structural.

2.2.3 Stratigraphy of the Khomas Trough

In the study area, the Khomas Trough is bordered to the north by the post-tectonic Donkerhoek Granite (Fig. 2.4). Further to the west, however, Porada and Wittig (1983) have established an interfingering of the metasediments with the Tinkas Formation of the Central Zone (Fig. 2.3). The only formal stratigraphic unit in the Khomas Trough is the Kuiseb Formation of the Swakop Group

iron Formations which conformably overlies rocks of the Kudis Subgroup. This is in contrast to the unconformity in this position suggested by SACS (Table 2.2; 1980). The Melrose Formation consists of green garnet-chlorite schists and subordinate quartzites, calcareous schist and marble which occasionally interfinger with quartzites, schists, amphibolites and marbles of the Mahonda Formation. The Gomab River Formation occurs as a small unit at the northern boundary of the Southern Margin Zone. It comprises dark amphibole schist, minor mica schist and marble and the former "Red Band Quartzite" (De Kock, 1934; Hälbich, 1970) which has been named "Hartelust Rhyolite Member" by Miller (1983b). The Kleine Kuppe Formation consists of intercalated, thin-bedded micaceous quartzites and schists as well as occasional thin amphibolite bands. Hoffmann (1983) interprets the Vaalgras Subgroup to represent slope (Chuos Formation) and ocean basin (Melrose and Kleine Kuppe Formations) deposits. Contacts with the overlying Kuiseb Formation pelites and metagreywackes are structural.

2.2.3 Stratigraphy of the Khomas Trough

In the study area, the Khomas Trough is bordered to the north by the post-tectonic Donkerhoek Granite (Fig. 2.4). Further to the west, however, Porada and Wittig (1983) have established an interfingering of the metasediments with the Tinkas Formation of the Central Zone (Fig. 2.3). The only formal stratigraphic unit in the Khomas Trough is the Kuiseb Formation of the Swakop Group

(Fig. 2.3). Rock types present are mainly metasediments such as metagreywackes, metasiltstones, pelites, graphite schists, scapolite schists, calc-silicates and a marble unit. Also part of the Kuiseb Formation is the Matchless Member (SACS, 1980), a 350 km long and up to 3 km wide zone (Miller, 1983b) of metamorphosed mafic volcanic and intrusive rocks which are interposed with the metasediments. Also associated with the Matchless Member are ultramafic lithologies (Barnes, 1982).

Mapping within the Khomas Trough has now shown that the sequence comprises several stratigraphic and structural marker horizons (Fig. 2.4). These are: (1) the Matchless Member, in this study referred to as the Matchless Amphibolite, which is associated with a graphite schist and a marble unit; (2) a thick pelitic unit north of the Matchless Amphibolite; (3) a graphite schist unit several tens of metres thick which is associated with a thin tremolite schist in the centre of the trough; and (4) two pelitic successions (several hundreds of metres thick) which have been scapolitized during late metamorphism (Fig. 2.4). The marker horizons are of regional importance since they may be traced for more than 150 kilometres laterally along strike. The Landsat image of the Khomas Trough confirms and emphasises this extreme lateral persistence of the markers (Fig. 2.4). It will be shown in Chapters 3 and 5 that these markers also designate the position of thrust-bound sequences.




Fig. 2.4: Landsat image of the central and western Khomas Trough showing lithological and structural marker units. Note their lateral extent (reproduced with permission of the Satellite Applications Centre of the CSIR).

Radiometric dating of Kuiseb Formation rocks in the Khomas Trough has mostly produced ambiguous results which is probably due to isotopic re-equilibration during regional metamorphism (Hawkesworth et al., 1983) leading for example to Rb-Sr whole rock ages in the order of 550 - 490 Ma (Hawkesworth et al., 1983; Kukla, in prep). A Rb/Sr whole rock date of 765 ± 37 Ma is listed by Hawkesworth et al. (1981) for the Matchless Amphibolite.

2.3 Deformation, crustal structure and metamorphism of the Damara Sequence

The Damara Sequence throughout the inland branch has been subjected to varying degrees of deformation involving folding, thrusting and faulting. As with the stratigraphic asymmetries, structural patterns also vary markedly across the orogen (Coward, 1983; Henry et al., 1990). Generally, deformation increases southwards from gently open, upright folds on the Northern Platform into tight, locally recumbent, northward verging folds and thrust in the Northern Zone (Frets, 1969; Miller, 1983b). Further south, complex interference patterns of upright to northerly and southerly inclined, tight and locally recumbent folds occur in the Central Zone (Smith, 1965; Jacob, 1974; Blaine, 1977; Sawyer, 1981; Coward, 1983; Miller, 1983b). Folds are tight to isoclinal and upright close to the Okahandja Lineament passing into south-eastward-verging, open and isoclinal folds in the Khomas Trough (Smith, 1965; Hålbich, 1977; Kukla et al., 1988). Several phases of deformation which are associated with

folding, thrusting, faulting and cleavage formation have been discerned within the Khomas Trough. Fold vergences are consistently to the south-east and axes generally trend north-east except at the Okahandja Lineament.

The Okahandja Lineament (Fig. 2.2) is a monoclinal downfold of the Damara succession along the southern Central Zone (Miller, 1983b). It constitutes a major structural break which shows early and late strike-slip displacements (Downing and Coward, 1981) and which has been interpreted by Miller (1979) to represent an early, repeatedly rejuvenated, fundamental structure of the orogen. Thrusting increases southwards and complex thrust and nappe systems involving pre-Damara basement and ultramafic bodies occur in the Southern Margin Zone (Hoffmann, 1933). The Schellen-Amerongen Line (Hartnady, 1978) or Us Pass Lineament (Hoffmann, 1983) is a prominent zone along the northern margin of the Southern Margin Zone (Figs. 2.2 and 2.4) which contains nappes of basement and ultramafic rocks, the Hartelust Rhyolite Member and thrusts. It has also been considered to represent a major tectonic boundary which might be connected and traced into the Mwembeshi shear zone of the Zambezi Belt, as such representing a transcontinental Pan-African shear zone (Unrug, 1990). The northern edge of the Southern Foreland has been deformed into open to tight folds but deformation dies out further to the south (Ahrendt et al., 1977; Weber et al., 1983).

Very little geophysical data are available from the Damara Sequence. Aeromagnetic surveys have confirmed and defined lineaments and lineament zones (Corner, 1983) that form the boundaries of the tectono-stratigraphic zones shown in Figure 2.2. Results support the hypothesis that the lineaments are associated with downfolding of stratigraphic sequences (Miller, 1983b). The most severe downfolding may have occurred along the Okahandja Lineament with the Central Zone being uplifted relative to the Khomas Trough in the order of 20 km (Miller, 1983b; Corner, 1983). An aeromagnetic survey of Botswana (Reeves, 1978) clearly shows a major tectonic belt connecting the inland branch with the Katanga and Zambezi Belts (Fig. 2.1). Three north-east trending seismic profiles in the Central Zone, the eastern Khomas Trough and the Southern Foreland respectively show complicated crustal sections (Green, 1983; Baier et al., 1983). In the Central Zone Damaran cover rocks and basement are indistinguishable in a 15 km thick upper crustal section. The depth of the Moho is interpreted to be between 36 and 47 km (Green, 1983). The Khomas Trough profile was set up along strike from the Windhoek area to the east. It shows a 3 km thick low-velocity section on top, followed by denser material down to the 50 km deep Moho (Green, 1983). Palaeomagnetic data suggest initially that there was no separation of the Congo and Kalahari Cratons during the Late Proterozoic (Piper et al., 1973; McWilliams and Kröner, 1981). The resolution of data, however, allows a separation of approximately 800 km and there are no data for the period from 730 to 700 Ma (Miller, 1983b).

The Damaran rocks have been subjected to low-, medium-, and high-grade metamorphism. Mapping of regional metamorphic isograds by Hoffer (1977) has shown that these describe a concentric distribution around an area close to Walvis Bay where partial melting associated with the highest temperatures has occurred. The studies of Sawyer (1981) and Kasch (1983b) confirmed that metamorphic temperatures increase and pressures decrease inward towards the Central Zone with the highest pressures of up to 11 kbar obtained in the southern Khomas Trough. Metamorphism in the Khomas Trough reached the upper amphibolite facies with partial melting occurring along the northern margin. The migmatites of the Kuiseb Formation in this area have been reinterpreted to represent in situ migmatization during regional metamorphism and U-Pb monazite ages of about 520 Ma are interpreted to date the peak of metamorphism (Kukla, Kramm et al., 1990; Kukla, in prep.). No agreement has yet been reached as to whether metamorphism in the Damara Orogen took place in a single prograde event (Jacob, 1974; Hoffer, 1977) or in several peaks as suggested by Sawyer (1981) and Kasch (1983b).

3. SEDIMENTOLOGY

3.1 Introduction

A large part of the present outcrop surface in the Southern Damara Orogen comprises lithologies of the Kuiseb Formation within the Khomas Trough. No detailed sedimentological studies have, however, been previously undertaken because of the supposed monotony of the sequence and because of its structural and metamorphic overprint. It is therefore the aim of this chapter to present data from measured sections taken across the Khomas Trough and to combine these in a model of depositional palaeoenvironments. The most likely tectonic settings in which the sedimentary precursors of the Kuiseb metasediments might have accumulated and suitable provenance areas are also discussed. Since the Kuiseb schists represent metamorphosed rocks, the present day lithotypes will be introduced primarily. For convenience the interpretation of their probable sedimentary precursor rocks are added to the headings of section 3.2.

3.2. Description of lithotypes

3.2.1 Quartz-plagioclase-mica schist (psammite)/greywacke

Psammites are most abundant throughout the Khomas Trough. The light grey to dark grey quartz-plagioclase-mica schists are from below 10 cm up to 5 m thick, mineralogically uniform and the

metamorphic texture is schistose. Quartz forms polygonal grain boundaries indicating recrystallization and the quartz-plagioclase matrix is fine- to medium-grained (<0.5 mm). Other mineral phases are largely dependent on the metamorphic grade in various parts of the traverse and include plagioclase, biotite, muscovite, chlorite, scapolite and minor amounts of tourmaline, epidote, sphene, zircon and apatite.

3.2.2 Mica-quartz-plagioclase schist (pelite and metasiltstone)/ mudstone and siltstone

Pelites are also most abundant throughout the Khomas Trough whilst metasiltstones only occur in the central part of the traverse. Both rock types are principally mica (biotite-muscovite)-quartz-plagioclase schists with unit thicknesses ranging from below 10 cm to more than 10 m. Depending on the metamorphic grade and the bulk rock geochemistry there are also the minerals garnet, staurolite, kyanite, andalusite, sillimanite, chlorite, scapolite as well as minor amounts of tourmaline, epidote, sphene, zircon and apatite present.

3.2.3 Graphitic mica-quartz-plagioclase schist/carbonaceous mudstone

Units of graphite schists are developed particularly in the central and southern part of the traverse. The amount of graphite ranges between 20% and nearly 100% within pelitic schists with

streaked texture which comprise (with decreasing frequency) biotite, muscovite, quartz, plagioclase and chlorite as well as andalusite in the appropriate metamorphic zones. The schists contain appreciable numbers of pyrite grains.

3.2.4 Marble and tremolite schist/carbonate

An up to 2 m thick marble unit in the hangingwall sequence of the Matchless Amphibolite is composed mainly of fine-grained dolomite and some calcite as well as minor amounts of quartz and muscovite. A heavily weathered, up to 1 m thick tremolite rock which contains mostly tremolite and some biotite and quartz (<5%) occurs in the centre of the Khomas Trough.

3.2.5 Calc-silicate rock/impure carbonate

Calc-silicate rocks occur as a relatively minor component of the sequence throughout the area and in a large variety of shapes (layers, spindles, nodules, segregations and veins) and mineralogical compositions. Mineral components encountered are: quartz, plagioclase, garnet, hornblende, biotite, muscovite, diopside, zoisite, calcite, scapolite, epidote, chlorite, sphene, rutile, apatite and tourmaline within a partly blastomylonitic matrix.

3.3 Geochemical characterization of psammites, pelites and meta-siltstones

A brief geochemical characterization of the Kuiseb schists was undertaken in order to support the thin section and sedimentological data. This also helps to constrain later considerations of a suitable source area. Layers of psammites, pelites and metasiltsstones were sampled along the study traverse and subsequently analysed by XRF whole-rock analysis for 23 major and trace elements. The data are presented in Table 3.1 which gives mean, minimum and maximum element concentrations as well as the standard deviation of the 132 samples analysed. The full analyses are given in Appendix I.

One of the major geochemical problems encountered in resedimented and metamorphosed terranes are secondary element mobilities. Studies in other parts of the Khomas Trough have indicated certain mobilities of major and minor elements (Miller, 1983c; Phillips et al., 1989). This is also confirmed by geochemical studies of Häussinger (in prep.) who compares unaltered Kuiseb schists from the present study area with altered Kuiseb schists from the Gorob massive sulphide deposit in the Namib desert. Elements plotted against an "immobile" TiO_2/Zr ratio (Häussinger and Kukla, 1990) show mostly good correlations in the case of the Khomas Trough. In the consideration of possible source areas, the psammites have been chosen for further investigations. This is because pelites usually show more significant changes during

metamorphism than the mineralogically and chemically more uniform psammites. Secondly, it will be shown later in this chapter that, in contrast to the psammites, the precursors of the pelites did form under different depositional processes.

Table 3.1: Chemical composition of psammites and pelites of the Kuiseb Formation along the study traverse in the western Khomas Trough (samples were reduced in a jaw crusher and tungsten carbide mill, and prepared as pressed pellets and fused discs in the Department of Geology, University of the Witwatersrand).

Psammites Khomas Trough					Pelites Khomas Trough				
Element	mean (n=70)	min	max	SD	Element	mean (n=62)	min	max	SD
SiO ₂ (wt %)	72.40	68.12	75.65	1.62	SiO ₂ (wt %)	57.85	39.93	68.23	5.57
TiO ₂	.85	.49	1.19	.15	TiO ₂	1.01	.78	1.55	.15
Al ₂ O ₃	11.19	9.35	13.11	.74	Al ₂ O ₃	18.06	13.33	25.90	2.73
Fe ₂ O ₃	5.06	3.35	6.34	.39	Fe ₂ O ₃	8.18	1.42	12.11	1.77
MnO	.08	.06	.15	.02	MnO	.10	.01	.18	.03
MgO	2.03	1.39	3.48	.36	MgO	4.24	.67	7.88	1.21
CaO	1.70	.71	5.07	.73	CaO	1.58	.11	8.84	1.78
Na ₂ O	2.78	1.62	3.94	.44	Na ₂ O	1.63	.59	4.31	.75
K ₂ O	2.16	1.26	3.95	.46	K ₂ O	4.51	.32	7.87	1.31
P ₂ O ₅	.19	.10	.27	.04	P ₂ O ₅	.21	.07	.35	.05
Cr (ppm)	77	60	101	9.55	Cr (ppm)	125	85	187	20.90
Ni	27	14	51	6.49	Ni	49	23	79	12.30
Rb	85	34	127	15.99	Rb	180	14	381	57.65
Sr	146	59	396	89.78	Sr	114	40	308	70.99
Ba	462	185	949	147.89	Ba	752	79	1486	275.74
V	99	70	124	11.19	V	191	121	304	38.93
Y	33	17	45	4.83	Y	39	26	64	7.36
Zn	71	13	121	17.13	Zn	117	14	212	42.61
Nb	10	4	15	1.96	Nb	14	3	20	2.64
Zr	243	125	384	66.92	Zr	202	132	291	27.33
Co	12	7	18	2.11	Co	18	6	32	4.56
Cu	26	6	142	29.97	Cu	42	4	233	46.82

* total Fe as Fe₂O₃




Fig. 3.1: (A) Geochemical variation diagrams showing major elements of psammite analyses plotted against an immobile parameter Zr. Note the good correlations with TiO_2 and P_2O_5 .




Fig. 3.1 (continued): (B) Geochemical variation diagrams showing minor elements of psammite analyses plotted against an immobile parameter Zr. Note the good correlations with Y, V, Nb and Cr.

The element Zr is thought to have been transported mostly as the heavy mineral zircon with other sand grains and consequently major and minor elements have been plotted against Zr as "immobile" parameter in Figure 3.1. Respective element mobilities are shown in this type of variation diagram and in this case they demonstrate good correlations and small variations of inter-element ratios of TiO_2 , P_2O_5 , V, Nb, Cr, and partly Fe_2O_3 and V with Zr. This does not necessarily assume that Zr was constant but it tests whether parts of the group including Zr could have been immobile. Phillips et al. (1989) have shown from investigations in the Kuiseb schists of the eastern Khomas Trough that most of the above elements are also reasonably constant if plotted against Ti using pelitic rock types.

The geochemical grid of Wimmenauer (1984) classifies sedimentary protoliths by means of $\text{K}_2\text{O}/\text{Na}_2\text{O}$ and $\text{SiO}_2/\text{Al}_2\text{O}_3$ ratios (Fig. 3.2). Although element mobilities especially for K and Na may be expected (Fig. 3.1), the diagram clearly distinguishes geochemically "pelites" and "greywackes". Data points in the arkose field are samples with slightly higher quartz contents due to veining. The more pelitic character of the siltstones is also indicated in this diagram.




Fig. 3.2: Geochemical grid for discriminating clastic sedimentary protoliths after Wimmenauer (1984), with Kuiseb metagreywackes, pelites, metasiltstones and graphite schists plotted.

3.4 Sedimentary structures and palaeocurrents


(a) Sedimentary structures

Short sections were measured in detail throughout the study traverse on a variety of scales from centimetres upwards. With the exception of the southernmost part of the area sedimentary structures have been detected throughout the Kuiseb Formation rocks. Sedimentary logs from outcrops with best preserved sedimentary structures are shown in Figure 3.3. Measured section data showed that bed thicknesses may be defined according to the scheme employed by Mutti and Ricci Lucchi (1975) with very thick beds greater than 100 cm; thick beds, 40-100 cm; medium beds,

10-40 cm; and thin beds 1-10 cm. In terms of measured bed thicknesses it is to be expected in a deformed terrane that tectonic thinning affects the analysis. Sedimentary structures do themselves act, however, as strain markers and may indicate a low degree of internal deformation, if original shapes are largely preserved. Additionally, it will be shown elsewhere (see Chapter 4) that layer-parallel extension played a minor role within low-strain zones in the Khomas Trough.

Initially, the primary nature of the layering in which the above lithotypes are organized is confirmed by sharp bases and tops of beds, graded beds and various erosional features (Fig. 3.3). Graded beds are more quartz- and feldspar-rich at the base and more mica-rich at the top, representing a metamorphosed compositional grading (Fig. 3.4,A) reflecting a sand- to mud-rich transition in a normally graded unit. Furthermore, structural fabrics mostly crosscut and refract at bedding surfaces and bedding-fabric relationships therefore allow structural way-up control of both folds and measured sections within the traverse. Sedimentary structures such as graded bedding confirm stratigraphic "way-up". This terminology will be employed in the following sections.

Fig. 3.3: Representative measured sections showing range of sedimentary structures preserved, Bouma sequences and palaeocurrent directions in the Kuiseb Formation. For facies classification according to Pickering et al. (1986) see section 3.5. Positions of profiles are indicated in Figure 3.12.






Fig. 3.3 (continued).

Bedding is generally very uniform laterally although observations are limited by outcrop size. In the case of the psammites internal bed forms present are: (1) massive, structureless; (2) plane laminated; and (3) cross-laminated. Small-scale trough cross-lamination (Fig. 3.4, B and C) has been recognized in several outcrops and occurs both within discrete psammitic layers and in graded units which form part of Bouma sequences.

Load casts are common with a maximum width of 10 cm (Fig. 3.4,D). In some cases the loads became detached from the original sediment and form load balls or ball-and-pillow structures in the underlying pelites (Fig. 3.4,E and F). Loads show internal lamination which is parallel at the margins but contorted towards the centre. Laminations of underlying strata are deformed by the flame structures which are associated with the loads (Fig. 3.4,F). Extreme loading has led in some cases to layers which comprise an accumulation of load balls (Fig. 3.4,E).

A variety of erosional structures are present namely flute casts, small-scale scours and channels (Fig. 3.3). Bilaterally symmetrical flute casts are preserved on the undersides of massive psammitic layers. The flutes range commonly in length from 10 cm to 20 cm and in width and depth from 5 cm to 10 cm (Fig. 3.4,C). In one particular outcrop at the Khomas Hochland road, however, mega-flutes with a length of about 1 m and a width and depth of 20 cm to 50 cm have been found (Fig. 3.5,A). The flutes are excellent way-up indicators and they have also been used to determine palaeocurrent directions.

Scour surfaces and channels are developed throughout the traverse. These erosional features are evident from mostly massive psammitic layers truncating earlier bedding surfaces (Fig. 3.3,IV and V). Only a few channels have, however, been found with both margins exposed and these show a maximum depth of about 3 m and a width of 5 metres. Some thick psammitic units, reaching a thick-

Load casts are common with a maximum width of 10 cm (Fig. 3.4,D). In some cases the loads became detached from the original sediment and form load balls or ball-and-pillow structures in the underlying pelites (Fig. 3.4,E and F). Loads show internal lamination which is parallel at the margins but contorted towards the centre. Laminations of underlying strata are deformed by the flame structures which are associated with the loads (Fig. 3.4,F). Extreme loading has led in some cases to layers which comprise an accumulation of load balls (Fig. 3.4,E).

A variety of erosional structures are present namely flute casts, small-scale scours and channels (Fig. 3.3). Bilaterally symmetrical flute casts are preserved on the undersides of massive psammitic layers. The flutes range commonly in length from 10 cm to 20 cm and in width and depth from 5 cm to 10 cm (Fig. 3.4,C). In one particular outcrop at the Khomas Hochland road, however, mega-flutes with a length of about 1 m and a width and depth of 20 cm to 50 cm have been found (Fig. 3.5,A). The flutes are excellent way-up indicators and they have also been used to determine palaeocurrent directions.

Scour surfaces and channels are developed throughout the traverse. These erosional features are evident from mostly massive psammitic layers truncating earlier bedding surfaces (Fig. 3.3,IV and V). Only a few channels have, however, been found with both margins exposed and these show a maximum depth of about 3 m and a width of 5 metres. Some thick psammitic units, reaching a thick-



ness of more than 10 m, are subdivided by bedding parallel joint-like surfaces which might indicate "amalgamation" (processes leading to erosional contact surfaces between adjacent psammitic beds).

In several outcrops pelite and graphite schist rip-up clasts, up to a few centimetres in length and width, have been observed within psammitic lithologies. Rip-up clasts of graphitic schist are incorporated into psammities and metasiltstones (Fig. 3.5,B) at the graphite schist sequence on the farm Kaan, thus confirming the primary sedimentary origin of this unit.

In the centre of the traverse "sandstone" (psammite) dykes are preserved in thick-bedded graded sequences and in the thick graphite schist on the farm Kaan. One particular outcrop exhibits exceptionally preserved dykes which are up to 2 m long and 30 cm wide. Dyke walls are both straight, parallel sided and irregular undulating. The dykes lead from the psammitic base of thick graded units and may be traced through the silty-pelitic top upwards where they link with the psammitic base of the overlying graded unit (Fig. 3.5,C). Internal structures of the dykes are contorted if compared with the outside texture. Similar structures may be observed at the graphite schist on the farm Kaan. There, however, the dykes occur isolated within the graphite schist and they contain graphite clasts.




Fig. 3.5: Sedimentary structures preserved in the Kuiseb metasediments. (A) Large flute casts at the underside of a facies B (class 1b of this study) turbidite. Palaeocurrents indicate current flow towards the south-west. Khomas Hochland Pass, farm Garums 300. (B) Graphite schist rip-up clasts in a thick-bedded facies C turbidite. Lens cap is 4.9 cm in diameter. Farm Kaan 309. (C) Metasandstone dykes in a thick, mud-dominated facies C 2.4 turbidite. Farm Kaan 309. (Facies terminology after Pickering et al., 1986).

(b) Palaeocurrents

Palaeocurrent determinations have been made in some outcrops where three dimensional orientations of flute casts and sets of trough cross-laminae could be measured. The measurement of palaeocurrents was facilitated by the fact that the sedimentary structures are preserved in zones of low strain. In these zones sequences are usually upward-facing and the fold axes of the main fold phase are horizontal with the axial plane dipping north-westwards ($330^{\circ}/45^{\circ}$).




Fig. 3.6: Palaeocurrent data from various measured sections throughout the Khomas Trough. Palaeocurrent directions determined from sets of cross-laminae and flute casts.

The second phase of deformation in these zones is represented only by a reorientation of micas, and small-scale folds related to this phase also have horizontal fold axes co-linear with the previous main fold phase. This meant that restoration of palaeocurrents involved a straightforward small circle rotation on the stereonet. Although only a few palaeocurrent orientations from flute casts and trough cross-beds could be obtained, they show a remarkable uniformity throughout the traverse (Fig. 3.6). Orientations indicate current flow from the east-north-east to the west-south-west (230° - 250°).

3.5 Turbiditic and pelagic facies

The recognition of sedimentary structures within graded units in the present study area proves that parts of the Kuiseb schists are organized in classical Bouma sequences (Bouma, 1962). These units are therefore hydrodynamically interpreted as having been deposited by turbidity currents, being one end member of "sediment gravity flows" as defined by Middleton and Hampton (1973, 1976). The development of graded bedding has previously been used in isolation to infer that the sedimentary precursors of the Kuiseb schists have been deposited by turbidity currents (Miller et al., 1983; Praussinger et al., 1987).

In consequence, sedimentary facies may be defined in the Kuiseb schists and be compared with current classification schemes of marine clastic sediments. The most widely used classification is

the "turbidite facies and facies associations" scheme of Mutti and Ricci Lucchi (1972, 1975). New research data from the past decade has led Pickering et al. (1986) to a re-classification of recent and ancient deep-water sediments. In the following a classification of the siliciclastic turbidite facies and the associated facies encountered in the Khomas Trough is applied to the Kuiseb Formation metasediments. Figure 3.7 gives an overview of the turbidite facies classes established in this study and these are compared with the schemes of Mutti and Ricci Lucchi (1975) and Pickering et al. (1986). In extending Gressly's (1838) original application of facies, Selley (1976) defines the parameters of facies, namely lithology, sedimentary structures, palaeontology, geometry and palaeocurrent patterns. These are only partly applicable, however, to Phanerozoic and Proterozoic deformed and metamorphosed rocks. The major attributes used to define facies in the Kuiseb schists are lithologies, bedding style, vertical bed thickness distribution, variations in psammite/pelite ratio and sedimentary structures. On the basis of these characteristics, the metasediments within the Khomas Trough are grouped into seven facies classes, representing both turbidite and pelagic facies which are characterized and hydrodynamically interpreted below. Additional data has led to an extension of a facies classification scheme given by the present author in an earlier publication (Kukla et al., 1988).

	THIS STUDY Facies Class	Pickering et al. (1986) Facies Class	Mutti & Ricci Lucchi (1975) Facies
	Facies Class (1) medium- to very thick-bedded psammites a) massive, structureless b) massive, "organized" c) parallel-stratified d) cross-stratified	B 1.1 — B 2.1 B 2.2	A1 or B1 B2 B1 —
	Facies Class (2) graded psammite/pelite couplets a) very thick- to thick-bedded b) medium-bedded c) thin-bedded d) very thick- to thick-bedded, mud-dominated	C 2.1 C 2.2 C 2.3 C 2.4	C2 D2 D1 —
	Facies Class (3) thin-laminated metasilstones	D 2.1	D1
	Facies Class (4) thin- to very thick-bedded pelites a) structureless b) "organized"	E 1 or G E 2 or G	thin- to medium-bedded D or G

Fig. 3.7: Summary of the turbidite facies classification of this study compared with other studies.

3.5.1 Medium- to very thick-bedded psammite facies (facies class 1)

This facies class includes psammitic layers which are not part of a Bouma sequence. It is subdivided into (a) massive, structureless psammites; (b) massive, "organized" psammites; (c) parallel-stratified psammites; and (d) cross-stratified psammites.

(a) Massive, structureless psammites

The structureless psammites have sharp and planar bounding surfaces and range in thickness from 15 cm upwards, commonly to about 3-5 m (Fig. 3.8,A). Psammitic units which are 5 m to 15 m thick commonly show signs of amalgamation. Graded layering has not been observed. This facies would best be compared with facies B 1.1 "thick/medium-bedded disorganized sands" of Pickering et al. (1986). (In the Mutti and Ricci Lucchi (1975) scheme, however, these psammites could be assigned to both facies A1, which includes medium- to coarse, often amalgamated sandstones, and to more organized facies B1 sands". In contrast facies A of Pickering et al. (op.cit.) only contains gravels and pebbly sands.)

Interpretation: Depositional processes assigned to this facies are high-density turbulent flows (Mutti and Ricci Lucchi, 1975; Pickering et al., 1986; Lowe, 1982). The psammites are similar to mostly structureless facies S₃ sands of Lowe (1982), who interprets deposition from high-concentration turbidity currents by suspension sedimentation. Some liquefied flow deposits closely resemble these S₃ divisions but would contain generally fine-grained sand and coarse silt (Lowe, 1982). Within this facies the presence of tractional processes, developed beneath turbidity currents and typical for "proximal" turbidites and Bouma T_a divisions, must also be considered.

(b) Massive, "organized" psammites

Abundant within the sections measured are psammites which have a

massive texture if compared with other facies in this facies class (see below) but which contain sedimentary structures (Fig. 3.3). Bed thicknesses range from 10 cm to about 3 m but are mostly in the order of 70 cm. Most commonly the layers which are up to 70 cm thick contain trough cross-lamination in the upper 10 cm. Load casts and flute casts do occur on bases (Fig. 3.4,C). Erosional channels and scours detected within the traverse are mostly developed within this facies class. Sandstone dykes and rip-up clasts have also been observed. This facies compares well with Mutti and Ricci Lucchi's (1975) facies B2 turbidites. Pickering et al. (1986), however, do not address a facies which includes massive, ungraded psammites containing a variety of sedimentary structures. Interpretation: This facies might indicate the transition from high-density suspension flow to residual low-density currents whose cross-lamination confirms continued rapid fallout from suspension. This process is suggested by Lowe (1982) and is manifest in units comprising his S_3 and T_t divisions.

(c) Parallel-stratified psammites

This facies is poorly developed within the area. The beds are 10-35 cm thick and show flat, planar upper and lower surfaces. No sedimentary structures have been observed. This facies is compared with plane-laminated facies B1 of Mutti and Ricci Lucchi (op.cit.) and with facies B2.1 of Pickering et al. (op.cit.). Interpretation: Within turbidite sequences this facies is interpreted as traction carpet deposits comprising "horizontal"

lamination and inverse grading (Lowe, 1982; Pickering et al., 1986; Hiscott and Middleton, 1979). The latter feature, however, could not be observed in the metamorphosed Kuiseb schists.

(d) Cross-stratified psammites

A cross-stratified psammitic layer which is not part of a Bouma sequence has only been observed in one outcrop (Fig. 3.4,B). The layer is 20 cm thick, trough cross-laminated and the top and basal contacts are sharply defined. This facies is the only facies of completely cross-laminated metasandstone layers and compares principally with facies B2.2 of Pickering et al. (1986). Restriction must be made, however, in terms of the grain size since this facies is only assigned to medium to granule-grade sands an evaluation which cannot be strictly made in metamorphic rocks.

Interpretation: It has been pointed out by various authors that discrete cross-stratified layers might be attributed to tractional processes beneath dilute turbidity currents or bottom currents (Mutti and Ricci Lucchi, 1972; Lowe, 1982; Pickering et al., 1986).

3.5.2 Very thick- to thin-bedded graded psammite/pelite facies (facies class 2)

The psammite-pelite couplets of facies class 2 show a wide range of psammite/pelite ratios from >10:1 to 1:10. Graded layering generally characterizes this facies and sedimentary structures within Bouma sequences are abundant. Four subfacies have been

distinguished (Fig 3.7) based mainly on bed thickness which may appear to be an arbitrary criterion initially. Measurements have shown, however, that certain sedimentary structures are associated with specific bed thicknesses and these agree broadly with the subdivision scheme employed by Pickering et al. (1986).

(a) Very thick- to thick-bedded psammite/pelite couplets range in thickness from 40 cm to 170 cm (Fig. 3.8,B). Psammite/pelite ratios in well developed graded beds vary between 1:1 and 10:1 but commonly are about 4:1. Sedimentary structures found in this facies are primarily sets of trough cross-laminae which contribute to partial Bouma sequences which are mostly T_{abc} divisions in this subfacies although complete Bouma divisions have also been found (Fig. 3.8,C and D). Further structures are rip-up clasts, scour surfaces, load casts, load balls and flame structures. This facies is compared with facies C2 of Mutti and Ricci Lucchi (1975) and with facies C 2.1 of Pickering et al. (1986).

(b) Medium-bedded graded units are abundant in measured sections (Fig. 3.3). The beds are 10-25 cm thick and psammite/pelite ratios range widely between 10:1 and 1:10 but with an average of 1:1. Bouma sequences are mainly T_{bcd} divisions lacking the lower massive psammite but T_{cd} and T_{ac} divisions have also been found. Sedimentary structures are comparable to those in the previous subfacies. This facies is compared with facies C 2.2 of Pickering et al. (op.cit.) and facies D2 of Mutti and Ricci Lucchi (op.cit.).

Fig. 3.8: Turbidite facies (facies terminology after Pickering et al., 1986).

(A) Thick-bedded facies B turbidites; height of scale (circled) is 1.7 m. Farm Usambara 304.




(B) Thick-bedded facies C 2.1 graded psammite/pelite turbidites. Beds are overturned. Farm Kaan 309.

(C) Complete Bouma sequence developed in a facies C 2.1 turbidite underlying a thick-bedded facies B psammite. Farm Dagbreek 365.

(D) Complete Bouma sequence developed in a facies C 2.1 turbidite overlying a medium-bedded facies B psammite and underlying a medium-bedded facies C 2.2 turbidite containing flute casts (see arrow). Farm Dagbreek 365.

(E) Thin-bedded facies C 2.3 turbidite with low psammite/pelite ratios. Note the selective development of sillimanite in the pelitic tops; beds are overturned. Pocket knife is 8.5 cm long. Farm Keises 312.

(F) Fine-laminated facies D 2.1 metasiltsstones containing small load structures (indicated by arrow); lens cap is 4.9 cm in diameter. Farm Kaan 309.



(c) Thin-bedded graded layers are up to 10 cm thick and are characterized by a dominant pelitic top (Fig. 3.8,E) with psammite/pelite ratios usually >1 . Bouma sequences often start with trough cross-laminated T_c units within overall T_{cde} sequences. No additional sedimentary structures have been found. This facies is comparable with facies C 2.3 of Pickering et al. (1986) and facies D1 of Mutté and Ricci Lucchi (1975). Interpretation: Facies 2 very thick- to thin-bedded graded layers represent the "classic" turbidites described by Walker (1976) and depositional processes therein have been interpreted by many workers (Bouma, 1962; Piper, 1978; Walker, 1978; Stow and Bowen, 1980). High concentration turbidity currents with rapid settling seem the predominant depositional processes within this facies but low concentration currents produce thin-bedded units and decreasing psammite/pelite ratios.

(d) Graded layers which are dominated by pelitic lithologies and which are 50 cm to more than 2 m thick have been observed in a few outcrops across the traverse. Psammitic bases are rather irregular and commonly show load structures. The pelitic parts of the units are laminated with alternations of pelites and meta-siltstones. On the farm Kaan, spectacular metasandstone (psammite) dykes have developed from the lower psammitic layer through the pelitic part to finally join the psammite of the overlying graded unit (Fig. 3.5,C). This facies is compared with facies C 2.4 of Pickering et al. (1986). Interpretation: Pickering and Hiscott (1985) attribute this unusual facies to large-volume,

high concentration turbidity currents confined within small basins. In this model the thick silt-mud layers are formed by rapid settling of flocs within a highly concentrated mud cloud. Piper (1978) has pointed out the occurrence of thick turbiditic mud beds overlying sands with partly gradational contact in channel to levee environments. He also cites ponding in basins as a possible mechanism to accumulate turbiditic thin sand/thick mud couplets.

3.5.3 Thin-laminated metasilstone facies (facies class 3)

This facies is only developed in the central part of the study traverse. The classification as siltstones seems appropriate because of the thin-laminated character of sedimentary layering and the modal compositions which point towards equal proportions of quartz and mica. The sequences comprising this facies are all very similar so that only one facies type, namely graded stratified metasilstones, has been established.

The sedimentary units comprising this facies are typically 20 cm to 350 cm thick. Within these, single metasilstone layers are internally well laminated (i.e. silt and clay laminations) with bed thicknesses ranging from 1 mm to 2 cm (Fig. 3.8,F). Only very few sequences comprise up to 7 cm thick layers. The majority of the beds show normal grading with psammite/pelite ratios in the order of 3:1-1:2. Bouma sequences comprise mostly T_{de} divisions. Pelitic tops are in some cases graphitic. Bases often show

micro-loading and flame structures. Cross-lamination is occasionally developed in the lower quartz-rich parts of layers, thus constituting Bouma T_{cd} turbidites. This facies compares with facies D1 of Mutti and Ricci Lucchi (1975) and with facies D2.1 of Pickering et al. (1986). Interpretation: Thin-laminated siltstones are interpreted to have formed by low concentration, low velocity turbidity currents (Piper, 1978; Stow and Piper, 1984). This is confirmed by the lack of erosive features, the thin bed thickness, the grading, and the lateral continuity of laminated units. Pickering (1984) attributes the thin laminations to discrete (ing) flow events with an accompanying depositional sorting process as described by Stow and Bowen (1978). An increase of this facies together with mud turbidites towards distal parts of a sedimentary basin has been pointed out by Piper (1978).

3.5.4 Very thick- to thin-bedded pelite facies (facies class 4)

This facies comprises pelitic layers which are not part of graded psammite/pelite couplets and it is subdivided into (a) structureless pelites and (b) "organized" pelites. The classifications of Pickering et al. (op.cit.) and Mutti and Ricci Lucchi (op.cit.) distinguish a variety of mud subfacies using additional components such as colour, organic carbon content, terrigenous input, degree of bioturbation and grain size. These cannot be evaluated

in the pelites of the Kuiseb schists. A further problem encountered is the preservation potential of pelitic units which would have been preferentially been eroded.

(a) Structureless pelites mostly occur in units where bedding is poorly defined. The thickness varies from about 20 cm to several metres. No sedimentary structures have been found and the layers are mostly coarsely recrystallized pelites with biotite and chlorite (depending on metamorphic grade and bulk composition) as the main constituent. This facies may be compared with facies E 1.1 "structureless muds" of Pickering et al. (op.cit.) and with the E3 division of Piper (1978). The thin- to medium-bedded pelites of this facies may be compared with Mutti and Ricci Lucchi's (op.cit.) facies D or facies G pelites. These authors have not accounted, however, for pelitic layers thicker than 60 cm.

(b) Pelites which show some degree of internal organization are assigned to the second group within this facies. These rocks may best be described as graded, laminated pelites. The grading varies from silt to mud with ratios of generally less than 1:3 but transitions are very often ambiguous. Pelite layer thicknesses range from below 10 cm to more than 10 m, one unit has been found in the centre of the traverse which is about 30 m thick but a component of tectonic thickening through repetition cannot be excluded as possible (Fig. 3.9,A). This facies may also be compared with facies D or G of Mutti and Ricci Lucchi (op.cit.) and with facies E2 and facies G of Pickering et al. (op.cit.).

Interpretation: Fine-grained sediment may be generally deposited as turbidites, contourites and a result of pelagic-hemipelagic settling. It has been pointed out by Stow and Piper (1984) that these processes strongly interact and overlap during both transport and deposition. Structureless muds may be interpreted as resulting from nepheloid settling through the water column to be finally reworked by deep-sea bottom currents (Gorsline, 1984). This facies may also result from ponding of thick, dilute turbidity currents as suggested by Pickering et al. (1986). Piper (1978) points out that the internal organization of muds is largely dependent on the deceleration of the turbidite flow concerned. Thin facies E2 turbidites may therefore be deposited through grain-by-grain settling or aggregate settling within low concentration turbidity currents (Pickering et al., 1986).

3.5.5 Impure metacarbonate facies (facies class 5)

(a) Description

Metacarbonate-rich lithologies occur widely as calc-silicates within the Khomas Trough and have been described previously (e.g. Gavers, 1963; Hälbig, 1970; Porada, 1973; Preussinger, 1987). A large variety of geometries of these units has been observed in the present study area such as: (a) well defined layers, up to 40 cm thick, parallel to bedding (Fig. 3.9,B); (b) cigar-shaped spindles, up to several metres long and 40 cm thick. They are either aligned along bedding planes or orientated between bedding and the S_2 cleavage (Fig. 3.9,B); (c) small nodules, up to sev-

eral cm long and wide; (d) diffuse concentrations of calcareous lithologies within cleavage domains; and (e) calc-silicate veins discordant to bedding. The occurrence of the calc-silicates is almost exclusively restricted to psammitic lithologies and in particular to the basal parts of facies 1 turbidites and the structureless Bouma T_a division of facies 2 turbidites. Furthermore, finely dispersed calcareous material is preferentially deposited within the troughs of cross-laminated psammities. This feature has also been observed in the Ugab area in north-western Namibia where much less deformed and metamorphosed equivalents of the Kuiseb schists crop out.

(b) Interpretation

There are several possibilities to account for the origin of the carbonate leading to the formation of calc-silicates during regional metamorphism. These are: (1) carbonate grains derived from adjacent shelves through resedimentation processes (e.g. Stow, 1984); (2) pelagic organic precipitation by bacterial oxidation of methane (Faure, 1986); (3) inorganic oxidation of methane (Faure, 1986); (4) carbonate derived from hydrothermal processes (e.g. Mottl et al., 1983).

The wide distribution of calc-silicates in the Khomas Trough and the striking confinement of these lithologies to psammities which are part of turbiditic sequences imply that calcareous sediment formed part of the resedimentation processes during deposition of the siliciclastics. Therefore possibility (1) is strongly fa-

voured for the origin of the carbonate. Stow (1984) described decreasing amounts of carbonate upward from Bouma T_p to T_e divisions in cores taken from the Angola basin. The redeposition of fine-grained carbonate sediment (aragonite and Mg-calcite) from shelf areas into adjacent ocean basins has frequently been described; from the Bahama Banks for example by Neumann and Land (1975) and Heath and Mullins (1984). Transport distances of 200 km or more from the nearest carbonate source have been reported (Berner and Honjo, 1981). Organic or inorganic precipitation of carbonate from seawater should have produced a more random distribution of carbonate within the variety of lithologies in the Khomas Trough. These processes may, however, not totally be excluded since carbonate formed by pelagic precipitation may have also been involved in resedimentation processes (e.g. bottom currents) from the site of original deposition. There is no evidence for hydrothermal processes in large parts of the Khomas Trough which excludes possibility (4).

Processes leading to the formation of the various geometries of calc-silicates may comprise diagenesis (including concretionary processes), deformation and subsequent regional metamorphism. Porada (1973) has initially proposed concretionary processes within an originally CaCO_3 -bearing sediment to account for the formation of the calc-silicates. This interpretation is acceptable for the spindles and some of the nodules; well developed carbonate concretions have also been observed in less deformed and metamorphosed Kuiseb Formation schists in the Ugab area.




Fig. 3.9: Turbidite and pelagic facies (facies terminology after Pickering et al., 1986). (A) Very thick-bedded (>10 m) facies E pelites. Farm Keises 312. (B) Calc-silicate layer and spindles (facies class 5) in thick-bedded facies B turbidite above facies C turbidite. Farm Dagbreek 365. (C) Very thick-bedded pelagic graphite schist facies (facies class 6). Height of outcrop is about 10 m. Farm Kaan 309. (D) Dolomitic marble facies (facies class 7) on top of a graphite schist in the hangingwall of the Matchless Amphibolite (stratigraphic top towards the left). Hammer for scale. Farm Annelie 412.

Calc-silicate layers and calc-silicate lithologies deposited in troughs of cross-laminated psammites have, however, not undergone concretionary processes and are interpreted to represent resedimented deposits. Regional metamorphism has formed the various mineral assemblages observed and element mobilization processes may account for the formation of calc-silicate assemblages along veins and fractures.

In conclusion, the occurrence of metacarbonate rocks in the Kuiseb schists implies that sediments comprising mixed carbonate and siliceous grains have also been deposited by resedimentation processes in addition to the majority of siliciclastic sediments being deposited by turbidity currents. Some of the calcareous lithologies have been subjected to concretionary processes during diagenesis. Regional metamorphism has subsequently formed calc-silicates.

3.5.6 Thin- to very thick-bedded graphite schist facies (facies class 6)

(a) Description

This facies is closely associated with sequences comprising turbidite facies classes 1 to 4. Graphite schists have been found mainly in the south and centre of the traverse, especially in the vicinity of the Matchless Amphibolite. Units are usually between 1 m and 10 m thick but an extremely thick graphite schist is developed on the farm Kaan with a thickness of about 60 m in out-

crop (Fig. 3.9,C). This thick-bedded graphite schist and one unit in the vicinity of the Matchless Amphibolite have been traced along strike through the Khomas Hochland into the Namib desert, proving the regional distribution of this facies. The graphite schists show very little internal organization, except of some of the graphitic tops in the thin-laminated metasiltstone facies. On the farm Kaan, psammitic dykes which contain graphitic clasts are developed within the thick graphite schist. Pyrite is abundant within the graphite schists.

(b) Stable isotope analysis

a first step towards the interpretation of the graphite schists stable isotope geochemistry has been applied in order to prove or disprove the organic origin of these rocks. The thick graphite schist on the farm Kaan and one unit close to the Matchless Amphibolite have been analysed and the data, given in Table 3.2, show a very homogeneous distribution of $\delta^{13}\text{C}$ indicating a considerable enrichment of up to 20‰ ^{12}C relative to unaltered marine limestones.

(c) Interpretation and discussion

This graphite schist facies is compared with facies G ("hemipelagic pelites") of Mutti and Ricci Lucchi (1975) and with facies group G ("biogenic oozes, hemipelagites and chemogenic sediments") of Pickering et al. (1986).

Table 3.2: Stable isotope data from graphite schists and dolomitic marble. For sample localities see Figure 3.12. (All samples refer to bulk rock analyses. Mass-spectrometric measurements were undertaken with a VG micromass 602 C. The samples were reacted with 100% H_3PO_4 at 25°C to liberate CO_2 ; analyses were carried out at the Schonland Research Centre for Nuclear Sciences, University of the Witwatersrand).

SAMPLE NO.	SAMPLE DESCRIPTION	$\delta^{13}C$ (‰ PDB)	$\delta^{18}O$ (‰ PDB)
PK 852	Graphite schist, Kwaggafontein farm	- 20.4	
PK 954	Graphite schist, Annelie farm	- 19.6	
PK 825	Dolomitic marble, Annelie farm	- 4.3	- 15.8
PK 866	Dolomitic marble, Annelie farm	- 9.0	- 15.7

The carbon isotope data obtained for the graphite schists are in accordance with published data of potentially analogous biogenic precursors of such rocks (Hahn-Weinheimer, 1966; Hoefs, 1980). Analyses of Hahn-Weinheimer (1966) on Precambrian and Cambrian metamorphosed graphite schists are divided by her into one group with a considerable depletion in ^{13}C (average -25‰) being interpreted as compatible with a biogenic origin of these rocks and a second group with $\delta^{13}C$ -values of up to -7‰ interpreted as bearing a probable crustal signature. The average $\delta^{13}C$ -value of about -20‰ fits well into data sets for sedimentary organic

material as shown in Figure 3.10,A. The graphite might have developed by the progressive loss of hydrogen from organic compounds leading to the recrystallization of the residual carbon as graphite (Faure, 1986). A mechanism involving the (abiogenic) reduction of CO_2 or of carbonates would have produced an enrichment in ^{13}C with a shift towards positive values of the $^{13}\text{C}/^{12}\text{C}$ ratio.

The interpretation of "black shales" preserved in the rock record is still problematic. Arthur et al. (1984) summarize the three most frequently used variables which are considered to be most significant for black shale development: (a) variations in the supply of marine and terrigenous organic matter from surface productivity, fluvial discharge, redepositional processes and settling from nepheloid-layers; (b) variation in the rate of sedimentation and hence rate of burial of organic matter; and (c) variation in bottom water oxygenation within an oxygen-minimum zone. Graphitic schists occur within distinct parts of the study area and are intercalated with turbidite facies sequences. The sequence stratigraphically above the graphite schist on the farm Kaan shows especially well preserved sedimentary structures which are part of turbidite facies (Fig. 3.3,I). High pyrite contents indicate reducing conditions. The most likely processes to account for this change in facies are initial changes in supply of organic matter (e.g. by increasing plankton productivity) and/or oxygen depletion associated with volcanic activity, e.g. as represented by the Matchless Amphibolite. Both these processes

may lead to temporary extensions of oxygen-minimum zones into the deep-sea which might even explain the occurrence of black shales near the Mid-Atlantic ridge (Tissot et al., 1980), in the deep Atlantic Cape Verde basin (Arthur et al., 1984) and the Angola basin off the south-west African coast (Stow and Dean, 1984).




Fig. 3.10: Diagram comparing $\delta^{13}\text{C}$ (A) and $\delta^{18}\text{O}$ (B) data from graphite schists and marble in the Khomas Trough with carbon and oxygen isotope distributions of the lithosphere and hydrosphere (from Hoefs, 1980).

Taking the case of the Angola basin, Stow and Dean (1984) point out that oxygen concentrations changed periodically in sediment and bottom waters. This leads to anoxic conditions both in the basin and on the continental margin. Analyses of black shale sequences in the Atlantic ocean have shown that both turbiditic and pelagic processes operate throughout their deposition (Arthur et al., 1984).

3.5.7 Marble and tremolite schist facies (facies class 7)

(a) Description

Rocks of this facies have only been found at the Matchless Amphibolite (marble) and stratigraphically below the graphite schist on the farm Kaan (tremolite schist). The up to 2 m thick marble horizon is developed on top of a 10 m thick graphite schist and has been traced laterally over several kilometres (Fig. 3.9,D). The marble is internally massive, the matrix consists mainly of finely recrystallized dolomite and some calcite. The tremolite schist is about 1 m thick and extremely weathered. It has been included with this facies because metamorphic assemblages indicate that it has formed from dolomite during prograde metamorphism (Winkler, 1979).

(b) Stable isotope analysis

Stable isotope techniques have been used to elucidate the primary (organic pelagic) or secondary (chemogenic, hydrothermal) origin of the marble layer at the Matchless Amphibolite. Oxygen data

(Table 3.2, Fig. 3.11,B) give constant $\delta^{18}\text{O}$ -values around -16‰ . This represents an enrichment in ^{18}O compared with average ocean water (Fig. 3.10,B) but a marked depletion if compared with data for Upper Proterozoic marine carbonates (Veizer and Hoefs, 1976). The $\delta^{13}\text{C}$ -values for carbon isotopes range between -4‰ and -9‰ (Table 3.2, Fig. 3.11,A) which represents a depletion in ^{13}C compared with marine carbonates (Hoefs, 1980).

(c) Interpretation and discussion

In comparison with the graphite schists, the interpretation of the carbon and oxygen data of the dolomitic marble horizon is more problematic. Land (1980) concludes that the marked depletion in ^{18}O of ancient dolomites compared with recent dolomites has either developed by primary precipitation (which is rather rare) or by replacement, either at elevated temperatures or from fluids depleted in ^{18}O relative to SMOW. Oxygen isotopic compositions may change during subsequent processes such as hydrothermal alteration and under the influence of meteoric waters (Cocker et al., 1982; Fig. 3.11,B). On the other hand Valley (1984) reports that during metamorphism volatilization and fluid exchange tend to decrease $\delta^{18}\text{O}$ but only on a scale of $1-3\text{‰}$ between lower greenschist and granulite facies. Carbon isotopic compositions are more difficult to alter due to the higher insolubility of CO_2 (Land, 1980). Since a freshwater origin as well as the participation of terrestrial organic carbon towards formation of the marble seem unlikely in terms of the encountered deep marine sedimentary facies in the Khomas Trough, a mechanism to deplete




Fig. 3.11: Diagram comparing $\delta^{13}\text{C}$ (A) and $\delta^{18}\text{O}$ (B) data from the dolomitic marble at the Matchless Amphibolite with other species of dolomite (from Mattes and Mountjoy, 1980).

$\delta^{13}\text{C}$ to the values observed was probably involved. This decrease in ^{13}C towards values characteristic for "juvenile carbon" in carbonatites and diamonds (Fig. 3.10,A) might be due to diagenetic processes (Mattes and Mountjoy, 1980; Land, 1980) or to hydrothermal alteration, which includes the possibility of fumarolic activity (Faure, 1986).

In conclusion, both data sets may be regarded from two points of view: if compared with recent and ancient "organic" limestones both heavy isotopes are depleted but compared to ocean seawater as well as meteoric, connate and formation waters ^{18}O is enriched and ^{13}C is enriched with regard to sedimentary organic carbon. Possibilities to explain the origin of the marble horizon are: (1) resedimentation processes involving shelf carbonates; and (2) precipitation and/or replacement of carbonate, involving marine organic CO_2 or CO_2 from hydrothermal/fumarolic activity. Possibility (1) may be excluded due to the pelagic sedimentary facies surrounding the marble. Therefore "in situ" precipitation of carbonate from seawater probably in the vicinity of the Matchless Amphibolite shortly after its extrusion is considered to explain better the isotope signatures obtained.

3.6 Vertical facies sequences and sedimentary cycles

(a) Vertical facies sequences

The facies described above occur within characteristic facies sequences throughout the Khomas Trough. Since the comparison with the turbidite facies classes of Pickering et al. (1986) has been drawn in section 3.5, their facies will be referred to for convenience in the following. A representative sample of measured sections is presented in Figures 3.12 and 3.13. This shows that vertical facies sequences mostly involve very thick-bedded (north) to thin-bedded (south) facies B layers which are associated with facies C and E at the northern margin of the Khomas

Trough (Figs. 3.12, 3.13, 3.14,A and B); with facies C, D and partly E in the centre (Figs. 3.9,B, 3.12, 3.13, 3.14,C); and with facies E and partly C in the south (Figs. 3.12, 3.13, 3.14, D). Also in the centre of the traverse facies C is associated with facies D. In the south and centre of the trough pelagic facies G graphite schists are intercalated within turbiditic facies B and C (Fig. 3.3,I). The turbiditic carbonate facies is distributed throughout the traverse and preferentially associated with facies B and C psammities.

The development of bed thicknesses of psammities and pelites shows similar trends for both rock types in the north and centre of the Khomas Trough but different trends in the south. This is expressed by a decrease in psammite layer thickness to a maximum of about 20 cm in the south whilst pelitic units increase in thickness to several metres (Fig. 3.12). An exception is a limited area on the farm Okasume where thicker beds are developed (Figs. 3.12 and 3.13,H). It is due to the greater differential weathering of the pelitic units that measured sections have a recording bias. They preferentially contain information from the psammitic parts of each sequence and do therefore not reflect psammite/pelite percentages on a larger scale along the traverse. Figure 3.12, however, indicates the increase of pelitic percentage in the southern part of the Khomas Trough.




Fig. 3.13: Representative measured sections showing facies analysis, sedimentary cycles and bed thickness plots. Diagrams from A to H confirm the change from small-scale thinning-upward to thickening-upward cycles respectively from north to south. Positions of sections are indicated in Figure 3.12.




Fig. 3.13 (continued).

In addition to the change in bed thickness it is important to note that there is a pronounced change in sedimentary features in the centre of the traverse. Sedimentary structures are developed commonly in sequences north of the upper Koam canyon (Figs. 3.12, G and 3.13). To the south, however, only graded layering appears to be preserved.




Fig. 3.14: Facies sequences. (A) Thick-bedded facies B turbidite underlying facies E turbidite, northern Khomas Trough, farm Keises 312. (B) Facies B, C and E turbidites in the northern Khomas Trough, farm Keises 312. (C) Facies B, C and E turbidites in the central Khomas Trough, farm Dagbreek 355. (D) Thin-bedded facies E turbidites below the Matchless Amphibolite in the southern Khomas Trough. Height of scale is 1.8 m. Farm Kobos 305.

(b) Sedimentary cycles

Further analyses of measured sections has shown that facies sequences are organized into sedimentary cycles which are developed on all scales. Cyclicity on a kilometre scale is already conspicuous in the landscape which exhibits a regular alternation of zones with smooth topography and scarce outcrop which contrast with rough, steep topographies with abundant outcrop. Mapping along the traverse and along some sections west towards the Namib desert has revealed that these topographical changes are related to sedimentary facies changes from major pelite dominated to psammite dominated successions respectively. The major cyclic sequences are also visible on the Landsat image of the area (Fig. 2.4) and they may be traced laterally for at least 100 km. Their distribution along the study traverse is shown in Figure 3.15. Medium-scale cycles have proved to be difficult to evaluate in measured sections due to outcrop preservation but could be mapped in the landscape where they are well shown (Fig. 3.16, A-D). The medium-scale cycles are between 200 m and 500 m thick and the measured cycles have been incorporated into the large cycles in Figure 3.15.




Fig. 3.15: Map of the study traverse showing the position of major sedimentary cycles and non-cyclic sequences in relation to marker units. Note the decrease of bed thicknesses from north to south.

Small-scale cycles vary in thickness from 2 m to 30 m and are nested within the medium-scale cycles. Bed thickness plots of some selected outcrops are given in Figure 3.13. These confirm that the north of the Khomas Trough comprises two major thinning-upward sequences (Figs. 3.15, 3.16,E), the southern of which, however, includes minor thickening-upward cycles (Fig. 3.15).

Towards the south a wide zone of nested thickening-upward cycles follows (Figs. 3.13, 3.15, 3.16,F and G) to be succeeded by non-cyclic successions in the south (Figs. 3.12, 3.15). A small zone containing thickening-upward cycles is incorporated within the latter zone (Figs. 3.15, 3.16,D).

Since the Kuiseb schists are strongly deformed and metamorphosed, a considerable amount of internal folding is developed within the sedimentary cycles. Notwithstanding this strong but widely coaxial deformation, sequential lithofacies changes have been shown to occur on all scales. Therefore the major large-scale cycles are regarded as coherent stratigraphic units which extend for more than 100 km laterally.

Fig. 3.16: Sedimentary cycles.

(A) Several thickening-upward cycles, approx. 50 m thick, etched in the landscape. Farm Dagbreek 365.

(B) Thickening-upward cycles, approx. 200 m thick. Farm Kaan 309.


(C) Thickening-upward cycles, approx. 200 m thick. Farm Kaan 309.

(D) Thickening-upward cycles, intercalated with thick non-cyclic basin plain sequences of the southern Khomas Trough (compare with Fig. 3.13). Farm Okasume 304.

(E) Small-scale thinning-upward cycles. Psammitic lithologies are light coloured, pelites are dark. Beds thin towards the stratigraphic top (top of the photograph). Farm Dagbreek 365.

(F) Small-scale thickening-upward cycle (3.5 m). Compare also bed thickness plot in Figure 3.13,D which contains this cycle. Individual beds are demarcated by bars. Hammer for scale. Farm Tsawisis 308.

(G) Thickening-upward cycle (approx. 15 m thick) within lobe sequence of the southern Khomas Trough. Sledge hammer for scale (circled) is 59 cm long. Farm Okasume 304.



3.7. Facies models

Most of the seven facies described above may be interpreted in terms of facies models for turbidites and pelagic sediments. The turbidites in the Khomas Trough are largely accommodated within the medium-grained turbidite model terminology of Stow, 1986 and Pickering et al., 1986). This involves the classical Bouma (1962) sequence and represents the depositional model for most of facies C and partly facies B and D (Fig. 3.7). The well-known five Bouma divisions are T_a to T_e . It seems, however, that incomplete sequences (top-absent, mid-absent, base-absent etc.) are the rule and this formed also the base of the facies subdivisions into immature facies (B1, C1) and mature facies (B2, C2) by Pickering et al. (1986). Most of the sand-rich turbidites (facies C) are deposits of high-concentration turbidity currents in contrast to low concentration currents of facies D. Tractional processes play a role where flows are underladen (Pickering et al., 1986).

The fine-grained turbidite model (Stow and Piper, 1984) represents much of facies D and E (Fig. 3.7). In this model graded, silt-laminated muds pass upward into graded muds and finally into ungraded muds. These sequences have been described by Piper (1978) and Stow and Shanmugam (1980). Again in this facies complete sequences are the exception and top-, mid-, and base-absent units occur. Waning current velocities account for the grading,

and the alternation of silt and mud laminae originated from depositional sorting of silt grains from clay flocs due to shear in the bottom boundary layer (Stow and Bowen, 1980).

Resedimented carbonates have become incorporated with the clastic depositional system in the Khomas Trough. Whilst fine-grained carbonate material would have tended to disperse in the water column and settle out with the pelagic background sediments (Stow, 1986), the sand and silt grade carbonates have been deposited with the turbidity currents to produce a mix which was metamorphosed as calc-silicate facies.

More than 100 m thick pelitic successions in the southern part of the traverse are considered to largely represent pelagic and hemipelagic deposits. Pelagic and hemipelagic facies models are very similar to bottom current (contourite) facies models and impose a recognition problem in the pre-Palaeozoic rock record (Gorsline, 1984). All these deposits occur mainly in facies E and G and lack direct evidence for current flow. Since muds up to several metres thick have been reported from turbidite basins ("unifites" of Stanley, 1981) it is extremely difficult to distinguish structureless pelitic turbidites, pelagic/hemipelagic pelites and pelitic bottom current deposits, especially in the metamorphosed sequences described here.

Further facies models encountered in the literature are slides and slumps (Woodcock, 1976), debrites (Thornton, 1984) and coarse-grained turbidites (Lowe, 1982). There is no evidence for slides, slumps or debris flow deposits in the Khomas Trough to date. Although the sediments have been considerably recrystallized during metamorphism it may be postulated that original grain sizes have not exceeded sand size. It is rather unlikely that a conglomeratic precursor recrystallized during metamorphism to produce the fine and medium "grain sizes" encountered in the study area. The relative uniformity of grain size is a regional feature. Some authors have, however, suggested that some of the carbonate-bearing nodules and spindles described above under the metacarbonate facies represent original sedimentary clasts (De Waal, 1966; Preussinger et al., 1987).

3.8 Depositional setting of the Khomas Trough

3.8.1 Previous sedimentation models

For the Khomas Trough interpretations of the sedimentation patterns have only been speculative in the past. Martin (1965) characterizes the Kuiseb schists as a "typical eugeosynclinal assemblage". Miller (1979) has initially demonstrated graded bedding and he concluded that the "flysch sediments" were deposited by turbidity currents. This has subsequently been confirmed

by several authors (e.g. Downing, 1983; Preussinger et al., 1987). Without presenting data, Downing (1983) has speculated upon a submarine fan environment for the Kuiseb schists.

3.8.2 Geochemical constraints on the source area of Kuiseb metagreywackes

With regard to a possible source area, chemical compositions of the Kuiseb metagreywackes of this study (see section 3.3), of Schneider (1983) and of Phillips et al. (1989) are compared in Table 3.3 with greywackes from different geotectonic settings on the basis of data compiled by Bhatia (1983) and Bhatia and Crook (1986). Also given are "average" greywacke analyses from Pettijohn (1963). The table demonstrates unusually high average contents of TiO_2 , Cr and Ni in the Kuiseb metagreywackes which is confirmed by the data of Phillips et al. (1989) who studied in detail an outcrop near Windhoek. The overall compositions show striking similarities to continental island arc and active continental margin greywackes which is confirmed particularly by the immobile elements.

Within Crook's (1974) classification based on SiO_2 and $\text{Na}_2\text{O}/\text{K}_2\text{O}$ contents the Kuiseb metagreywackes classify as quartz-intermediate Andean margin greywackes. Roser and Korsch (1986) have also analysed greywackes from different tectonic settings and have

tried to characterize these by means of major element ratios. The Kuiseb data have been plotted into one of their diagrams and this also confirms an active continental margin source for the

Table 3.3: Chemical composition of greywackes from various geotectonic settings (Bhatia, 1983; Bhatia and Crook, 1986 and Pettijohn, 1963) in comparison with average Kuiseb metagreywackes (this study; Schneider, 1983; Phillips et al., 1989).

	A	B	C	D	E	F	G	H
SiO ₂ (wt %)	72.40	58.83	70.69	73.86	81.95	71.79	70.54	66.70
TiO ₂	.85	1.06	.64	.46	.49	.93	.78	.60
Al ₂ O ₃	11.19	17.11	14.04	12.89	8.41	11.71	12.10	13.50
FeO	nd	5.52	3.05	1.58	1.76	5.03	3.19	3.50
Fe ₂ O ₃ *	5.06	1.95	1.43	1.30	1.32	nd	1.63	1.60
MnO	.08	.15	.10	.10	.05	.08	.10	.10
MgO	2.03	3.65	1.97	1.23	1.39	2.23	2.24	2.10
CaO	1.70	5.83	2.68	2.48	1.89	1.58	2.73	2.50
Na ₂ O	2.78	4.10	3.12	2.77	1.07	2.28	2.84	2.90
K ₂ O	2.16	1.60	1.89	2.90	1.71	2.17	1.76	2.00
P ₂ O ₅	.19	.26	.16	.09	.12	.18	.18	.20
Cr (ppm)	77	37	51	26	39	76		
Ni	27	11	13	10	8	24		
Rb	85	18	67	115	61	88		
Sr	146	637	250	141	66	114		
Ba	462	370	444	522	253	389		
V	99	131	89	48	31	96		
Y	33	20	24	25	27	40		
Zn	71	89	74	52	26	67		
Nb	10	2	9	11	8	11		
Zr	243	96	229	179	298	238		

* total Fe as Fe₂O₃ in Kuiseb schists

A - Kuiseb metagreywacke (this study; quartz-plagioclase-biotite schist) (n=70)

B - oceanic island arc greywacke (n=82)

C - continental island arc greywacke (n=257)

D - active continental margin greywacke (n=212)

E - passive continental margin greywacke (n=123)

F - Kuiseb "gneiss" (Phillips et al., 1989; n=17)

G - Kuiseb greywacke (Schneider, 1983; n=57)

H - average greywacke (Pettijohn, 1963; n=61)

precursor (Fig. 3.17). Although major elements have been modified during metamorphism, the variation diagrams (Fig. 3.1) show that K_2O , Na_2O and SiO_2 have been enriched. Pettijohn (1975) points out that K_2O and Na_2O increase with increased maturity of the terrigenoclastic sedimentary rock. It may therefore be expected that K_2O/Na_2O ratios were originally lower, a fact which emphasises even more, considering Figure 3.17, the probable active margin derivation of the Kuiseb metagreywackes.




Fig. 3.17: Major element plot distinguishing tectonic settings of sandstone-mudstone suites (after Roser and Korsch, 1986).

These results suggesting that an active continental margin with both volcanic and plutonic magmatic suites contributed considerably towards the precursor of the Kuiseb metagreywackes in the Khomas Trough are not in accordance with the findings of Miller et al. (1983) who studied the geochemistry of the Kuiseb schists along a traverse between Okahandja and Windhoek. Based on the geochemical maturity index of Pettijohn (1975) the authors conclude that a southern and central group in the Khomas Trough is related to a passive margin provenance whereas a northern group has been supplied by a northerly-situated rhyolite-rich source.

3.8.3 Interpretation of elongate submarine fan and basin plain depositional environments

By the very nature of the metamorphosed Kuiseb Formation metasediments, comparison must be made between the sedimentary features recognized and those facies associations already described from more recent turbidite sequences. Within marine environments three fundamental "facies associations" (Nelson and Nilsen, 1984) or "environments" (Stow, 1986) have been identified: slope aprons, submarine fans and basin plains. The facies and facies models which have been documented and summarized above are interpreted to indicate submarine fan environments and basin plain environments. The lateral extent of marker horizons, the consistent paleocurrents from the north-east parallel with the tectonic

strike, the size of sedimentary cycles and the uniformity in lithologies and grain sizes strongly suggest a mixed-sediment elongate fan system (Nelson and Nilsen, 1984).

Interpreting submarine fan facies associations from "proximal" to "distal" has limitations. Various authors have put emphasis on the problems arising from the comparison of modern fan settings with those of ancient fans (Normark et al., 1983/84; Shanmugam et al., 1988). This is initially a problem of study approaches since modern fan research deals mainly with morphologic aspects and shallow drill cores. Subsequently the turbidite facies scheme of Mutti and Ricci Lucchi (1972), developed on an ancient mixed-sediment fan (Nelson and Nilsen, 1984), has been applied to modern fan settings. Ancient fans on the other hand are interpreted from vertical facies sequences which are dependent on outcrop preservation. Large-scale morphological features which help to confirm a fan shape are extremely difficult to evaluate. In the rock record it is problematic on a smaller scale to recognize channels, which are such an important feature of fan settings, as has been pointed out by Normark et al. (1983/84) and Shanmugam et al. (1988).

Interpretation of sedimentary sequences in the Khomas Trough is made with the background that the succession is subdivided into individual thrust-bound sequences (this will be shown in Chapter 4). However, having taken internal folding into account during the measurements in the field, it is implicit that facies rela-

tionships are largely intact within the individual slabs. The fold style and south-east directed vergences have produced thick, upright fold limbs with upward-facing sequences and only very narrow overturned limbs. Stratigraphic relations between adjacent slabs, however, are unknown and considerable parts of the fan system might be missing but are more probably repeated.

The distribution and organization of facies and vertical facies sequences, together with cyclic patterns as shown in Figures 3.12, 3.13 and 3.15, are interpreted to document middle fan and outer fan depositional environments of an elongate submarine fan in the north and centre of the Khomas Trough. Basin plain deposits are developed in the south (Fig. 3.18). Since there is no evidence for coarse-grained, conglomerate facies A (Pickering et al., 1986; Mutti and Ricci Lucchi, 1975) on a larger scale as well as for facies F "chaotic deposits" (Pickering et al., 1986; Mutti and Ricci Lucchi, 1975) it is inferred that inner fan environments and slump and slide deposits have not been developed on the line of this traverse or have not been preserved. Inner fan depositional environments are typically small and closely situated to the feeding source of elongate fans (e.g. Nelson, 1983/84) and may therefore easily be obliterated or developed laterally in ancient orogenic settings.



In the northern part of the Khomas Trough middle fan depositional environments of an idealized fan system (Nelson and Nilsen, 1984) are indicated by the dominance of thick-bedded over thin-bedded

turbidites within an overall thinning-upward trend. Irregular alternations of thinning- and thickening-upward cycles together with small channels and incomplete Bouma sequences suggest, however, the widespread occurrence of interchannel deposits (Nelson and Nilsen, 1974; Stow, 1986).

Facies features outlined above from the centre of the trough are consistent with outer fan lobe (in the sense of Mutti and Ricci Lucchi, 1972) and fan fringe facies associations (summaries in Nelson and Nilsen, 1984 and Shanmugam and Moiola, 1988). The small-scale thickening-upward cycles (up to 5 m thick) most probably represent compensation cycles as described by Mutti and Sonnino (1981). Regarding cyclicity, Stow (1986) has pointed out that proximal sandy lobes tend to show thickening-upward sequences in contrast to distal sandy and muddy lobes which show more symmetrical sequences.

Sedimentary sequences in the southern Khomas Trough, from several kilometres north of the Matchless Amphibolite to the Southern Margin Zone, document the transition from outer fan lobes to fan fringe and basin plain successions (Fig. 3.18). In favour of this interpretation are: (1) thin-bedded turbidites intercalated with pelagic deposits; (2) the overall decreasing bed thickness of turbidites towards the southern margin of the Khomas Trough; and simultaneously, (3) the increasing thickness of large-scale pelagic successions (pelites and graphite schists) up to a hundred metres scale towards the south, reflecting the preponderance of

Fig. 3.18: (A) Map of depositional palaeoenvironments interpreted for the Khomas Trough. Middle fan and outer fan deposits of an elongate submarine fan system as well as basin plain deposits are developed in the north, centre and south respectively. (B) Schematic profile through the southern inland branch of the Damara Orogen showing palaeoenvironmental setting and facies associations in the present-day Khomas Trough and in adjacent areas. Note the position of the Matchless Amphibolite.



hemipelagic and pelagic sedimentation over turbiditic processes. The narrow zone which comprises thick psammitic beds organized within thickening-upward cycles and intercalated within the basin plain succession (Figs. 3.12 and 3.18) might either be explained by structural interposition or by an episode of outbuilding of a lobe sequence into the distal environments. This would be similar to one of the basin-plain lobes described by Pickering (1981) from the late Proterozoic Kongsfjord turbidite system and by Ricci Lucchi and Valmori (1980) from the Italian Apennines.

There are most probably levee, interchannel and contourite environments intercalated in various parts of the succession. Facies D deposits in the centre of the Khomas Trough are especially likely candidates for interchannel deposits in the outer fan. Levees, interchannels and thin-bedded basin plain turbidites are, however, very similar in depositional patterns (Nelson and Nilsen, 1984) and therefore great uncertainties accompany interpretations in an ancient terrain.

Comparing the assignment of cyclicity to various submarine fan facies associations on modern and ancient fans in various studies shows that there are considerable dissimilarities. There seems to be only partial consensus in recognizing the larger-scale thinning-upward trends as inner and middle fan environments as opposed to thickening-upward trends of outer fan environments. In view of the widespread symmetrical sequences occurring in the Khomas Trough the compilation of "typical" vertical sequences of

turbidites and associated sequences by Stow (1985) shows that regular cyclicity, which occurs preferentially in proximal environments, is rather the exception. In outer fan and distal environments symmetrical sequences or non-cyclic sequences are widespread features (Stow, 1985).

3.8.4 Discussion of other possible depositional environments

The basic turbidite sedimentation systems within the marine realm are slope aprons, radial fans, elongate fans in trenches and open basins, and extended deep-sea channel systems. Slope aprons as well as radial fan systems (summaries e.g. in Nelson and Nilsen, 1984 and Stow, 1986) can be ruled out for the Khomas Trough based on the following reasons: (1) the lateral extent and the consistency of major sedimentation units; (2) the overall vertical facies distribution with uniform (metamorphic) psammite grain sizes probably reflecting original sedimentary grain sizes, and mostly regular bedding surfaces; (3) the lack of proximal slope and inner fan deposits; (4) the uniform longitudinal palaeocurrent distribution; and (5) the present day size of the Khomas Trough is larger than most radial fans described in the literature.

Stow et al. (1983/84) point out that fans with elongate shapes also develop in trench floor settings (compared to elongate open basin fans) due to structural confinement and if a large sediment source exists. An ancient example is the Cretaceous Chugach ter-

rane in Alaska (Nilsen and Zuffa, 1982). Underwood and Bachmann (1982) show that trenches may contain debris aprons, elongate fans, axial channel deposits and unchanneled turbidite sheet flows. It has been furthermore emphasized by Nelson and Nilsen (1984) that there are also striking similarities in source debris and depositional patterns amongst elongate trench fans, elongate open basin fans and deep-sea channel turbidites. The authors further emphasize that source muds for these trench fans may be high in organic content due to deposition at depths coincident with oxygen minimum layers in the ocean.

3.9. Palaeoenvironmental synthesis

A palaeoenvironmental interpretation of the Khomas Trough has to take the following regional aspects into account (Fig. 2.3). Towards the south of the Khomas Trough continental margin sediments of the Upper Damara Sequence of the Kalahari Craton have been interpreted to partly represent slope to deep-water turbidites deposited on small fans (Porada and Wittig, 1983; Hoffmann, 1983). On the Congo Craton in the north, calcareous platform sediments are overlain by younger clastic sequences. Along the cratonic margin calcareous turbidites form slope facies associations which have been deposited within radial submarine fan systems according to Porada and Wittig (1983). Margins both north and south of the Khomas Trough have thus been interpreted as platform and slope settings which contain partly turbiditic deep-water sediments (Fig. 2.3).

This study proposes the following palaeoenvironmental setting for the Khomas Trough (Fig. 3.19). Clastic sedimentation probably commenced by divergent plate movements in the Southern Damara Craton (e.g. Miller, 1983b; Henry et al., 1990). The lithofacies and facies associations described in the previous sections indicate that turbidity currents within a submarine fan, here named Khomas Fan, were the main depositional processes within the Khomas Sea which separated the Congo and Kalahari Cratons. The turbidites carried overwhelmingly a clastic load but some calcareous material which was most probably derived from the adjacent shelf to the north was included in the flows. The sediment load was effectively transported laterally parallel to the basin margins from the north-east to the south-west. This type of longitudinal, long distance sediment transport is best interpreted by deposition within an elongate submarine fan as shown in Figure 3.19. "Proximal" to "distal" relationships occur from north to south confirming the development and preservation of middle fan, outer fan and basin plain depositional environments through time. The mass flow processes were accompanied by contemporaneous pelagic and hemipelagic settling but parts of the pelagic and hemipelagic sediment has also been involved in resedimentation processes during progressive development of the basin. Various graphite schists intercalated with turbiditic as well as pelagic facies have probably originated from both pelagic settling and transport of organic carbon-rich detritus by turbidity currents into oxygen-deficient, anoxic parts of the Khomas Sea where they have been deposited as black shales.




Fig. 3.19: Palaeoenvironmental model of the Khomas Trough. The elongate Khomas Fan is fed primarily from a mixed volcanic-plutonic active continental margin source which is situated to the north-east of the present Khomas Trough. Pelagic and hemipelagic sedimentation dominates the basin plain towards the south. Continental platform and slope sedimentation, partly in submarine fans, occurs on the Congo and Kalahari Cratons on either side of the Khomas Sea.

Palaeocurrent data confirm that the main source for the clastic sediment was situated towards the north-eastern end of the present Khomas Trough (Fig. 3.19).

Geochemical patterns show volcanic source influence and point towards continental island arc and/or active continental margin derivation of the precursor greywackes. Judging from these data the most probable provenance areas are either the Proterozoic mobile belts in the east (Lufilian Arc, Zambezi Belt), or, alternatively, a volcanic arc feeding in from the Central Zone (Fig. 3.19).

The width and depth of the initial Khomas Sea has repeatedly been a controversial issue and speculations have been based on overall geotectonic models of the Damara Orogen. The sedimentological data presented here suggest that the basin has been wide enough to accommodate thick submarine fan and basin plain sequences. Furthermore two contrasting depositional environments, clastic and calcareous, have been operating on opposite margins of the basin. No evidence for deposition above wave base, such as symmetric-asymmetric ripples or hummocky cross-stratification is present. Facies C turbidites with base truncated Bouma T_{bcde} divisions do confirm the basinal nature of deposition as does the lack of sedimentary structures together with thin-bedded turbidites and thick pelagic pelites in the southern Khomas Trough. Carbonates indicate deposition above CCD but judging from the present day CCD levels between 4000 m and 5500 m water depth as well as from the interpreted slope successions at adjacent margins, the water depth of the original depository was well in excess of 1500 m (average base of continental slope; Cook et al.,

1982). This estimate is in accordance with data obtained from modern elongate fans on passive and active continental margins (Nelson and Nilsen, 1984).

A comparison with modern and ancient elongate fans shows the considerable size and the shape of the proposed Khomas Fan (Fig. 3.20; Table 3.4). It is interesting in terms of possible tectonic settings that modern studies describe both passive margin fans (e.g. Bengal, Indus, Amazon; Fig. 3.20) and active margin fans (e.g. Astoria, Crati, Magdalena, Zodiac). In strong contrast to this most of the ancient fans (Marnoso-Arenacea, Gottero, Ferrelo, Chugach, Butano, Jackford Formation/Pennsylvanian, Torlesse Terrane, Eastern Alps; Table 3.4) are interpreted as situated at proposed active margins (Bouma et al., 1985). Many of these active margin fans are furthermore elongate in shape and are interpreted to have developed in oceanic trenches. Exceptions are the slope-apron system of the Brae Oil Field in the North Sea (Stow, 1985) and possibly the Late Proterozoic Kongsfjord submarine fan-slope-delta system (Pickering, 1985).




Fig. 3.20: Comparison of the size and shape of the present day outcrop of the Khomas Fan with other ancient and modern fan systems (modified from Barnes and Normark, 1983/84).

In conclusion, the above shows that the facies and the facies associations in the Khomas Trough compare well with published elongate submarine fan settings. The vertical and lateral facies distribution, the high percentage of metasediments which indicates a large sediment supply and the inferred shape of the

Thomas Fan are similar to elongate trench fans developed at active continental margins. Ancient examples are the Cretaceous Chugach terrain in Alaska (Nilsen and Zuffa, 1982), the Middle Phanerozoic Torlesse terrain in New Zealand (MacKinnon and Howell, 1983/84), the Early Palaeozoic of the Central Appalachians (Lash, 1986) and the Cretaceous Shimanto Belt in Japan (Taira et al., 1982).

Table 3.4: Comparison of tectonic settings, sizes, thicknesses and shapes of modern (above the dashed line) and ancient (below the dashed line) fans (from Barnes and Normark, 1983/84). Note that ancient fans are nearly exclusively situated at active continental margins as pointed out by Bouma et al. (1985).

NAME	MARGIN SETTING type of margin, type of crust	LENGTH, WIDTH (RADIUS) (km)	MAX. THICKNESS (m)	SHAPE	REFERENCE
1. Amazon	P, O	720km, 250-700	4200	elongated partial cone	Normark et al., 1983/84
2. Astoria	A, O	250km, 130	2200	trapezoidal	Normark et al., 1983/84
3. Bergat	P, O	2800, 1100	>5000	elongated	Normark et al., 1983/84
4. Cap Ferret	P, C	(75)	1800	elongated dissymmetric	Cousses et al., 1983
5. Brati	A, C	16, 4-5	30	elongated	Normark et al., 1983/84
6. Delgado	T, O	>3500	3000	elongated bi-lobed	Normark et al., 1983/84
7. Ebro	P, O	100, 50	370	oval	Normark et al., 1983/84
8. Indus	P, O	1500, 960max	>3000	fan	Normark et al., 1983/84
9. La Jolla	T, C	40, 50	1600	pear shaped	Graham & Nicholas, 1983
10. Laurentian	P, O	500km-1500km, 200-400	2800	elongated, lobate	Normark et al., 1983/84
11. Magdalena	A, O	(230)	3000	trapezoidal fan	Normark et al., 1983/84
12. Mississippi	P, C/O	540, 570	4000	conical	Normark et al., 1983/84
13. Monterey	T, O	400, 250	2000	quarter cone	Normark et al., 1983/84
14. Navy	T, C	(40)	900	elongate basin	Normark & Piper, 1972
15. Nicobar	A/T, O	(2200)	3000	triangular	Boules et al., 1978
16. Nile	P, C	280, 500	>3000	fan	Maldonado & Stanley, 1978
17. Nizinet	A, O	240, 80	1000	triangular	Stokke et al., 1977
18. Rhone	T, C/O	440, 210	1500	elongated	Normark et al., 1983/84
19. San Lucas	P, O	(60)	1000	rectangular	Normark, 1970
20. Blanca	T, C	215, 30	1000	elongated	Normark et al., 1983/84
21. Brae	P, C	overlapping fans each (5-10)	600	slope-apron elongated	Normark et al., 1983/84
22. Butane	P, C	80, 40	3000	elongated ellipsoidal	Normark et al., 1983/84
23. Congo	A, C	6.4, 6.8	170	arcuate	Normark et al., 1983/84
24. Chugach	P, O	2000, 100	10000	narrow prism	Normark et al., 1983/84
25. Ferrate	A, O	340, 45	1800	elongated	Normark et al., 1983/84
26. Cottat's	A, O	(30, 50)	1500	semicircle	Normark et al., 1983/84
27. Kanto	A, O	175, 40-50	3500	elongated	Normark et al., 1983/84
28. Marrocco- Arenacea	A, C	Major-27-30, 6-15 Minor-20-25, 4-10	1000	elongated	Normark et al., 1983/84
29. Thomas	A, O	425, 100	7 (>5000)	elongated	this study

abbreviations: (a) type of margin: A-accretionary; P-passive; T-transform; S-subduction.
(b) type of crust: C-continental; O-oceanic.

4. STRUCTURAL GEOLOGY OF THE KHOMAS TROUGH

4.1 Introduction

Structural studies along the study traverse examined the overall deformation pattern in order to help constrain the tectonic setting of the Khomas Trough. The studies benefited from the fact that almost continuous exposure exists along the river sections. Detailed structural analyses in the Khomas Trough were first undertaken by Gevers (1963) and Smith (1965) in the vicinity of the Donkerhoek Granite south-west of Okahandja, followed by Hälbig (1970, 1977), Blaine (1977) and Sawyer (1981). Hälbig (1977) has studied the Khomas Trough between Okahandja and Windhoek, 100 km to the east of the present study traverse. A reconnaissance study by Hälbig (op.cit.) in the western Khomas Trough was largely based on aerial photographs. Kasch (1975, 1983c) studied the Kuiseb Formation east of Windhoek in the Omitara area whilst Sawyer (1981) and Preussinger (1987, 1990) concentrated on the structural style of the Gorob mining area in the Namib desert, 150 km south-west of the present study traverse.

In the study area five phases of deformation, four of which are associated with cleavage development, have been discerned. Changes in fabric development which sometimes coincide with changes in fold morphology allow subdivision into four structural domains, labelled A, B, C, and D. "Domain" here is used in the grammatical

and physical sense of a region which has been affected by a unitary influence. The characteristics of domains, i.e. fabric elements and folds, will be described in section 4.2 and the contact of the Kuiseb metasediments with the Donkerhoek Granite in section 4.3. Structural discontinuities play an important role in the deformation history and these will be discussed separately in section 4.4. The gross structural style and the timing of deformational events (section 4.5) are interpreted in a unitary structural model for the Khomas Trough in section 4.6.

Since there is no general classification scheme on the terminology of fabric elements, "foliation" is used in the current text to describe generally planar surfaces of structural origin. Following the subdivision of cleavage types by Hobbs et al. (1976), axial planar foliations are represented in the study area by metamorphic banding cleavages and crenulation cleavages. Transposed foliations in the southern part of the traverse represent the second major group. Penetrative cleavage is a more general term used for fabrics which are characterized by the preferred alignment (newly crystallized and/or reorientated) of a particular mineral species. The nomenclature of Fleuty (1964) is used for fold shapes (i.e. open, close, tight). Where more accurate measurements were taken, Ramsay's (1967) fold classification is employed.

The earliest planar element developed in most parts of the traverse is original sedimentary bedding defined by graded and non-graded units, but also plane bedding and a variety of other sedimentary structures documented in Chapter 3. Sedimentary bedding is referred to as S_0 . As far as other structural elements are concerned the terminology of Turner and Weiss (1963) is used where S_n characterizes planar, penetrative fabrics, L_n linear penetrative fabrics and F_n folding of fabrics. The age order of consecutive fabric generations is denoted by suffixes 1,2,3,4. The deformations identified are labelled D_1 to D_5 and they are characterized and defined by the following structural elements: (1) D_1 by an S_1 cleavage and F_1 folds; (2) D_2 by an S_2 cleavage, an L_2 lineation and F_2 folds; (3) D_3 by an S_3 cleavage and F_3 folds; (4) D_4 by an S_4 cleavage and F_4 folds; and (5) D_5 by F_5 folds. It is important to note that D_1 structural elements in the southern part of the traverse could not conclusively be established for the northern part. There is evidence, however, that the structural elements which are associated with D_2 are developed throughout the traverse and this therefore serves as a structural datum or benchmark. These relationships, nomenclatures and the occurrences of planar elements and folds within the particular domains are summarized in Table 4.1.

4.2 Structural characteristics of domains

The problems of correlating structures, microstructures and metamorphic assemblages in multiply deformed terrains has repeatedly

Table 4.1: Summary of planar fabrics and folds encountered in domains A-D along the study traverse.

	Planar elements				Folds				
Domain A	S _{0,1,2,3}			S ₄				F ₄	F ₅
Domain B	S ₁	S ₂	S ₃	S ₄	F ₁	F ₂	F ₃	F ₄	
Domain C		S ₂	S ₃		?	F ₂	F ₃		
Domain D		S ₂	S ₃	S ₄		F ₂	F ₃	F ₄	

been pointed out (e.g. Spry, 1963; Williams, 1985). To obtain a relative timing of events in an area, as many "positive" relationships as possible have to be taken into consideration. In the study area, the following lines of evidence have been used to distinguish consecutive phases of cleavage development and fold formation:

- (1) preferred orientation and character of planar and linear fabric elements;
- (2) overprinting of planar and linear fabrics of earlier folds;
- (3) crystallization and recrystallization of metamorphic minerals and its relationships to the present foliations (see Chapter 6);
- (4) styles of mesoscopic and macroscopic folds.




Fig. 4.1: Map of the study traverse showing geographical locations of structural domains A-D.

The first two of the above criteria define the four domains which are shown in Figure 4.1. In comparison with an earlier publication of Kukla et al. (1988) it is apparent that on the basis of additional data a new subdivision of the traverse has been undertaken (Table 4.2). The structural profile along the study traverse (Fig. 4.2) indicates that on the basis of fold style a further subdivision is possible. This has been omitted because fabric elements in this area represent a more reliable "first order" structural marker. The fold geometry is much more dependent on the mechanical and rheological state of the rocks during the folding process (Ramsay and Huber, 1987).

The symbols used in the following for various structural elements are summarized in Table 4.3. Generally orientations of axial planes give strike, angle of dip and dip direction (i.e. $030^{\circ}/40^{\circ}\text{NW}$). Orientations of linear elements are recorded by azimuth and angle of plunge (i.e. $060^{\circ}/11^{\circ}$). All structural data are presented on a Schmidt lower hemisphere stereographic net.

Table 4.2: Comparison of the subdivision of the study traverse into domains A-D of this study with an earlier study of Kukla et al. (1988).

Domain	E	D	C	B	A	Kukla et al. 1988
Domain	D	C	B	A		Kukla this study




Fig. 4.2: Structural profile across the Khomas Trough showing the size and the style of major D_2 folds.

4.2.1 Domain A

This domain covers approximately the area between the confluence of the Koam and Kuiseb rivers at the southern margin of the Khomas Trough and the Us Pass road in the north (Fig. 4.3).

(a) Planar fabrics

The southernmost part of the traverse is characterized by a distinct subparallel orientation of planar fabric elements. Judging from other parts of the traverse where original bedding is

Table 4.3: Summary of the symbols used for various structural elements.

PLANAR ELEMENTS		Pole	Trace
Sedimentary layering, strike and dip	S ₀	x	
Metamorphic foliation	S ₁	o	
Metamorphic foliation	S ₂	Δ	
D ₂ axial plane		Δ	
Metamorphic foliation	S ₃	Σ	
D ₃ axial plane		Σ	
Crenulation cleavage	S ₄	□	
D ₄ axial plane		■	
D ₅ axial plane (Kink folds, only axial plane readings)		*	
Antiform axial surface trace (north dipping)			
Synform axial surface trace (north dipping)			
Exposed normal fault (with dip tick)			
Exposed reverse or thrust fault (triangle on upper sheet)			
Infer. reverse or thrust fault (triangle on upper sheet)			
Thrust zone (triangle on upper sheet)			
LINEAR ELEMENTS		Pole	Trace
D ₂ fold hinge line (with azimuth and angle of plunge)		⊙	
D ₃ fold hinge line (with azimuth and angle of plunge)		⊙	
D ₄ fold hinge line (with azimuth and angle of plunge)		⊙	
D ₅ kink fold hinge line (with azimuth and angle of plunge)		⊙	
D ₂ mineral lineation	L _{2A}	*	
Intersection line S ₀ /S ₂	L _{2B}	Δ	
Long axes of calc-silicate spindles		•	

evident, it is inferred that lithological contacts between meta-greywackes and pelites in this domain also represent original sedimentary layering. Since there is evidence for three penetrative fabrics in the adjacent domain B (Fig. 4.1), subparallel planar elements in this domain are inferred to constitute an $S_{0,1,2,3}$ composite cleavage. The mean orientation of this fabric is $052^{\circ}/35^{\circ}\text{NW}$. It is mainly defined by the parallel to subparallel alignment of chlorite, muscovite and biotite which encloses staurolite, kyanite and garnet (Fig. 4.4,A). Within the composite cleavage domains symmetrical boudinage occurs which is associated with quartz-chlorite-ankerite segregations within the extensional spaces. The composite cleavage is overprinted by a weak S_4 crenulation cleavage in pelitic lithologies (Fig. 4.4,B). The crenulation fabric dips moderate to steep towards the north-east ($133^{\circ}/84^{\circ}\text{NE}$).

(b) Linear elements

Throughout the domain, a prominent mineral lineation comprising elongate biotite aggregates is developed on composite cleavage surfaces. Although data show a considerable scatter there is a major cluster with a mean orientation of $336^{\circ}/40^{\circ}$. A partial girdle representing an anticlockwise shift of orientations from north-north-west towards west-north-west appears to occur towards the north of the domain (Fig. 4.3). However, to the east of the study traverse close to the Us Pass, an S_4 crenulation cleavage has been observed with a biotite lineation comparable in characteristics and orientations with the west-north-westerly trends




Fig. 4.3: Map of the study traverse showing a selection of structural data for domain A. See Table 4.3 for explanation of symbols; key gives number of measurements.




Fig. 4.4: Microtextures in domain A. Tracings from thin sections showing: (A) $S_{0,1,2,3}$ composite cleavage illustrating the parallel to subparallel alignment of biotite within a chlorite-muscovite matrix enclosing garnet I (specimen PK 855, farm Usambara 304, south of Us Pass road); (B) Chlorite-biotite schist showing S_4 crenulation cleavage developed within the $S_{0,1,2,3}$ composite cleavage. Note microfaults at hinge lines (specimen PK 140, farm Usambara 304, south of Us Pass road).

just described. It can therefore not be excluded that in fact two different generations have been measured. Left-lateral shearing along the southern margin of the Khomas Trough may on the other hand also account for this observed shift of linear element orientations. A second type of linear element is represented by deformed quartz-chlorite-carbonate concretions, set mostly in pelitic lithologies, which are up to several tens of centimetres long. The long axes of these concretions are parallel to the fold axes in this area which are orientated $057^{\circ}/5^{\circ}$.

(c) Folds

No major folds have been observed within this domain. Fold structures occurring are asymmetric and monoclinical kink folds, as defined by Ramsay and Huber (1987). The composite cleavage is deflected from its original orientation within kink bands which are 10-100 cm wide. Axial surfaces (kink planes) dip 20° - 60° towards 156° which is opposite to the north-west dipping attitude of the regional cleavage. Quartz-filled dilation spaces occur parallel to the kinked surfaces (Fig. 4.5) and kinking is closely associated with joint planes. No direct relationship of kink folds with fabric elements could be observed but the kinking occurred subsequently to faulting events which displaced the S_4 cleavage.




Fig. 4.5: Small-scale (D_5) kink band in domain A, showing quartz-filled dilation space parallel to the $S_{0,1,2,3}$ composite cleavage. Lens cap for scale is circled. Farm Usambara 304, south of Us Pass road.

4.2.2 Domain B

Various generations of fabric elements and folds are discernible within this domain and in domains C and D towards the north. Five planar elements and several linear elements can be distinguished including bedding. The domain covers an area from the Us Pass road in the south to the northern part of the farm Kaan Dam (Fig. 4.6). The Matchless Amphibolite is situated in the centre of this domain.

(a) Planar fabrics

Bedding S_0 can be readily defined from original layering. This is evident in parts of the sequence where graded bedding occurs. Graded layers which provide younging evidence are more quartz-




Fig. 4.6: Map of the study traverse showing a selection of structural data for the southern (A), central (B), and northern (C) part of domain B. See Table 4.3 for explanation of symbols; key gives number of measurements.

and feldspar-rich at the base and more mica-rich at the top, representing a metamorphosed compositional grading. The orientation of bedding is variable but generally trends north-east and dips moderately towards the north-west ($054^{\circ}/40^{\circ}\text{NW}$). In contrast to bedding S_0 , the earliest structural fabric is an S_1 compositional banding with alternating quartz-rich and mica-rich layers orientated obliquely to bedding (Fig. 4.7,A).

Because of later refolding (Fig. 4.7,B) there is no consistency in the orientation of S_1 which is strongly transposed within S_2 cleavage domains to be preferentially preserved as a crenulation in F_2 fold hinges (Fig. 4.8). The fabric dips both towards the south-east ($050^{\circ}/30^{\circ}\text{SE}$) and the north-west ($060^{\circ}/30^{\circ}\text{NW}$; Fig. 4.6). The S_1 fabric is characterized by an early generation of biotites which may be enclosed and wrapped-around by later biotites developed in S_2 . Further evidence for S_1 comes from early quartz veins (Fig. 4.7,C) and calc-silicate layers which parallel S_0 and which are folded by D_1 and subsequently by D_2 (Fig. 4.7,B).

The second recognizable structural fabric (S_2) is a strong, penetrative cleavage throughout the domain and a metamorphic banding cleavage in which S_0 and S_1 are partly transposed by D_2 (Fig. 4.7,A) in the centre and north. The S_2 fabric dips moderately (30° - 40°) to the north-west (060°) and occurs axial planar to F_2 folds. Fanning of the cleavage and refraction at psammite - pelite contacts is common. The character of the S_2 fabric changes with the lithology shown by the widths of the quartz-feldspar-rich and the layer-silicate-rich bands which vary from less

Fig. 4.7: Planar fabrics and folds in domain B.

(A) Transposition of S_1 and refraction of S_2 at lithological contacts S_0 (indicated by arrows). Sedimentary younging indicated by graded layering is towards the bottom of the photograph. Locality Koam canyon, farm Annelie 412.





(B) Calc-silicate layer folded within pelitic lithologies, representing intrafolial D_2 fold within S_2 cleavage domains. Folded and transposed S_1 fabric also indicated by arrow. Farm Usambara 304, north of US Pass road.

(C) Photograph showing intrafolial D_2 folds within the S_2 cleavage and overprinting S_4 crenulation cleavage in pelitic schist. Farm Usambara 304, north of US Pass road.

(D) Narrow shear zone in psammitic lithologies showing small-scale F_3 fold. The biotite fabric constituting the S_2 cleavage is deformed about the fold and the penetrative S_3 cleavage is developed in the fold hinge. Koam canyon, farm Annelie 412.

(E) Photograph showing overprinting relationships of deformations D_2 - D_4 in narrow shear zone in pelitic lithologies. S_2 is folded by D_3 which developed small-scale F_3 folds and a penetrative S_3 cleavage; these are overprinted by the S_4 crenulation cleavage. All planar fabrics are indicated by arrows. Matchless Amphibolite sequence, farm Annelie 412.

(F) Flattened, concentric D_2 folds (class 1C, : Ramsay, 1967) in the Koam canyon section. Height of scale (circled) is 1.7 m. Farm Annelie 412.



than one millimetre to about one centimetre. S_2 is defined by the preferred alignment of biotite and chlorite constituting either a penetrative foliation or a wavy to anastomosing network (Fig. 4.8). Calc-silicate spindles with sizes from several centimetres to several tens of centimetres are mostly orientated with their long axes parallel to S_2 .




Fig. 4.8: Tracing from thin section showing hinge area of minor F_2 fold developed in pelitic lithologies. The S_1 fabric is transposed and crenulated within S_2 domains. S_2 constitutes an anastomosing network within psammitic lithologies (specimen PK 86/57, farm Kaan Dam 411, near Khomas Hochland road).

S_3 is a rather unevenly distributed fabric especially in the southern part of this domain. The mean orientation in the centre and north is $050^\circ/30^\circ\text{NW}$ (Fig. 4.6). The fabric is best developed in narrow shear zones where folding of S_2 by D_3 occurs (Fig. 4.7, D and E). Notably in the hinges of F_3 folds S_3 constitutes a penetrative biotite fabric which encloses the S_2 fabric.

An S_4 crenulation cleavage occurs in the highly pelitic lithologies (Fig. 4.7, C and E). The orientation of this fabric is variable (Fig. 4.6) and it describes a clockwise rotation from orientations of $010^\circ/40^\circ\text{--}60^\circ\text{NW}$ in the south to $060^\circ/60^\circ\text{--}80^\circ\text{NW}$ close to the Matchless Amphibolite where the fabric is exceptionally strongly developed (Fig. 4.6, A and B).

(b) Linear elements

There are several linear elements present in this domain. The most distinct is a mineral lineation which plunges $20^\circ\text{--}40^\circ$ towards 320° on S_2 planes and which is therefore designated L_{2A} . Minerals defining L_{2A} are mainly biotite but also plagioclase and amphiboles at the Matchless Amphibolite. A second lineation, L_{2B} , is the S_0/S_2 intersection with an orientation of $060^\circ/0^\circ$. In the south and centre of the domain, the long axes of small calc-silicate spindles constitute a lineation which plunges at $30^\circ\text{--}50^\circ$ towards 315° down-dip on S_2 planes (Fig. 4.6, A). At the Matchless Amphibolite the long axes of pillow structures plunge $330^\circ/35^\circ$ forming a down-dip lineation on S_2 planes together with the elongated plagioclase porphyroblasts they contain. In the southern

part of the domain on the farm Usambara the long axes of quartz-chlorite-carbonate concretions are orientated $250^{\circ}/10^{\circ}$ (Fig. 4.6,A).

(c) Folds

D_2 structures represent the major fold phase in this domain. Folds are developed on all scales varying from cm-scale intrafolial folds to isoclinal folds with wavelengths of up to 250 m. Quartz and calc-silicate layers which parallel S_0 are folded by D_2 to form intrafolial folds within S_2 cleavage domains (Fig. 4.7,B and C). Folds with wavelengths of several metres are isoclinal with axial planes dipping mostly north-west ($050^{\circ}/20^{\circ}-60^{\circ}\text{NW}$) although some folds with north-east dipping axial planes with a considerable spread of orientations occur in the southernmost part of the domain (Fig. 4.6,A and B). The majority of the fold axes plunge subhorizontally towards the north-east and the south-west but steeply plunging axes also occur (Fig. 4.6,A and B). Intrafolial D_2 folds and isoclinal folds with wavelengths of up to 5 m are particularly well-developed within metasedimentary sequences intercalated with the Matchless Amphibolite. D_2 folds with wavelengths of 15-20 m and amplitudes of tens of metres are spectacularly developed and well-exposed in a canyon section of the upper course of the Koam river (Figs. 4.9 and 4.10). These folds are flattened concentric folds (class 1C; Ramsey, 1967) which are tight to isoclinal, inclined, and horizontally to shallowly plunging in attitude (Fig. 4.7,F; Fig. 4.9). Axial planes are orientated $040^{\circ}/40^{\circ}-60^{\circ}\text{NW}$ and fold axes



Fig. 4.9: Map of the Koam canyon section on the farm Annelie 412 showing localities with D₂ downward-facing structures and stereo-net data. Major sedimentary cycles are also indicated.




Fig. 4.10: Map of the Koam canyon section showing sketches of downward-facing structures and related thin section information. Note particularly the direction of sedimentary younging with respect to the S_2 axial planar cleavage, which indicates downward-facing. Abbreviations: Q, quartz; PLAG, plagioclase; BIO, biotite. See Table 4.3 for explanation of symbols. Farm Annelie 412.

plunge at low angles both towards 235° and 050° - 060° (Fig. 4.6,C). Way-up criteria to determine major D_2 fold closures are provided by bedding - cleavage relationships. Detailed mapping of the canyon section has shown that the wavelengths of the major

folds are in the order of 5 km. Overturned limbs, however, are very narrow confirming that mainly right-way up sequences are developed within this part of the Khomas Trough.

Downward-facing D_2 folds have been detected at three localities (Figs. 4.9 and 4.10) of the Koam canyon section (Kukla et al., 1989). It is essential for the recognition of downward-facing that sedimentary structures, providing way-up criteria, are combined with fabric elements. Two lines of evidence were used to define downward-facing: (i) sedimentary younging indicated by graded bedding and (ii) bedding - cleavage relationships with respect to D_2 folds. Figures 4.7,F and 4.11 demonstrate the structural style of part of the canyon section where downward-facing has been detected. The S_1 cleavage has been refolded and strongly transposed into S_2 (Figs. 4.7,A and 4.10) so that F_1 fold closures have been largely obscured. Orientations of S_1 in the canyon section vary consequently with dip directions both to the north-west and the south-east (Fig. 4.9).

F_3 folds are cm- to m-scale tight to isoclinal, asymmetric folds which are developed in narrow shear zones (Fig. 4.7,D and E). They have gently to moderately plunging fold axes ($250^\circ/14^\circ-40^\circ$) and axial planes which dip moderately to steeply towards the north-west ($059^\circ/43^\circ-63^\circ\text{NW}$) and the south-east ($059^\circ/25^\circ\text{SE}$; Fig. 4.6).

Axial planes of cm-scale close-tight crenulation folds (Fig. 4.7,C and E) dip moderately towards both the north-west and the south-east with axes plunging subhorizontally towards the north-east and the south-west (Fig. 4.6,B).

Kink bands of monoclinial kink folds are up to two metres wide and are occasionally brecciated. Axial planes dip both towards the south-east and the north-east (Fig. 4.6,A).




Fig. 4.11: Structural sketch illustrating the style of D_2 folding in the Koam canyon section. S_0 and S_2 form lines are indicated. Note sedimentary younging evidence. Farm Annelie 412.

4.2.3 Domain C


This domain covers a wide area between the Upper Koam river canyon on the farm Annelie up to the central part of the farm Keises (Fig. 4.12). In this domain only D_2 and D_3 structural elements are evident according to the nomenclature of previous domains (Table 4.1). However, one downward-facing D_2 fold has been detected in the centre of this domain which might suggest the presence of an earlier D_1 phase of folding.

(a) Planar fabrics

Bedding is evident throughout the domain and a variety of sedimentary structures have been described (Chapter 3). S_0 strikes uniformly towards the north-east and dips both towards the north-west and the south-east (Fig. 4.12).

The first recognizable fabric element is the S_2 cleavage which is similar in character to that described in domain B. S_2 is a strong, pervasive, narrow to widely spaced and wavy to anastomosing metamorphic banding with quartz-feldspar-rich and mica-rich (biotite and muscovite) cleavage domains (Fig. 4.13, A and B). Fanning of the cleavage and refraction at psammite - pelite contacts are common (Fig. 4.13, C). The S_2 fabric is axial planar to the dominant F_2 folds in this domain and it varies according to the orientation of the folds but generally trends towards the north-east (Fig. 4.12).

Fig. 4.12: Map of the study traverse showing a selection of structural data for domain C from south (A) to north (D). See Table 4.3 for explanation of symbols; key gives number of measurements.



S_3 occurs within the southern part of the domain in narrow shear zones but is more strongly developed towards the north where it is dominant in major high-strain zones. The fabric is penetrative (Fig. 4.13,D) and is characterized by a newly formed biotite generation which encloses the S_2 fabric. In units of low competence such as the graphite schist on the farm Kaan, however, S_3 is rather a strong crenulation cleavage. Orientation data for S_3 indicate a shift from north-easterly trends ($050^\circ/30^\circ-50^\circ\text{NW}$) to north-north-easterly trends ($030^\circ/30^\circ\text{NW}$) towards the north of the domain, demonstrated by the stereoplots in Figure 4.12.

(b) Linear elements

Within shear zones mineral lineations of elongate biotite and garnet are occasionally developed showing a wide spread of orientations (Fig. 4.12,C). A north-east trending S_0/S_2 intersection lineation also occurs. Furthermore the long axes of calc-silicate spindles are elongated parallel to the D_2 fold axes (Fig. 4.12,A and B). An example of the occurrences, sizes and orientations of calc-silicate spindles in an open asymmetric fold on the farm Kaan is shown in Figure 4.14.

Fig. 4.13: Planar fabrics and folds in domain C.

(A) Photograph showing the strong development of the S_2 metamorphic banding cleavage (indicated by arrow) in pelitic lithologies. Note the alignment of staurolite porphyroblasts within the cleavage domains and along bedding S_0 (indicated by arrows). Locality is at the northern boundary of the farm Kaan 309.

(B) Anastomosing S_2 biotite fabric in calc-silicate rich psammitic, northern scapolite schist, farm Keises 312.



(C) Refraction of the S_2 metamorphic banding cleavage at lithological contacts between psammites and calc-silicate layers. Locality in the centre of the farm Keises 312.

(D) S_2 metamorphic banding cleavage superimposed by intense S_3 spaced fabric in high-strain zone of the southern scapolite schist on the farm Dagbreek 365.

(E) Open asymmetric SE verging F_2 fold in mainly psammitic lithologies on the southern, shallow-dipping limb of the Tsawisis syncline (see Fig. 4.2). S_0 is demarcated by dashed line. Hammer for scale. Domain C, farm Tsawisis 308.

(F) Open F_2 fold in psammitic schist on the southern margin of domain C. North is towards the left of the photograph, the height of the scale is 1.7 m. Farm Kaan Dam 411.

(G) Metre-scale isoclinal F_3 folds with axial planar S_3 penetrative fabric in shear zone at the southern scapolite schist on the farm Dagbreek 365.






Fig. 4.14: Diagram showing sketch, photograph and stereoplot of an open asymmetric D_2 fold in the area between the graphite schist and the southern scapolite schist (Fig. 4.2). The orientation and shape of calc-silicate layers and spindles respective to S_0 and S_2 is strongly dependent on their positions within the fold. Shear processes parallel to S_0 are also indicated. See Table 4.3 for explanation of symbols. Farm Kaan 309.

(c) Minor folds

F_2 folds are open to tight in the northern part of the domain and on the steep limbs of some major fold structures. In contrast a pronounced open asymmetric fold style occurs in the centre and south. Figures 4.13 (E and F), 4.14 and 4.15 illustrate examples of open asymmetric folds on the upright limb of a major fold structure on the farm Kaan. In contrast, Figure 4.16 shows tight folding associated with the steep limb of the major syncline on the farm Tsawisis. Axial planes become steeper towards the north as limbs tighten (Fig. 4.12, A-C). Fold axes plunge at low angles both towards the north-east and south-west ($050^\circ/10^\circ$ and $230^\circ/10^\circ$), but within zones of high strain axes plunge up to 20° towards 050° . Wavelengths of asymmetric folds are in the order of 20-50 m in the shallow limbs and of 5-10 m in the steep limbs of larger structures (Figs. 4.15 and 4.16). There is evidence for a D_2 downward-facing fold towards the top of the scapolite schist sequence on the farm Dagbreek. This is based on the relationship of graded bedding which provides way-up criteria and the attitude of the S_2 cleavage (Fig. 4.17, E). The presence of this fold indicates that folding and overturning of fold limbs has occurred prior to D_2 . This may therefore be seen as evidence for a D_1 phase of deformation in this part of the Khomas Trough.

(c) Minor folds

F_2 folds are open to tight in the northern part of the domain and on the steep limbs of some major fold structures. In contrast a pronounced open asymmetric fold style occurs in the centre and south. Figures 4.13 (E and F), 4.14 and 4.15 illustrate examples of open asymmetric folds on the upright limb of a major fold structure on the farm Kaan. In contrast, Figure 4.16 shows tight folding associated with the steep limb of the major syncline on the farm Tsawisis. Axial planes become steeper towards the north as limbs tighten (Fig. 4.12, A-C). Fold axes plunge at low angles both towards the north-east and south-west ($050^\circ/10^\circ$ and $230^\circ/10^\circ$), but within zones of high strain axes plunge up to 20° towards 050° . Wavelengths of asymmetric folds are in the order of 20-50 m in the shallow limbs and of 5-10 m in the steep limbs of larger structures (Figs. 4.15 and 4.16). There is evidence for a D_2 downward-facing fold towards the top of the scapolite schist sequence on the farm Dagbreek. This is based on the relationship of graded bedding which provides way-up criteria and the attitude of the S_2 cleavage (Fig. 4.17, E). The presence of this fold indicates that folding and overturning of fold limbs has occurred prior to D_2 . This may therefore be seen as evidence for a D_1 phase of deformation in this part of the Khomas Trough.




Fig. 4.15: Diagram showing sketch, photograph and stereoplot of an open asymmetric D_2 fold in the area between the graphite schist and the southern scapolite schist (Fig. 4.2). Younging evidence is based on sedimentary structures. Bedding is demarcated by dashed line. Height of scale (circled) is 1.7 m. Farm Kaan 309.

F_3 folds are developed on a centimetre- to metre-scale in narrow high strain zones (Fig. 4.13,G). In these zones F_3 tight to isoclinal folds largely overprint earlier structures. Typical features of D_3 folding and overprinting relationships of D_3 on D_2 are well developed in the southern scapolite schist (Fig. 4.12) and are illustrated in Figure 4.17. The orientations of fold axes and axial planes change from south to north within this domain.




Fig. 4.16: Diagram showing sketch, photograph and stereoplot of tight to isoclinal SE verging D_2 folds on the northern, upright to overturned limb of the Tsawisis syncline (Fig. 4.2). In order to compare sketch and photograph reference may be made to the thrust indicated. Note also sedimentary younging evidence. See Table 4.3 for explanation of symbols. Height of scale (circled) is 1.8 m. Farm Tsawisis 308.

Axial planes of F_3 folds change from $060^\circ/50^\circ\text{NW}$ in the south to $020^\circ/30^\circ\text{NW}$ at the scapolite schists and fold axes change from $060^\circ/10^\circ$ in the south to $036^\circ/10^\circ-20^\circ$ in the north (Fig. 4.12).

Fig. 4.17: Structural sketches showing D_2 and D_3 features of the southern scapolite schist on the farm Dagbreek 365 (see Fig. 4.2).


(A) Tight F_2 syncline partly refolded by D_3 . Note superimposition of S_2 by S_3 .

(B) Intrafolial minor F_2 folds situated on the overturned limb of a larger D_3 syncline.

(C) Refolded quartz-vein showing the development of minor F_2 and F_3 folds.

(D) Penetrative S_3 cleavage and post- D_3 shear underlined by quartz segregation.

(E) Downward-facing D_2 fold confirmed by sedimentary younging evidence and overprinting relationships of D_3 on D_2 . The development of this fold suggests the presence of a D_1 deformation prior to D_2 in this part of the study traverse. See Table 4.3 for explanation of symbols.



(d) Major folds

Major F_2 folds have been detected in this domain and they are indicated by the bedding - cleavage relationships on minor structures. Characteristically the major folds are open asymmetric with shallowly to moderately dipping southern limbs and steep northern limbs. The major fold structures as shown in Figure 4.2 are: (1) the Tsawisis syncline in the south; (2) a zone of open, asymmetric folding on the upright limb of a major synclinal structure in the centre; (3) the Dagbreek anticline between the two scapolite schist sequences; and (4) a zone of isoclinal folding in the northern part of the domain. The fold hinges of the major structures are situated in the most psammitic part of the respective areas. It can be seen in Figure 4.2, however, that parts of the limbs of the major folds are missing due to the presence of structural discontinuities which will be described below.

4.2.4 Domain D

This domain extends from the centre of the farm Keises to the southern margin of the Donkerhoek Granite (Fig. 4.18). The establishment of this domain is based on the recognition of an S_4 crenulation cleavage and a clockwise rotation of fabric elements. Additionally, axial planes of deformation phases D_2 to D_4 are steeply inclined to upright and fold axes plunge moderately in the north of the domain. The northern margin of the Khomas Trough is defined by the Donkerhoek Granite in this area.




Fig. 4.18: Map of the study traverse showing a selection of structural data for the south (A) and the north (B) of domain D. See Table 4.3 for explanation of symbols; key gives number of measurements.

(a) Planar fabrics

As in domain C original bedding is confirmed by a variety of sedimentary structures. S_2 is a widely spaced biotite foliation with sillimanite (fibrolite) knots orientated parallel to and situated within the mica-rich cleavage domains. The fabric changes orientation from westerly trends in the south ($086^\circ/10^\circ-90^\circ\text{NW}$) to east-south-easterly trends in the north ($102^\circ/50^\circ-90^\circ\text{NE}$). The S_2 fabric is folded by D_3 within narrow shear zones in a manner similar to that described in domain C (Fig. 4.19, A and B). S_3 is a spaced cleavage which is axial planar to F_3 folds. This biotite fabric is developed throughout the domain but especially in high-strain zones as in domain C. Orientations are similar to S_2 and also trend east-south-easterly in the north. Sillimanite knots which usually parallel S_2 have been bent (transposed) partly into S_3 orientations. Within highly pelitic lithologies a symmetric crenulation cleavage is developed which is here designated S_4 (Fig. 4.19, C).

Generally data plots of fabric elements indicate a more uniform coaxial distribution in the south of the domain but a wide spread of orientations for respective fabric elements occurs in the north (Fig. 4.18).

(b) Linear elements

There are only occasional S_0/S_2 intersection lineations preserved which plunge $280^\circ/10^\circ-40^\circ$ in the north of the domain (Fig. 4.18).

Fig. 4.19: Planar fabrics and folds in domain D.

(A) S_2 metamorphic banding cleavage folded in narrow shear zone in pelitic lithologies by D_3 which developed tight F_3 folds and an axial planar S_3 cleavage; northern farm Keises 312.


(B) Superimposition of S_2 by S_3 in pelitic schist on the farm Keises 312.

(C) Symmetrical, steeply dipping S_4 crenulation cleavage developed in pelitic lithologies in the north of domain D, farm Keises 312.

(D) Downward-facing D_3 synformal anticline in pelites, confirmed by sedimentary younging evidence; bedding is demarcated by dashed line. Hammer for scale. Farm Nomatsaus 28.

(E) Minor F_3 fold in psammitic lithologies, demarcated by the calc-silicate layer within the folded S_2 cleavage. Farm Keises 312.

(F) NE-dipping F_3 fold with steeply plunging fold axis (demarcated by arrow) in pelitic schist. Pen is 14 cm long. Northern domain D, farm Nomatsaus 28.



(c) Folds

The vergence of minor fold structures together with bedding - cleavage information indicates that the domain is situated on the overturned limb of a major D_2 anticlinal closure located to the north (Fig. 4.2). Observed D_2 folds are open to tight to isoclinal in the south and strongly isoclinal in the north with wavelengths decreasing from 10-20 m to 5 m respectively. Axial planes of these flattened concentric F_2 folds (class 1C; Ramsay, 1967) change clockwise from $074^\circ/40^\circ-50^\circ\text{NW}$ in the south to $106^\circ/65^\circ\text{NE}$ in the north; fold axes change from $080^\circ/10^\circ$ to $106^\circ/30^\circ-40^\circ$ respectively (Fig. 4.18). The more steeply plunging attitude of D_2 fold axes in the north of this traverse stands out against the usually horizontal to subhorizontal orientations elsewhere along the traverse.

Tight F_3 folds with wavelengths of up to 5 m have developed in shear zones (Fig. 4.19, D, E and F) and orientations also rotate clockwise (Fig. 4.18). Similar to F_2 fold axes also F_3 fold axes plunge more steeply in this domain (Figs. 4.18 and 4.19, F). Furthermore downward-facing F_3 folds have been detected and one of these structures is shown in Figure 4.19, D.

Small-scale (tens of centimetres) F_4 folds are related to the S_4 crenulation cleavage and occur towards the northern margin at the contact with the Donkerhoek Granite.

A structural section from the southern part of this domain is presented in Figure 4.20 showing fabric elements, fold styles, and overprinting relationships of deformation phases D_2 , D_3 and D_4 .




Fig. 4.20: Structural profile illustrating tight to isoclinal, moderately to steeply dipping D_2 folds with axial planar S_2 fabric. Superimposed are the S_3 and S_4 fabrics in this low-strain zone in the southern part of domain D. See Table 4.3 for explanation of symbols. Farm Keises 312.

4.2.5 Late fractures

Late-stage joints and faults are considered here together since their characteristics are similar in all domains. A minor feature occurring in domain A are post- D_4 joint sets with subvertical north-easterly strikes. The two major fault sets occurring in the Khomas Trough appear prominently on the Landsat image of the Khomas Trough (Fig. 2.4). One set is orientated subvertically and trends north-south and the second set is also orientated subvertically and trends north-west - south-east. A north-south trending fault is recognizable all along the course of the Kaan river and displaces the graphite schist on the farms Kaan and Tsawisis in the order of several hundreds of metres. This is accompanied by brecciation, silicification, quartz mobilisation and iron-staining. The north-west striking fault set formed the Koam canyon but only minimal displacement is envisaged since structural elements and lithologies can be traced across it. Senses of movement are largely dextral in both sets. The time of formation of both fault sets was after the intrusion of the Donkerhoek Granite which has been partly displaced.

4.3 Contact relationships of metasediments and migmatites with the Donkerhoek Granite

The northern margin of the Khomas Trough in the study area is defined by the contact with the Donkerhoek Granite. Structural relationships between this granite and the metasediments with

regard to the time of granitic emplacement have been discussed by many authors (e.g. Rønning, 1923; Gevers, 1963; Martin, 1965; Smith, 1965; Hälbich, 1970; Jacob, 1974; Faupel, 1974; Nieberding, 1976). In overview these studies have concluded that the granite intruded after deformation into the Kuiseb metasediments where it caused the formation of migmatites (Fig. 4.21, A and B). With respect to these suggestions this study contributes the following findings from investigations on the structural relationships between migmatites, metasediments, and granitic phases.

Generally, migmatites occur around the Donkerhoek Granite in well-defined zones covering several km². The western boundary of one of these zones is shown in Figure 4.18 on the farm Davetsaub where investigations have been undertaken. This figure illustrates that no migmatites are developed in the Kaan river section.

The following features are important with respect to the northern margin of the study area: (1) metasediments are coarsely recrystallized only several hundreds of metres to the south of the granite contact in the Kaan river section; (2) deformational features in the metasediments include a strong S₄ crenulation cleavage, F₂ and F₃ folds with plunging fold axes and steeply inclined axial surfaces as well as downward-facing F₃ folds; (3) the migmatitic areas contain xenoliths of metasediments and

Fig. 4.21: Contact relationships between metasediments, migmatites and granitic phases at the northern margin of the Khomas Trough.

(A) Kuiseb schist migmatites showing palaeosome and neosome, ptygmatic folding, and granitic apophyses. Lens cap for scale is circled. Davetsaub river, farm Nomatsaus 28.


(B) D_2 synform in Kuiseb schist migmatites. Note boudinage in the centre of the photograph. Davetsaub river, farm Davetsaub 29.

(C) Xenolith of Kuiseb Formation pelitic schist in granite comprising S_2 and S_3 cleavages (indicated by arrows) and ptygmatic folds. Farm Davetsaub 29.

(D) Photograph showing pegmatite veins of the Donkerhoek Granite folded by D_4 . The S_4 crenulation cleavage is demarcated. Pocket knife for scale is circled. Kaan river, farm Keises 312.

(E) Photograph showing granitic apophysis in pelitic schist folded by D_4 . The orientation of the S_4 crenulation cleavage is indicated by arrow. Davetsaub river, farm Davetsaub 29.

(F) Photograph showing sharp contact between cross-cutting pegmatite (lower part of the photograph) and Kuiseb schist migmatites (upper part of the photograph). Davetsaub river, farm Davetsaub 29.



calc-silicates (Fig. 4.21,B); (4) xenoliths of coarse grained metasediment within the white two-mica granite contain the S_2 , S_3 and S_4 cleavages, as well as ptygmatic folds (Fig. 4.21,C); (5) thin pegmatite veins and granite apophyses are folded by the S_4 crenulation cleavage (Fig. 4.21,D and E); and (6) migmatitic areas are clearly cut with sharp contacts by pegmatite phases of the granite (Fig. 4.21,F).

In conclusion, field observations along the northern boundary of the Khomas Trough show that the main granite intrusion has occurred after the main deformation events which affected the Khomas Trough. Coarser grain sizes of Kuisab metasediments in a small zone bounding the granite indicate a certain thermal influence of the pluton. In some areas, however, migmatites extend up to several kilometres south of the granite contact. Structural relationships which show pegmatites cross-cutting the migmatites with sharp contacts confirm that migmatites have formed before the emplacement of the Donkerhoek Granite. These findings are interpreted to speak in favour of an "in situ" migmatization by the regional metamorphism which preceded the intrusion. This is preferred to models of the above authors which explain the migmatization by melting and injection during the intrusion of the Donkerhoek Granite.

4.4 The recognition of heterogeneous strain and thrusting

4.4.1 Heterogeneous strain

The distribution of strain throughout the traverse is distinctly heterogeneous in the sense of Ramsay (1967). Multilayered sequences are especially receptive to strain variations in lithologies with different physical properties. Heterogeneity develops on all scales. On a small scale, it is expressed in the differential development of fabrics in more competent quartz-rich (low-strain) and more incompetent mica-rich (high-strain) lithologies. On a large scale strain variations may be expressed in particular high-strain zones which alternate with discrete zones of low strain. Such a pattern has been observed in the study area. Figure 4.22 illustrates the above described major fold structures in the Khomas Trough developed during the D_2 phase of deformation. Major structural discontinuities subdivide the Khomas Trough and discrete changes of fold styles occur across the discontinuities as indicated in this figure. The features which define the discontinuities are the ultimate expression of heterogeneous deformation within the Khomas Trough.

4.4.2 Major high-strain zones

Characteristics of the most important of the discontinuities outlined in Figure 4.22 are described in the following from south to north.




Fig. 4.22: Structural profile across the Khomas Trough showing the organization of the sequence into individual thrust slices after the D_2 phase of deformation. Note the structural steepening towards the north and the pronounced changes in fold style across the individual thrusts.

a) Southernmost Khomas Trough

Thrust faulting is clearly evident at the contact of the Klein Kuppe quartzites and schists and the Kuiseb Formation schists just north of the confluence between the Koam and Kuiseb rivers (Fig. 4.3). At this locality a large number of north-east trending thrust faults dip at shallow to steep angles towards the

Fig. 4.23: High-strain zones in the southern Khomas Trough.


(A) Small-scale, south-east verging thrust fault within Kleine Kuppe Formation pelites and quartzites, about 500 m north of the confluence of the Koam and Kuiseb rivers on the farm Usambara 304.

(B) South-east verging thrust faults in Kuiseb Formation pelites, several hundreds of metres north of the confluence of the Koam and Kuiseb rivers on the farm Usambara 304. Hammer for scale is circled.

(C) Photograph showing shear zone near thrust fault indicated by sigmoidally shaped quartz segregations within $S_{0,1,2,3}$ composite cleavage in chlorite schist. Farm Usambara 304.

(D) Small-scale shear zone comprising sigmoidally shaped S_2 fabric and intrafolial D_2 folds. Pocket knife is 8.5 cm long. Farm Okasume 304.

north-west. The faults cut-out lithological units and produce typical wedge-shaped outcrop patterns. They are characterized by silicified and brecciated zones and the presence of iron staining.



When enclosed by two fault planes, small-scale duplex-type structures indicate a south-easterly verging shear sense (Fig. 4.23, A and B). The occurrence of drag folds on the upper sheet of faults also confirm the contractional style of the faulting. Associated with the faults are small-scale shear zones (comprising the composite cleavage which is sigmoidally shaped) and some deformed quartz segregations (Fig. 4.23, C and D). These quartz segregations act as small-scale strain markers and confirm the reverse attitude of the observed thrust faults.

b) Matchless Amphibolite

Heterogeneous strain is particularly developed within the Matchless Amphibolite which is situated in thick pelitic sequences. The heterogeneity is initially expressed by the alternation of low-strain zones and high-strain zones on a metre-scale. This is best illustrated by the shape of pillow structures which range between original spheroidal shapes and extremely elongated structures. The main fabric element is the S_2 cleavage which is axial planar to isoclinal F_2 folds. Fold axes of these folds plunge more steeply (up to 25°) towards the north-east if compared with sequences north and south of the Matchless Amphibolite (Figs. 4.6 and 4.24). Elongated biotites and hornblendes form a pronounced north-west plunging lineation. This lineation is strongest developed within the Matchless Amphibolite if compared to elsewhere along the traverse. Long axes of pillow structures are also plunging to the north-west. S_3 is a penetrative biotite fab-

ric which overprints S_2 in intercalated biotite schists and the S_4 crenulation cleavage occurs exceptionally strong within this sequence (Fig. 4.24).

Stratigraphic relationships within the Matchless Amphibolite are strongly connected with the development of reverse faults. These have been observed throughout the sequence but they are much more pronounced at the base (Fig. 4.25,A). The main thrusting event has occurred pre- D_3 which is evident from the shearing of the S_2 fabric and the unaffected S_3 cleavage (Fig. 4.25,C).




Fig. 4.24: Stereonet showing structural data from metasediments and amphibolites within the Matchless Amphibolite. See Table 4.3 for explanation of symbols; key gives number of measurements.

Post- D_3 thrusting, however, has also been observed. Orientations of thrust planes are largely parallel to F_2 axial surfaces at 040° - $055^{\circ}/35^{\circ}$ - 50° NW. Some thrusts are associated with breccia

Fig. 4.25: Shearing and thrusting at the Matchless Amphibolite.


(A) Major thrust fault (décollement) situated in 10 m thick graphite schist at the base of the Matchless Amphibolite. Thrusting is accompanied by brecciation and silicification. For detailed profile see Figure 5.5. Amsas river, Farm Kobos 305.

(B) Shear zone of D_2 age in pelitic schist associated with the graphite schist thrust zone shown in Figure 4.25, A. Photograph shows sigmoidally shaped S_2 metamorphic banding cleavage in which S_1 is strongly transposed (indicated by arrows). Amsas river, farm Kobos 305.

(C) South-east verging thrust zone of post- D_2 age developed in type I amphibolites of the Matchless Amphibolite. Waterfall profile (see profile A in Figure 5.1), farm Annelie 412.

(D) Shear zone in metagabbro of the Matchless Amphibolite. Koam river, farm Kobos 305.

bands, silicification and iron staining (Fig. 4.25,A). Thrust faults are generally associated with shear zones in which the S_2 fabric shows a sigmoidal pattern (Fig. 4.25,B). Metagabbros in the vicinity of thrusts are also strongly sheared (Fig. 4.25,D). More information on the stratigraphic implications due to thrusting within the Matchless Amphibolite will be given in Chapter 5. Important to note at this stage, however, is the occurrence of a 15 m thick graphite schist and an overlying, 2 m thick marble unit at the top of the Matchless Amphibolite (Fig. 4.22).



c) Koam canyon section

Geological features are well exposed in this north-west trending, 6 km long canyon on the farm Annelie (Fig. 4.9). Three phases of deformation (D_1 , D_2 and D_3) are recognized in this area. Strain is also heterogeneous, shown by superimposed folding and thrusting. The structural fabrics and folds have been described above (section 4.2, domain B) and structural data are summarized in Figure 4.9. The earliest phase of thrusting is evident in the southern canyon where the cross-cutting S_2 fabric post-dates a thrust fault (Fig. 4.26).



Fig. 4.26: South-east verging pre- D_2 thrust fault in psammitic and pelitic schist in the southern Koam canyon. This thrust zone is clearly cross-cut by the S_2 metamorphic banding cleavage which suggests D_1 thrusting in this area. Brecciation and silicification occurs. Farm Bergkrans 370.

A major phase of thrusting occurred after the formation of F_2 folds and the S_2 cleavage. This is shown by the development of shear zones which show sigmoidally curved S_2 fabric elements and by sheared-out D_2 synclines and anticlines. Figure 4.11 illustrates the shearing-out of major limbs of tight to isoclinal F_2 folds. A pronounced L_2 biotite lineation plunging moderately towards the north-west on S_2 foliation surfaces occurs in the vicinity of the high-strain zones in the sequence. Within these zones D_2 downward-facing structures have been observed which are unique in this part of the overall study traverse (Figs. 4.9, 4.10, 4.11). The downward-facing structures have been interpreted by Kukla et al. (1989) to have originated from early D_1 folding and thrusting which created overturned limbs. This was followed by D_2 folding and rejuvenated thrusting to develop the downward-facing structures (Fig. 4.27). Centimetre- to metre-scale F_3 folds are confined to the narrow shear zones which developed in the less competent lithologies (Fig. 4.7,D). A major structural discontinuity is indicated towards the northern end of the canyon section (Fig. 4.22). This is shown by a change from open asymmetric folds on the north side of the discontinuity to folds on the south side in which the bedding/cleavage relationships confirm the presence of antiforms in which overturned limbs have been eliminated. These antiforms pass southward into tight to isoclinal overturned folds (Fig. 4.11).




Fig. 4.27: Schematic diagram of the model for the development of downward-facing structures along the Koam canyon section. (A) Early (D₁) folding and thrusting, creating overturned limbs. (B) D₂ folding, rejuvenated thrusting and subsequent development of downward-facing structures. Note that folds produced in the overturned sequence are downward-facing. (From Kukla et al., 1989).

d) Graphite schist

The area of the thick graphite schist on the farm Kaan in the centre of the Khomas Trough (Fig. 4.22) is a further high-strain zone. A one metre thick tremolite schist occurs at the base of

the approximately 60 metres thick graphite schist. The tremolite schist has been interpreted previously to have formed from a dolomitic precursor during metamorphism (see Chapter 3.5.7). A thrust fault with an orientation of $075^{\circ}/40^{\circ}\text{NW}$ has been observed at the base of the sequence shown by the shearing-out of an F_2 synclinal fold (Fig. 4.28, A and B). This zone is characterized by shearing although observations are more limited due to the uniform lithology of the graphite schist. In thin section, however, strongly elongated quartz may be seen within a highly sheared S_2 foliation matrix (Fig. 4.28, C). A further feature is the isoclinal character of the F_2 folds which is unusual compared with the open folds north and south of this zone (Figs. 4.12; 4.13, E and F; 4.28, C). Additionally F_2 fold axes in this zone plunge at steeper angles (20°) towards the north-east. In contrast to these D_2 features, F_3 fold axes maintain their horizontal to subhorizontal attitude throughout domain C. The latter, together with the cross-cutting S_3 cleavage (which is a strong crenulation cleavage in the graphite schist) indicates that the thrusting event occurred pre- D_3 .

An inferred thrust zone is situated between the graphite schist and the southern scapolite schist in domain C (Fig. 4.22). Since features of this zone are similar to the scapolite schists further northwards these are described together in the following.




Fig. 4.28: Diagram showing photograph, sketch and stereonet of geological features at the graphite schist in the centre of the Khomas Trough. Kaan river, farm Kaan 309. (A) Photograph showing pre-D₃ thrust fault and sheared-out synform at the base of the graphite schist. Thrust zone is brecciated and iron-stained. (B) Stereonet data for the graphite schist sequence. See Table 4.3 for explanation of symbols. (C) Tracing from thin section showing elongated and sheared quartz in highly sheared graphitic matrix.


e) Scapolite schists

The two scapolite schist sequences occur in the northern part of domain C and they will be considered together, because characteristics are similar (Fig. 4.22). Each of these zones is several hundreds of metres wide and they contain overwhelmingly pelitic lithologies. D_2 and D_3 structural elements comprising cleavages and folds have been encountered. F_2 folds and the S_2 cleavage have, however, been strongly refolded and overprinted by D_3 within prominent shear zones where s-c band shearing occurs (Fig. 4.29,A). The usually competent calc-silicate spindles and layers are extremely folded and sheared into adjacent lithologies. The shearing and associated thrusting has led to D_2 downward-facing structures at the top of the sequence (Fig. 4.17,E) and to plunging F_2 fold axes (Fig. 4.29,B). Generally the S_3 spaced cleavage is most strongly developed within this zone (Fig. 4.13,D) where it cross-cuts dislocation zones which contain refolded and sheared D_2 structures. This indicates that the main thrusting event has also occurred pre- D_3 . In parts of the sequence plunging D_3 fold axes have been observed and this suggests, that syn- to post- D_3 faulting has also occurred if the missing evidence for a strong D_4 fold phase in this area is considered. Some strike-parallel fault surfaces have been observed along which massive scapolitization, brecciation and occasionally iron-sulphide mineralization occurs (Fig. 4.29,C). Some of the observed features, especially the alternation of high- and low-strain zones and the refolding of F_2 folds by D_3 , may be seen in Figure 4.30 which is a structural



Fig. 4.29: Shearing and thrusting at the southern scapolite schist sequence, farm Dagbreek 365. (A) Strong s-c band shearing of S_2 by D_3 . S_2 metamorphic banding cleavage and orientation of S_3 cleavage parallel to D_3 shear zones are indicated by arrows. (B) Structural data for the scapolite schist sequence. See Table 4.3 for explanation of symbols; key gives number of measurements. (C) Brecciated and silicified bedding-parallel fault being part of a D_2 thrust zone. Western flank of "Kuduspitze" mountain, farm Dagbreek 365.

profile across the northern scapolite schist on the farm Keises (Figs. 4.18 and 4.22). The abrupt changes from areas with preponderant D_2 folding to areas with strong D_3 folding are especially noteworthy.






Fig. 4.30: Structural profile across the northern scapolite schist sequence on the farm Keises 312. Diagram illustrates overprinting relationships of D_3 on D_2 in association with thrust faults. Structural data along the profile are given in stereonet. See Table 4.3 for explanation of symbols.

A further important feature towards the interpretation of these scapolite zones are the abrupt changes of fold styles on a large scale on the respective northern and southern sides of the discontinuities. This is conspicuous in the landscape and it is illustrated in Figure 4.22 which shows that subhorizontal limbs of open asymmetric folds occur on the southern sides but steep to overturned limbs of isoclinal folds occur in the north.

f) Northern Khomas Trough

The central and northern parts of domain D, designated the Okahandja Lineament Zone (Miller, 1983b) in Figure 4.22, are characterized by mostly pelitic sequences. The S_2 fabric and D_2 folds have been refolded within shear zones which has led to the formation of D_3 downward-facing folds (Fig. 4.19,D). Parallel-sided shear zones with development of F_3 folds and a strong S_3 cleavage are illustrated in Figure 4.31. A structural cross-section shown earlier (Fig. 4.20) demonstrates the shearing-out of overturned F_2 limbs by thrusting in the central part of the farm Keises. The Schmidt net in Figure 4.31,B indicates an unusually wide spread of poles to cleavages as well as the steeply inclined attitude of the axial planes in this area. A post- D_4 feature in this area is the clockwise rotation of structural elements (Fig. 4.18).




Fig. 4.31: (A) Photograph of parallel-sided D_3 shear zone containing F_3 folds and a pervasive S_3 spaced cleavage. S_0 and S_2 are intensely folded. Note parallelism of S_0 , S_2 and S_3 on either side of the shear zone. Northern margin of the farm Keises 312. (B) Stereonet showing structural data for the northern part of domain D (see Fig. 4.18). Note wide spread of data, clockwise rotation of structural elements compared with domains A-C, and plunging fold axes. See Table 4.3 for explanation of symbols; key gives number of measurements.

4.4.3 Summary and conclusions

Most of the above described individual high-strain zones throughout the study traverse share features which are the ultimate expression of heterogeneous deformation in the Khomas Trough. The following characteristics are common to most of the discontinuities described.

(1) The discontinuities are zones which are several hundreds of metres wide and they are situated particularly in the thickest pelitic successions of the Khomas Trough. Thrust faulting has been directly observed mainly through the displacement of fold limbs which have been sheared-out at the southern margin of the traverse, the Matchless Amphibolite, the Koam canyon section, the graphite schist on the farm Kaan, and the scapolite schists. Pronounced mineral lineations down-dip on axial planes are associated with the south-easterly directed thrusting. Small-scale strain markers such as sheared pre-thrusting fabrics, quartz-layers and calc-silicate spindles confirm the reverse attitude of the observed discontinuities. Earliest thrusting has occurred during the D_1 phase of deformation but major thrusting was associated with the D_2 and D_3 phases of deformation which is evident in all high-strain zones described. Late shearing and thrusting post-dating D_3 is indicated in the Matchless Amphibolite sections and the scapolite schists. The above features confirm the contemporaneity of folding, cleavage formation and thrusting.

(2) The discontinuities are zones of concentrated shear. On a small scale ductile shearing is indicated in thin section and in outcrop by cm- to m-wide zones where pre-shear foliations are deflected and sigmoidally shaped. In some cases layer-parallel s-c band shearing is developed also indicating the heterogeneity of strain during fold development. Apart from enhanced retrograde reactions there is very little evidence for changes in meta-

morphic conditions within the shear zones since the peak of metamorphism outlasted the major deformation phases (Chapter 6). Strain determinations, shear zone geometries and compressional directions are difficult to evaluate since shear zones are largely parallel-sided within the overall north-east trending tectonic grain of the orogen. The intense refolding of the S_2 metamorphic banding cleavage and the largely unaffected S_3 cleavage confirm the pre- D_3 age of major shearing within the high-strain zones.

(3) With respect to the main fold phase D_2 , discrete and rather abrupt changes of fold styles occur across the discontinuities, separating isoclinally from openly folded zones. This may be seen in the centre and the north of the traverse where shallow and steep dipping bedding surfaces on the respective northern and southern sides of the discontinuities exhibit a distinct ramp and flat geometry.

(4) Within the high-strain zones there is a remarkable development of structures associated with the D_3 phase of deformation. The S_3 fabric and tight to isoclinal F_3 folds, only scarcely developed in low strain zones and restricted to metre-scale shear zones, dominate within these high-strain zones. Original sedimentary features are largely obliterated and D_2 fold structures and fabric elements are strongly overprinted to become uneven in geometry and intensity. The above is in strong contrast to adjacent low-strain zones where sedimentary structures are

remarkably well preserved and F_2 folds with the associated penetrative S_2 axial planar foliation form the main structural elements. Orientations of planar and linear structural elements vary considerably within the high-strain zones which is especially evident from the plunging attitude of F_2 fold axes. This is unusual if compared to the commonly horizontal to subhorizontal plunges of fold axes in low-strain zones of the Khomas Trough.

(5) Downward-facing D_2 and D_3 structures along the study traverse are exclusively confined to the observed high-strain zones, i.e. the Koam canyon section, the hangingwall of the southern scapolite schist, and the northern margin of the Khomas Trough.

(6) In the case of the two scapolite schists the scapolitization of the originally plagioclase-bearing wallrock occurred post- D_3 . The massive enrichment along fractures as well as the chlorine-rich compositions of the scapolites (Chapter 6.4) indirectly point to the presence of tectonic weakness zones which hosted fluid movement.

(7) There are similar lithologies indicated in two of the high-strain zones. These are the marble and graphite schist association on top of the Matchless Amphibolite (Fig. 4.22) and the tremolite schist - graphite schist association in the centre of the traverse (Fig. 4.22). Also striking lithological similarities characterize the two scapolite schists which comprise calc-

silicate rich and pelitic sequences. These are suggestive of geological repetition of units which could ideally have been used as décollement planes within the sequence.

In conclusion these zones are interpreted as major shear and thrust zones, situated in pelitic sequences. The individual thrust slices may be traced over more than 150 km along strike (Fig. 2.4) and they define together with the northwards steepening attitude of structures an overall imbricate fan geometry in the Khomas Trough (Fig. 4.22). With respect to this structural setting and the similar lithologies occurring in some of the thrust zones it may be speculated that the individual thrusts are all related to a major décollement surface at depth.

4.5 Kinematic interpretation and time sequence of deformational events

The correlation of structural elements along the traverse uses the S_2 foliation as a time datum because this fabric is a recognizable metamorphic banding cleavage and is axial planar to F_2 folds of varying style. The following kinematic interpretation is structured according to the proposed time sequence of events as evident from several successive stages of cleavage and fold formation. This does, however, not necessarily imply discrete and independent phases of deformation through time.

Lithological contacts are interpreted to represent original bedding, which is in any case evident from original sedimentary structures preserved through large parts of the traverse. Structural elements encountered and their correlation along the study traverse are represented in Table 4.1.

4.5.1 D_1 phase of deformation

The first phase of deformation is mostly evident in the southern part of the Rhomas Trough. D_1 is represented by a north-easterly trending metamorphic banding cleavage which is defined by an early biotite generation of metamorphic origin. S_1 has been intensely overprinted and transposed during subsequent deformation phases. This process would account for the lack of recognition of F_1 folds which even in domain B are of a regional scale. In other medium-grade metamorphic terrains, transposition and obscuring of D_1 fold closures by later phases of deformation has been widely documented (Turner and Weiss, 1963; Hobbs et al., 1976). Lines of evidence suggesting the development of F_1 fold closures are the northerly and southerly inclined attitude of S_1 and the presence of D_2 downward-facing structures in domain B and the southern scapolite schist in domain C. The latter have formed through the refolding of overturned F_1 limbs during D_2 . This together with silicified and brecciated zones which are cross-cut by S_2 demonstrate that thrusting had already initiated during D_1 and that these thrusts were inherited by later deformation phases. Cleavage data confirm that S_1 formed within the overall coaxially

consistent stress regime of the Khomas Trough. The structural style and the character of the cleavage indicate that it formed under an overall compressive regime.

4.5.2 D_2 phase of deformation

The second phase of deformation has been labelled D_2 on the basis of the S_2 fabric which is always a strong, penetrative metamorphic banding cleavage with quartz-feldspar- and mica-rich domains and which is axial planar to second generation folds throughout the area. S_2 trends north-east and dips north-west with the exception of high-strain shear zones, where orientations vary. Calc-silicate spindles are preferentially orientated parallel or subparallel to this fabric. Wide spacing of the cleavage in psammites and narrow spacing in pelites indicates a lithological control of the cleavage formation.

The style of D_2 folds varies throughout the Khomas Trough from intrafolial to isoclinal in the south through open in the centre and to isoclinal in the north. The major fold structures which are indicated in Figure 4.22 are thrust-bound. Rather abrupt changes of fold styles occur across the thrust zones. The consistent south-easterly vergence, the subhorizontal fold axes and the corresponding axial planar cleavage indicate that the folds have formed within a compressive regime. The formation of open asymmetric folds in the low-strain zones in the centre might be attributed to: (1) an oblique angle between layering and the max-

imum shortening direction; (2) south-east directed shear, and (3) south-east directed translation during fold development. The first possibility is ruled out since there is no evidence for noncoaxial folding in this area. Shear deformation within the low-strain zones is only evident on a minor scale. It is therefore more conceivable that these particular folds have developed during south-eastward directed translation with possibly additional shear components participating in this process. The extreme coaxiality of structures confirms the constancy of the principal axis of shortening throughout the deformational history of the Khomas Trough. The existence of intrafolial D_2 folds in domain B occurring in association with isoclinal D_2 folds confirms that considerable layer-parallel extension has occurred after layer-parallel shortening. Distinct mineral elongations of mainly biotite and amphiboles occur in domains A and B. Since the direction of maximum extension will be close to perpendicular to the fold axis, the lineations most likely represent extensional down-dip lineations within S_2 planes. The remarkable development of these lineations at the southern margin of the Khomas Trough, the Matchless Amphibolite and the scapolite schists in the north speak in favour of formation parallel to tectonic transport in thrust zones as described by Hobbs et al. (1976).

A major phase of thrusting occurred during this stage of the structural evolution. The thrust zones are high-strain zones and simple shear deformation plays a major role as evident from non-

coaxial deformation. Observed shear senses are mostly directed towards the south-east. It is mainly the overprinting relationships of D_3 features on D_2 which indicate that the main thrusting period occurred late during D_2 , most probably representing the culmination of this D_2 deformation. The lack of mylonites might indicate that folding and thrusting occurred contemporaneously, a feature pointed out by Lewis et al. (1988). The orientations of thrust zones also confirm the steepening of structural elements towards the north to develop an overall imbricate fan geometry as indicated in Figure 4.22.

Finally the coaxial and subhorizontal attitude of structures developed in low-strain zones is related to simple shear deformation whereas pure shear produced plunging attitudes of structural elements in high-strain zones during the subsequent D_3 deformation.

4.5.3 D_3 phase of deformation

The structural patterns which characterize the third deformation differ from those of the D_2 phase. The S_3 cleavage and F_3 folds have preferentially developed within zones of high strain. The penetrative S_3 biotite fabric is a spaced cleavage and tight to isoclinal metre-scale F_3 folds have only developed within these high-strain zones. The style and scale of folding and the development of plunging F_2 and F_3 fold axes indicate that shear processes have played a major role during and after D_3 . Downward-

facing D_2 folds originated through the refolding of overturned D_2 limbs during D_3 . Sillimanite knots which were formed during D_2 have partly been reorientated into the S_3 cleavage. The participation of fluid phases during deformation in high-strain zones is illustrated by the post- D_3 scapolitization of metasediments in the north. The above aspects indicate that the D_3 deformation had mainly a compressional character.

The features outlined for the D_1 , D_2 and D_3 deformations show that fold formation, cleavage formation and thrusting occurred continuously through time, emphasized by the inheritance of the major thrust from one phase to the next. The structural evolution of the Khomas Trough is therefore interpreted to be one of progressive deformation.

4.5.4 Later phases of deformation

S_4 crenulation cleavages and related small-scale F_4 folds are only developed at the southern and northern margin of the study traverse. The symmetric and asymmetric fabric only occurs in the most pelitic lithologies where it overprints earlier planar fabrics. An early generation of Donkerhoek pegmatites as well as some granite apophyses are folded by D_4 .

Asymmetric and monoclinial kink folds, designated as D_5 structures in Table 4.1, with southerly dipping axial surfaces are a particular feature of the southern part of the traverse up to the

Matchless Amphibolite. The kink folds clearly post-date the crenulation cleavage. The development of kink folds has been attributed to the principal compressive stress directions being parallel to the folded surface and cleavage planes (Donath, 1961). It is therefore probable that the kinks developed by late-phase fault movements directed towards the south-east. The restriction of the kink folds to the southern part of the traverse might be a factor of confining pressure with the preferred kink band formation above 3 kbar as shown by experiments of Anderson (1974).

4.5.5 Strike-slip displacement along the northern margin of the Khomas Trough

The clockwise rotation of structural elements in domain D is the youngest deformation discernible in this area. This rotation has been explained to be caused by the intrusion of the Donkerhoek Granite (Faupel, 1974) or by late right-lateral strike-slip movement (Gevers, 1963; Blaine, 1977) in the vicinity of the Okahandja Lineament (Miller, 1979). These findings are in contrast to a study of Downing and Coward (1981) who postulate a sinistral strike-slip movement along the Okahandja Lineament, based on a south-west - north-east orientated extension lineation in the Central Zone and the Okahandja Lineament Zone.

A compilation of data from several studies in the vicinity of the Donkerhoek Granite (Gevers, 1963; Smith, 1965; Faupel, 1974; Hälbich, 1977; Blaine, 1977; Sawyer, 1981; Preussinger, 1987) has been undertaken by the present author. This has revealed that rotation of structural elements is not confined to the respective outcrop limits of the granite. It is therefore concluded that the clockwise rotation has occurred post- D_4 within a right-lateral transpressional strike-slip regime, according to the mechanism described by Sanderson and Marchini (1984). Since some granite apophyses have been folded by D_4 it is conceivable that strike-slip displacement and granite intrusion were approximately contemporaneous.

4.5.6 Aspects of strain determinations

Strain determinations within the Khomas Trough have been undertaken previously by Hälbich (1977) who obtained a total amount of 67% shortening, studying selected folds and calc-silicate spindles in the Okahandja - Windhoek profile. Sawyer (1981) has used folds, deformed pebbles, variolites and amphibolite pillows for his strain determinations and presents a rough estimate of 50-80% shortening for the Khomas Trough. Within the Kuiseb schists markers to determine strain quantitatively are extremely rare. Calc-silicate bodies of spindle shape are widespread and it has been shown previously that their maximum elongation is parallel to the regional fold axes in the Y-direction of the strain ellipsoid. These bodies do not, however, appear to be suitable.

for strain analysis since they represent originally calcareous lithologies which have been subjected to concretionary processes and metamorphism, as pointed out in Chapter 3. Pillow bodies within the Matchless Amphibolite have been used by Sawyer (1981) and they are also studied here to give an initial overview on the types of strain involved during deformation. The profile from which data were obtained is shown in Figure 5.2. The pillows are considered to have had originally spherical or near-spherical shape which is confirmed by the X:Y:Z data of certain pillows in zones of low strain. In contrast to the calc-silicate spindles the maximum direction of extension, X, is perpendicular to the regional strike. The intermediate elongation, Y, parallels the regional fold axes. Strain data and calculations are compiled in Table 4.4 which gives the number of two- and three-dimensional readings as well as the maximum, minimum, and average extension and shortening. The initial size of the assumed spherical pillows has been calculated from the X:Y:Z ratios, with $Z=1$.

The results in Table 4.4 indicate that shortening in the Z direction averages 47%, ranging from 20% to 63%. Extension towards X is most pronounced and the wide range of values for both extension directions demonstrates the variability of imposed strain rates. High-strain and low-strain zones on a metre-scale within the Matchless Amphibolite (see Chapter 5.3.2) are respectively represented by maximum and minimum values of extension.

Table 4.4: Strain data for deformed pillow structures in locality A (Fig. 5.1) at the Matchless Amphibolite. Given are averages, minimum, and maximum extension and shortening obtained from three-dimensional (n=6) and two-dimensional (n=23) measurements (formulas after Hobbs et al., 1976: p. 33).

	$\bar{X}$	$\bar{Y}$	$\bar{Z}$	$\frac{R_{xy}-1}{R_{yz}-1}$
pillows (n=6)	4.5	2.9	1	0.02-1.05
extension (mean) (max./min.)	107% (123%/50%)	70% (116%/36%)		
shortening (mean) (max./min.)			-67% (-61%/-35%)	
pillows (n=23)		3.3	1	
extension (mean) (max./min.)		81% (170%/22%)		
shortening (mean) (max./min.)			-45% (-63%/-20%)	

Shortening estimates, however, are regarded as minimum values since competent pillows within an incompetent amphibole-carbonate-plagioclase matrix most probably react to compressive stress to a certain extent by internal deformation. They might therefore record different strain from that of the bulk of the rock, a factor pointed out by Hobbs et al. (1976) as being valid for most lithological markers. Additionally several successive stages of shortening which have not been separated are likely to be recorded within the pillows.

Three-dimensional measurements have been plotted on a Flinn diagram (Fig. 4.32). The ellipsoids are oblate and in the field of apparent flattening. The data confirm a large flattening strain imposed and k-values from 0 to 1 imply a complex deformation history involving flattening-type deformation with volume loss and plane strain deformation in a simple shear environment. High- and low-strain domains are additionally confirmed by these data indicating progressive incremental shortening.




Fig. 4.32: Flinn diagram showing data from strain measurements of pillow structures within the Matchless Amphibolite. Pillows plot into the oblate field indicating a flattening-type deformation.

4.5.7 Consideration of previous studies: a correlation of deformation events in the Khomas Trough

With the increasing number of data obtained from studies in various parts of the Damara Orogen it is tempting to combine these to correlate deformation events over larger areas. It has been frequently shown in other folded terranes that it is highly tenuous to correlate structural elements over such large areas. In acknowledging this problem a correlation of structural elements is nevertheless proposed in the case of the Khomas Trough. This is based on a few detailed structural studies which have been undertaken in previous years. In order to improve the confidence level of such a correlation the study areas of Hälbich (1977) in the east and of Sawyer (1981) and Preussinger (1987) in the Namib Desert Park in the west have been additionally studied by the present author. The correlation is mainly based on the character of foliations, the associations of mineral assemblages with particular deformation periods (see Chapter 6.2) and on fold styles. The proposed correlation is summarized in Table 4.5.

A weakly developed and transposed S_1 fabric has been reported by all authors except Hälbich (1977) and its existence is acknowledged in Table 4.5. The D_2 phase involved the formation of a penetrative metamorphic banding cleavage, tight to isoclinal folds, thrusts, and an L_2 down-dip mineral lineation. This phase is also associated with the growth of a variety of metamorphic index minerals (Chapter 6.2), all features which are similar to

Table 4.5: Proposed correlation of deformation phases of various studies in the Khomas Trough. Note that Sawyer (1981) suggests contemporaneous deformation of the Central Zone, Okahandja Lineament Zone and the Khomas Trough. Abbreviations: CZ, Central Zone; OLZ, Okahandja Lineament Zone; KT, Khomas Trough.

Namib desert/Gorob mine		Okahandja-Windhoek section	Upper Black Nossob River area	Khomas Hochland Escarpment
Sawyer 1981 CZ-OLZ-KT	Preussinger 1997 KT	Hälbich 1977 OLZ-KT	Kasch 1986, 1987 Eastern KT	Kukla (this study) Western KT
D ₁	D ₁		D ₁	D ₁
D ₂	D ₂	D ₁	D ₂	D ₂
D ₃	D ₃	D ₂	D ₃	D ₃
D ₄	D ₄	D ₃	D ₄	D ₄
D ₅				D ₅
D ₆				

Hälbich's (op.cit.) D₁ phase (Table 4.5). Structural elements of subsequent deformation phases seem also comparable throughout the Khomas Trough and show regional importance including the D₄ phase which is mostly represented by crenulation cleavages and associated open folds. Sawyer's (1981) D₅ and D₆ deformations are minor phases of kink folds comparable to the late-phase kinking event described from the present study. Finally it is important to point out that there is considerable disagreement on the timing of structural elements between the Central Zone, the

Okahandja Lineament Zone, and the Khomas Trough. Whilst Miller and Hoffmann (1981) postulate two earlier deformation phases in the Central Zone, Sawyer (1981) presents evidence that all three zones experienced the same deformation episodes, as shown in Table 4.5.

4.6 Structural evolution of the Khomas Trough fold-and-thrust belt

Various authors have previously speculated upon the structural evolution of the Khomas Trough. Only very little research, however, has been undertaken to study in detail the deformation features within the Khomas Trough to finally present an evolutionary synthesis. Gevers (1963) characterized the "Khomas Highlands" as a tightly folded synclinorium of schists with largely isoclinal folds. Hälbig (1977) based the timing of deformation events "in the absence of marker horizons" on fold styles and subdivides the area into a northern belt with discernible major fold structures and a southern belt with a preponderant schistosity. He draws the boundary in the area of the graphite schist on the farm Kaan of this study. Hälbig (op.cit.) further defines on the basis of aerial photographs two major synclinal structures (Berlin and Gorogoneib synclines) in the northern Khomas Trough. This cannot be confirmed since the suggested synclinal axes are in fact geographically situated at the scapolite schist sequences which have proved to separate openly from isoclinally folded areas with a thrust zone situated in the supposed hinge area.

In conclusion, the structural investigations within this study have revealed the following structural patterns. An initial phase of deformation (D_1) was associated with the formation of a biotite foliation and of folds and was accompanied by thrusting. A major deformation period, labelled D_2 , involved the formation of: (1) penetrative axial planar cleavages; (2) tight to isoclinal and open asymmetric folds; (3) downward-facing folds in previously overturned strata; and (4) thrust faults. The cleavage formation parallel to the XY plane of the finite strain ellipsoid was accompanied with the formation of folds of various styles. Folding, thrusting and south-eastward directed structural translation occurred contemporaneously. The major compression was directed towards the north-west and elongation occurred along D_2 axes towards the north-east. This major regional deformation was followed by the D_3 deformation which was a phase of intensified shear within high-strain thrust zones. A strong spaced cleavage and isoclinal F_3 folds were formed preferentially in these zones. Fluid movement along the D_3 thrusts is indicated by the scapolitization in the northern Khomas Trough. The patterns of the D_1 , D_2 and D_3 phases of deformation show that the structural evolution is one of progressive deformation. Late phases of deformation include the formation of crenulation cleavages (D_4) and the formation of kink folds (D_5) which might indicate layer-parallel faulting. The emplacement of the Donkerhoek Granite took place during these late deformation events and right-lateral strike-slip faulting occurred along the northern margin of the Khomas Trough, indicating an oblique compression direction rela-

tive to the margins of the Central Zone. Prominent north-south and north-west trending fault sets clearly post-date the Donkerhoek Granite and have been attributed to Karoo age by Behr et al. (1983).

The above features show that the Khomas Trough deformational history involves several deformation phases which are characterized by contemporaneous folding and thrusting throughout the structural evolution. This has developed laterally extensive, northward steepening thrust slices within an overall imbricate fan geometry with probably repeated sedimentary sequences. The thrust zones which are situated in pelitic schists, graphite schists, and amphibolites have been a locus of both thrusting and shearing throughout the protracted history of the Southern Damara Orogen. This structural style shows striking similarities to the imbricate thrust fan and duplex geometries which have been reported from many compressional fold-and-thrust belts worldwide (e.g. Boyer and Elliot, 1982; Park, 1988). Examples of these are, amongst others, the Caledonides of Britain, the Alps, the Himalayas, the Appalachians as well as parts of the Pan-African of Mozambique (Shackleton and Ries, 1984) and Morocco (Saguarque et al., 1989). This comparison is especially valid when the distinct changes of structural styles across the thrust slices in the Khomas Trough are considered.

5. THE MATCHLESS AMPHIBOLITE

5.1 General setting of the Matchless Amphibolite

The Matchless Member (SACS, 1980) of the Kuiseb Formation forms a linear outcrop which may be traced for more than 350 km along strike from the Namib desert in the south-west to the Steinhausen area in the north-east (Fig. 2.4). The Matchless Member sequence, here termed the Matchless Amphibolite, consists of interlayered amphibolites (mainly), metagabbros and metasediments. In other areas west and east of the study traverse Alpine-type ultramafic bodies are also associated with the Matchless Amphibolite (Barnes, 1982).

Several economically important massive sulphide ore bodies and prospects such as Gorob, Hope, Matchless, Kupferberg, Otjihase and Ongombo occur within the sequence. Studies by Finnemore (1978), Sawyer (1981), Barnes (1982), Killick (1983), Miller (1983c), Schmidt and Wedepohl (1983), Breithkopf and Maiden (1987, 1988), Preussinger (1987, 1990) and Klemm et al. (1987, 1989) have concentrated mainly on the geochemistry and the ore-forming processes within the Matchless Amphibolite. The main concern of this study, however, are aspects of the stratigraphic and structural relationships of various metabasic and metasedimentary rock types. Unusually well-preserved outcrops in the study area (Fig. 5.1,A) have allowed mapping of several correlative river profiles along strike.

5.2 Lithologies, mineral assemblages and textures

The mafic rock types may be distinguished on the basis of textures and mineral assemblages into: type I, massive, epidote-rich amphibolite; type II, banded, carbonate-rich amphibolite; and type III, coarse grained amphibolite, i.e. metagabbro. Amphibolitic breccias have also been encountered in the present study. The amphibolites are associated with chlorite schists, pelitic and psammitic schists, graphite schists, and a thin marble unit.

Type I amphibolites are massive, epidote-rich and form units which comprise mostly pillow lavas. Modal compositions are dominated by green and blue-green hornblende, plagioclase and epidote. Minor constituents are chlorite, sphene, clinozoisite, opaque grains, biotite, calcite and quartz. Calcite is much less common than in type II amphibolites and occurs mostly in small layers or segregations together with chlorite and epidote. Pillow structures which have also been described from other parts of the Matchless Amphibolite (Sawyer, 1981; Miller, 1983a; Bretkopf and Maiden, 1987; Preussinger, 1987) are abundant in all measured sections. They occur as spheroidal to elongated bodies which are separated by seams of epidote amphibolite forming the inter-pillow fillings (Fig. 5.1,B).

Type II amphibolites are parallel to wavy banded and carbonate-rich. The banding consists of alternations of light bands comprising plagioclase-epidote-calcite-quartz assemblages and

dark bands comprising green hornblende-epidote-calcite-quartz-plagioclase assemblages with minor biotite and chlorite (Fig. 5.1,C). Hornblendes within the matrix and opaques define the predominant S_2 structural fabric whereas large hornblende crystals overgrow the S_4 crenulation cleavage.

Type III amphibolites (metagabbros) are coarse-grained and mineralogically uniform, containing mainly porphyroblasts of green hornblende, plagioclase and calcite. Minor constituents are epidote, sphene, chlorite and opaques. Grain sizes are coarse but a distinct zoning towards finer grained margins has also been observed in association with shear zones (Fig. 5.1,D). Metagabbro lithologies form lensoid, round and irregular shaped bodies within the amphibolites and at the contacts to metasediments. Sizes are variable from a few metres to several tens of metres in length and width. In one case a "bleached" margin to the pelitic host rock has developed. The contact zone is extremely fine grained showing the assemblage quartz-plagioclase-hornblende-chlorite-biotite-epidote. Similar features in other areas along the Matchless Amphibolite have been interpreted as "chilled" intrusive margins (Preussinger, 1987; Bretkopf and Maiden, 1987).

Amphibolite breccias have been found in parts of the sequence containing several tens of centimetres long clasts or aggregates comprising hornblende and chlorite in a matrix of both type I and

Fig. 5.1: Features of the Matchless Amphibolite.

(A) Photograph showing the Matchless Amphibolite (indicated by arrows) as a prominent feature in the landscape on the farm Annelie 412 (see profile A in Figure 5.2).

(B) Little deformed pillow structures wrapped around by extremely sheared pillows and inter-pillow fillings in type I amphibolites. Farm Annelie 412 (profile A in Figure 5.2); lens cap is 4.9 cm in diameter.

(C) Carbonate-rich, banded type II amphibolite. Farm Kobos 305 (profile B in Figure 5.2).


(D) Photograph showing structurally emplaced metagabbro body in type I amphibolite. Note extremely sheared margins, underlined by plagioclase elongation. Amsas river profile, farm Kobos 305.

(E) Photograph showing amphibolitic breccia, consisting of elongated, massive, type I amphibolite clasts within type II amphibolite matrix. Farm Kobos, Amsas river (profile B in Figure 5.2).

(F) Chert nodules developed in type I amphibolite in the footwall of the Matchless sequence on the farm Annelie 412 (see also Figure 5.4).

(G) Photograph showing décollement plane developed in the thick graphite schist in the structural footwall of the Matchless sequence. Farm Kobos 305, see Figures 5.2, B and 5.5.

(H) Photograph showing post-D₂, north-west dipping thrust planes developed in type I amphibolite. Farm Annelie 412.



type II amphibolites (Fig. 5.1,E). Cherts occur as several cm long "clasts" in type I amphibolites in the structural footwall of the Matchless Amphibolite on the farm Annelie (Fig. 5.1,F).

Associated with the amphibolites are extremely fine-grained chlorite schists, chlorite-hornblende schists and biotite schists. These comprise mainly chlorite, epidote, biotite, hornblende and opaques. Minor constituents are plagioclase, calcite, quartz, garnet, sphene and clinozoisite.

Several graphite schists are associated with the Matchless Amphibolite and a distinct dolomitic marble unit occurs in the hangingwall of the sequence.

Field observations such as: the conformable intercalation of metasediments with amphibolites; the lateral extent of the fine- to medium-grained amphibolites; and the recognition of pillow lavas suggest that the amphibolites were derived from mafic extrusive rocks. The interpretation of the metagabbros as metamorphosed mafic intrusives is based on partly developed bleached marginal zones with sediments and amphibolites and on coarser grained cores compared with the rims. The metagabbros, however, have mostly been subjected to structural displacement and dismemberment which will be discussed later.



5.3 Stratigraphic and structural relationships

5.3.1 Stratigraphy

Three traverses within the Matchless Amphibolite sequence have been studied in detail and these are shown in Figure 5.2. The measured sections confirm that the overall structural thickness of the Matchless Amphibolite is in the order of 1500 m in this area. There are basically three major units developed: (1) A structurally lower unit consisting of intercalated graphite schists, pelitic schists and minor psammitic schists, metagabbros and amphibolites; (2) a middle unit comprising massive and banded amphibolites as well as some gabbros; and (3) an upper unit with intercalated pelitic schists, graphite schists, a marble unit and amphibolites (Fig. 5.2).

A comparison of the sections in Figure 5.2 shows that metagabbro bodies occur preferentially in the lower parts of the sequence mostly at contacts of amphibolites with sediment. Carbonate-rich type II amphibolites occur in the upper parts and pillow lavas mostly in the massive middle unit together with breccias. Graphite schists and graphitic pelites up to several metres thick occur in the structural footwall of the sequence. A thick graphite schist unit in this position has also been described from the Gorob area further to the west (Sawyer, 1981; Preussinger, 1990). The metasediments throughout the studied sections are mainly pelitic with, however, a strong predominance of chlorite schists.

Fig. 5.2: Map and detailed measured sections A - C along the Matchless Amphibolite. Also shown are positions of geochemistry samples within the Annelie (A) and Amsas (B) river profiles and the locations of Figures 5.4 - 5.7.



Bed thicknesses do not exceed 15 cm. Graded layering provides way-up criteria indicating mostly right way-up and some inverted sequences. In the upper part of the Matchless sections, the up to 2 m thick marble unit occurs rather continuously along strike for more than 10 km (Fig. 5.2). The layer is strongly boudinaged which most likely accounts for the occasional non-recognition of this unit as in traverse B (Fig. 5.2). The occurrence and thickness of graphite layers in the structural hangingwall varies along strike.

5.3.2 Structure

As with the surrounding Kuiseb schists, the structural geology of the Matchless Amphibolite is characterized by folding and thrusting. According to the timing of deformational events established in Chapter 4, D_2 is generally the main folding phase which accounts for the development of strongly isoclinal, metre-scale folds and a penetrative, north-west dipping S_2 cleavage (Fig. 5.3). Elongated biotites and hornblendes form a pronounced down-dip L_2 lineation which shows its strongest development at the Matchless Amphibolite if compared with other areas of the study traverse as a whole. Pillow bodies are also strongly elongated down-dip on S_2 planes. Other features are the S_3 biotite fabric, which is recognizable in intercalated biotite schists, and a strong S_4 crenulation cleavage. The structural features within the Matchless Amphibolite show all characteristics of high-strain zones which have been described in the structural context of the




Fig. 5.3: Stereonet showing structural data from amphibolites and metasediments of the Matchless Amphibolite. Note sub-horizontal to plunging attitude of fold axes. (Symbols: X, poles to S_0 ; Δ , poles to S_2 ; $\blacktriangle$, poles to D_2 axial plane; $\times$, poles to S_3 ; $\square$, poles to S_4 ; $\blacksquare$, poles to D_4 axial plane; $\odot$, F_2 fold axis; $\otimes$, F_4 fold axis; $*$, L_{2A} lineation; for further details see Chapter 4.4.2).

overall study traverse in Chapter 4.4.2. On a small scale, the alternation of low- and high-strain zones in vertical profiles is illustrated in Figure 5.4 by the shape of pillow lavas some of which have their spheroidal shape preserved whereas others are extremely elongated. Thrusting is generally evident from the displacement of type I and type II amphibolites, metagabbros and metasediments as well as the development of shear zones. The pronounced L_2 lineation has been interpreted to have formed parallel to tectonic transport in thrust zones (Chapter 4).




Fig. 5.4: Detailed measured section (profile A in Fig. 5.2) showing the interposition of amphibolites, metagabbros and metasediments. Major thrust contacts are indicated and the spheroidal to elongate shape of pillows lavas (distinguishable by the degree of curvature of the pillow symbol in the figure, e.g. in the top part of the left column) is regarded as a measure of the imposed strain (for symbols see Fig. 5.2).

High strain zones are associated with thrusting which is particularly evident in the lower part of the sequence, shown in the Annelie section where major thrust contacts occur (Fig. 5.4). A major horizon of displacement is developed at the lowermost graphite schist (Fig. 5.5) with a *décollement* plane indicated by the disruption of layering and fabrics, silicification, quartz segregation and sulphide precipitation (Fig. 5.1,G). Further upwards, displacements and shear zones are mainly observable at the contacts of metasediments, metabasalts and metagabbros (Fig. 5.4).




Fig. 5.5: Diagram showing graphite schists developed in the Amsas river section. A major *décollement* is developed in the lower part of the sequence. The location of the profile is indicated in Figure 5.2,B.

Structural displacement of the metagabbros is postulated on the basis of contact relationships between amphibolites and metasediments. Metagabbro always occurs in bodies which are up to 10 m thick but which terminate mostly within the lateral extent of the outcrop (Fig. 5.6). The majority of the contacts with associated lithologies are sharp and the rims of the metagabbro lenses are extremely sheared (Fig. 5.1,D). Some of the bodies confirm the overall south-eastward directed vergence and displacements by their overall shape and by the internal shear fabric (Fig. 5.6).




Fig. 5.6: Sketch showing the structural interposition of sheared metagabbro bodies with type I and type II amphibolites and with chlorite schists. Note sigmoidal internal shear fabric of the metagabbros. The location and symbols are shown in Figure 5.2,B.

The main thrusting event has occurred syn- to post- D_2 (Figs. 5.7 and 5.1,H) which is inferred from the associated shearing of the S_2 cleavage and the unaffected S_3 fabric. Post- D_3 thrusting also occurs, however, as illustrated by the shearing of D_3 structural elements in parts of the sequence. The D_4 crenulation cleavage post-dates these events.




Fig. 5.7: Structural sketch showing post- D_2 thrusting within a pillow lava sequence on the farm Annelie (see Fig. 5.2,A). Note the sheared pillow structures. Form lines represent S_2 structural fabric. For symbols see Figure 5.2.

Concluding the above, thrusting and shearing identify the Matchless Amphibolite as a highly and heterogeneously strained zone situated within pelites of the Kuiseb Formation. Graded layering suggests that the overall sequence is upward-facing.

Structural dislocation is especially indicated in the lower parts of the sequence with the interposition of thinly layered amphibolites, pelitic schists, graphite schists and metagabbro bodies. Upper parts of the sequence show a more coherent relationship between carbonate-rich amphibolites and units of graphite schist and marble.

5.4 Classification of metabasic rocks

Over and above the study of field relationships, a classification and chemical characterization of the amphibolites and metagabbros within the Matchless Amphibolite aimed to determine the nature of the Matchless metabasic rocks. Geochemical analyses of 23 major and minor elements were undertaken by XRF analysis on 14 amphibolite and metagabbro samples along the Amsas river profile and the profile on the farm Annelie. Sample locations are indicated in Figure 5.2 and full analyses are presented in Appendix II.

The geochemistry of the Matchless metabasites has previously been investigated in detail in a number of studies (Finnemore, 1978; Miller, 1983c; Schmidt and Wedepohl, 1983; Breitkopf and Maiden, 1987; Klemm et al., 1989). In particular Miller (op.cit.) and Breitkopf and Maiden (op.cit.) have put emphasis on element mobility during hydrothermal alteration and metamorphism. These authors show that the high field-strength elements (small size, high charge) such as Zr, Y, Nb, Ti, and Al may be considered to have behaved in an immobile fashion. Most major elements on the

other hand have been considerably mobile. These results from the Matchless Amphibolite confirm the findings of Pearce (1975) and Garcia (1978) from studies of various metabasalts elsewhere. Major element mobility is also indicated by plotting data of this study in the classification diagram of Cox et al. (1979) which shows a wide spread of compositions for the analysed samples mostly within the basalt field (Fig. 5.8).




Fig. 5.8: Variation diagram $K_2O + Na_2O$ versus SiO_2 after Cox et al. (1979) classifying amphibolites and metagabbros of the Matchless sequence as basalts.

A distinct tholeiitic trend for the amphibolites is defined by the TiO_2 versus Zr diagram of Floyd and Winchester (1975) which shows the majority of the samples exclusively in the oceanic tholeiite field (Fig. 5.9). This is confirmed by the diagram of Miyashiro and Shido (1975) which is based on absolute contents of SiO_2 and Cr (Fig. 5.10). Judging from these data the Matchless amphibolites may be classified as tholeiitic metabasalts.




Fig. 5.9: Variation diagram TiO_2 versus Zr after Floyd and Winchester (1975). The majority of the Matchless metabasites plot within the oceanic tholeiite field. Symbols as for Figure 5.8.




Fig. 5.10: Matchless Amphibolite samples plotted on the variation diagram SiO_2 versus Cr after Miyashiro and Shido (1975). This shows the tholeiitic character of the Matchless metabasic rock types. Symbols as for Figure 5.8.

In acknowledging the problem of element mobilities, the discrimination diagrams most widely used to deduce the tectonic setting of basaltic rocks are those employing the above mentioned elements, which have proved immobile in many studies. The diagram of Pearce and Cann (1973) uses Ti, Zr and Y and the Matchless samples cluster in the ocean floor basalt, within-plate basalt (i.e. continental and ocean island basalt), and island-arc fields (Fig. 5.11). The Zr/Y versus Zr diagram of Pearce and Morry (1979), however, characterizes all samples, apart from one metagabbro sample, as mid-ocean ridge basalts (MORB; Fig. 5.12).




Fig. 5.11: Matchless Amphibolite samples plotted on the triangular variation diagram after Pearce and Cann (1973). Within-plate basalts plot in field D, ocean-floor basalts in field B, island-arc tholeiites in fields A and B and calc-alkali basalts in fields C and B. Symbols as for Figure 5.8.

In conclusion, the Matchless amphibolites represent metamorphosed equivalents of igneous rocks of tholeiitic basaltic composition. Although some of the analysed amphibolites plot close to and into the within-plate basalt field, the majority show geochemical affinities to mid-ocean ridge basalts.




Fig. 5.12: Variation diagram Zr/Y versus Zr after Pearce and Norry (1979) showing the mid-ocean ridge basalt (MORB) affinity of the Matchless metabasites. Symbols as for Figure 5.8.

A comparison of average geochemical compositions of the Matchless amphibolites with those of within-plate and plate margin basalts as compiled by Carmichael et al. (1974), Pearce (1976) and Condie (1982) shows that most elements, but especially the more immobile TiO_2 , Zr , Y , Co and Cr , compare best with low-K ocean-floor basalts from diverging plate regimes.

These data confirm the results of Finnemore (1978), Miller (1983c) and Schmidt and Wedepohl (1983) who found exclusively mid-ocean ridge type compositions for the Matchless metabasalts. This is in contrast with the findings of Bräitkopf and Maiden

(1937) who describe within-plate compositions of metabasalts in the western Khomas Trough and mid-ocean ridge basaltic compositions to the east of Windhoek.

5.5 Tectonic setting of the Matchless Amphibolite with special regard to the development of the Khomas Trough

In summary detailed sections through the Matchless Amphibolite show the sedimentological and structural interposition of various amphibolites, metagabbros, amphibolite breccias, pelitic schists, some psammitic schists, graphite schists, and a marble unit. Structural emplacement is indicated especially in the lower parts of the sequence. Serpentinities which are derived from mantle harzburgites are a structurally dismembered part of the sequence as well (Barnes, 1982). Genetically the extrusive origin of the amphibolites in a submarine environment is confirmed by pillow lavas and gradational contacts with pelitic and some psammitic sediments. Graded layering within sequences of amphibolites, metagabbros and various sediments demonstrates the generally contemporaneous aspect of turbidite and pelagic sedimentation and mafic extrusion as well as intrusive magmatism. Isotope signatures of graphite schist and marble (see Chapter 3) confirm additionally contemporaneous biogenic sedimentation and hydrothermal magmatic processes on the sea floor. Geochemical analyses reveal an oceanic tholeiitic character and a close affinity of the Matchless metabasic rocks to mid-ocean ridge basalts.

Since more detailed studies have been carried out during the last decade, the genesis and tectonostratigraphic importance of the Matchless Amphibolite has been discussed intensively and several models have been presented. The basic question which has arisen is whether or not the metabasalts are of plate margin or of intraplate origin. Finnemore (1978) concludes his initial geochemical studies, characterizing the amphibolites as having followed a tholeiitic differentiation trend but within an ensialic crust which he interpreted because of a perceived lack of field evidence for a collisional orogeny. From geological comparisons with similar settings, Hartnady (1978) suggests that the Matchless massive sulphide deposits may have been formed both in Red Sea type settings and also at mid-ocean ridges. Schmidt and Wedepohl (1983) found exclusively MORB major and minor element patterns along the entire Matchless Amphibolite. Furthermore rare earth elements demonstrate a very flat element pattern i.e. a very small degree of fractionation of the light rare earth against the heavy rare earth elements. These patterns are characteristic for ocean-ridge tholeiitic basalts (Menzies, 1976). The authors conclude their study with a statement that, judging from the lack of evidence for ophiolitic suites and deep-sea sediments, the Damara Orogen must have formed on sialic crust although all geochemical signatures point towards mid-ocean ridge basalts and low-K tholeiites.

From tectonostratigraphic considerations Kasch (1983a) postulates that the Matchless Amphibolite either represents a fragment of oceanic crust emplaced in an active subduction complex or that basaltic magmas intruded into trench deposits. Miller (1983c) also found evidence for tholeiitic trends from geochemical studies and envisages the formation of the basalts and massive sulphide deposits in a Red Sea type situation with volcanics and intrusives occurring above a buried mid-ocean ridge with minor amounts of oceanic crust. Considering the massive sulphide mineralizations and their host rocks, Killick (1983) concludes that the deposits have most probably formed at a site of sea-floor spreading at a constructive plate margin.

Breitkopf and Maiden (1987) found that the western Matchless Amphibolite shows a considerable amount of fractionation which they related to the presence of continental crust in this area. In contrast to this, samples from the eastern part show little fractionation and are interpreted by Breitkopf and Maiden (op. cit.) to have developed in small strike-slip related pull-apart subbasins underlain by oceanic crust.

Klemm et al. (1989, p. 615) conclude their geochemical studies of the Matchless massive sulphide ore deposit with a model which involves "... seafloor precipitation of metal sulphides from convecting hydrothermal fluid generated by reaction of seawater with subseafloor basalts and clastic sediments".

In view of the massive sulphide mineralization, Rona (1988), in his compilation of massive sulphide deposits associated with oceanic ridges worldwide, gives statistics concerning the tectonic settings of these deposits. This shows that basalt-hosted massive sulphides which may have formed in oceanic hydrothermal settings constitute about 17% of the 508 deposits considered; sediment-hosted deposits associated with oceanic volcanic rocks form about 9%. The most numerous and largest deposits occur in subduction-related volcanic suites and island-arc or continental rift tectonic settings which are associated with rhyolites. Rona (op.cit.) further states that all major massive sulphide deposits associated with basalts in the ancient record are related to oceanic ridges and rifts.

Thus the sum of stratigraphic, sedimentological, structural and geochemical data from the Matchless Amphibolite suggests an interaction of contemporaneous pelagic sedimentation, turbiditic sedimentation and formation of massive sulphide deposits in an oceanic setting. This allows a comparison with oceanic ridge settings close to adjacent continents such as in the eastern Pacific. There sediment-hosted massive sulphide deposits are associated with volcanics of MORB composition such as in the Escabana Trough of the southern Gorda ridge (Morton et al., 1987) and in the Middle Valley (Endeavour segment) of the Juan de Fuca ridge (Davis et al., 1987). Similar associations of meta-greywackes and pelagics with only minor amounts of oceanic pillow basalts, cherts and some ultramafics (without sheeted dykes) in

ancient terrains are known from parts of the Cordillera Belt such as the Slide Mountain and Quesnel terrains (Coney, 1989) and from the Central Appalachians (Lash, 1986). Judging from these data the Matchless Amphibolite is here interpreted to represent the upper part of an oceanic crustal sequence.

6. METAMORPHISM

6.1 Introduction

Studies on the metamorphic evolution of the Khomas Trough were undertaken by Hoffer (1977) as part of a large scale investigation on the thermal evolution of the Damara Orogen. Metamorphism of the eastern Khomas Trough has been studied by Kasch (1983b, 1987); whereas Sawyer (1981) and Preussinger (1987, 1990) studied the metamorphism of the western Khomas Trough.

Taking the approach and the findings of the latter studies into account it is the aim of this chapter to present an overview of the critical mineral assemblages and textures of pelites and calcareous rocks encountered along the study traverse and to place crystallization events within the framework of the structural development of the Khomas Trough. The pelites of the Kuiseb Formation are most suitable for studies of the stability conditions during metamorphism. Mineral compositions of pelites from crucial areas have been determined by microprobe analysis. These together with data derived from mineral assemblages lead to qualitative and some quantitative pressure - temperature (P-T) estimates.

6.2 Mineral textures and relationships to structural elements

Textural relationships of mineral assemblages indicate their relative time of formation during consecutive deformation phases.

The study of mineral - fabric relationships is facilitated by the fact that original sedimentary layering is largely preserved in the metasediments. Figure 6.1,A shows a graded turbidite layer with psammitic compositions at the base consisting mainly of quartz, plagioclase and biotite. The thin pelitic top, however, shows staurolite strongly aligned with the bedding plane within a matrix of mainly biotite with minor quartz and plagioclase. This is an excellent demonstration that the development of specific mineral phases and assemblages depended largely on the respective small-scale bulk rock compositions.

Modal compositions of pelites which have also been analysed chemically (see 6.4) are shown in Table 6.1. Sample 86/76 is a chlorite schist and sample 306 contains scapolite as a major constituent. The composition of an average psammite is shown for comparison (sample 816 in Table 6.1). The relative timing of deformation phases D_1 to D_4 , which have proved to be associated with cleavage development (Chapter 4), and related crystallization events is presented in Table 6.2.

6.2.1 Pelites

Quartz is a major constituent of the groundmass of pelites and occurs as recrystallized grains of variable sizes. In the southernmost part of the traverse, close to the contact with the

Southern Margin Zone, as well as in shear and thrust zones throughout the traverse, quartz is highly strained, as indicated by undulous extinction and subgrain development.

Plagioclase is a common constituent of mineral assemblages in all rock types along the study traverse. The crystals are usually very small, xenomorphic and occur in clusters together with quartz. Sericitization is common, only very few twinned plagioclases have been found.

Table 6.1: Modal compositions of selected pelites, scapolite schists and psammities of the Khomas Trough (sample localities are shown in Figure 6.2).

SAMPLE	146	86/76	274	306	308	109	816
quartz	22	5	26	22	16	22	61
plagioclase	7	4	2	< 1	16	14	14
biotite	36	36	27	31	35	33	24
muscovite	33	8	27	< 1	7	28	< 1
garnet	2	1	< 1		5		
staurolite					3		
andalusite			4				
sillimanite					10	2	
scapolite				39	5		
chlorite		44	13	< 1	1	< 1	
green amphibole				6			
calcite				< 1			
opaque ore	< 1	2	1		1	< 1	< 1
tourmaline	< 1	< 1	< 1		< 1	< 1	< 1
sphene				< 1			
zircon	< 1	< 1	< 1	< 1	< 1	< 1	< 1
apatite	< 1	< 1	< 1	< 1	< 1	< 1	< 1
clino-zoisite				< 1			


K-feldspar occurs in coarsely recrystallized pelites as microcline at the northernmost margin of the study traverse in the Kaan river up to several hundreds of metres south of the contact with the Donkerhoek Granite.

Biotites are subidioblastic to xenoblastic red-brown to green-brown crystals. Generally biotite has crystallized syn- and post-kinematically during various deformation phases (Table 6.2). This is inferred from the alignment of the biotite generations within respective cleavage domains as well as from overprinting relationships of various biotite fabrics. Syn-kinematic biotites occur as small thin tablets and define the composite cleavage in the south, the S_1 , S_2 and S_3 penetrative cleavages further north as well as the distinct L_{2A} mineral lineation. The first biotite fabric formed during the D_1 deformation and has subsequently been wrapped-around and enclosed by biotites formed during the main deformation D_2 (Fig. 4.10). A third biotite fabric has formed during D_3 and clearly overprints earlier biotite generations (Fig. 4.10). Post-kinematic biotites occur throughout the traverse. The crystals are unorientated, up to several millimetres long and overgrow the penetrative cleavages as well as the D_4 crenulation cleavages. Biotites have also formed as reaction products around and within garnets. Frequent inclusions in biotites are quartz, zircon (with abundant pleochroic halos), muscovite, apatite and rutile.

K-feldspar occurs in coarsely recrystallized pelites as microcline at the northernmost margin of the study traverse in the Kaan river up to several hundreds of metres south of the contact with the Donkerhoek Granite.

Biotites are subidioblastic to xenoblastic red-brown to green-brown crystals. Generally biotite has crystallized syn- and post-kinematically during various deformation phases (Table 6.2). This is inferred from the alignment of the biotite generations within respective cleavage domains as well as from overprinting relationships of various biotite fabrics. Syn-kinematic biotites occur as small thin tablets and define the composite cleavage in the south, the S_1 , S_2 and S_3 penetrative cleavages further north as well as the distinct L_{2A} mineral lineation. The first biotite fabric formed during the D_1 deformation and has subsequently been wrapped-around and enclosed by biotites formed during the main deformation D_2 (Fig. 4.10). A third biotite fabric has formed during D_3 and clearly overprints earlier biotite generations (Fig. 4.10). Post-kinematic biotites occur throughout the traverse. The crystals are unorientated, up to several millimetres long and overgrow the penetrative cleavages as well as the D_4 crenulation cleavages. Biotites have also formed as reaction products around and within garnets. Frequent inclusions in biotites are quartz, zircon (with abundant pleochroic halos), muscovite, apatite and rutile.

Table 6.2: Relative timing of deformation phases and metamorphic crystallization in the western Khomas Trough.



Muscovites occur basically in two different modes. The first type is that of matrix muscovites which were orientated in the composite cleavage in the southern Khomas Trough and within the S₂ cleavage in the north. These muscovites were deformed within late crenulation cleavage domains (Table 6.2). The second type of muscovite has grown after the D₄ phase of deformation and occurs as small grains within the matrix but also as large porphyroblastic crystals which are up to several millimetres long. Crystalli-

zation under stress-free conditions (post-D₄) is indicated by radial muscovite bundles. A striking and widely distributed feature of the central and northern Khomas Trough is the muscovitization of alumo-silicates such as andalusite and sillimanite as well as of staurolite (Fig. 6.1,B).

Chlorite formation during prograde metamorphism in the southern part of the traverse is related to the D₂ deformation which is evident from assemblages containing chlorite, syn-D₂ garnet and biotite. Chlorite forms the matrix of rocks with suitable bulk compositions. Retrograde chloritization of biotite, garnet and staurolite occurs especially in the high-strain zones throughout the traverse.

Garnet occurs in three different generations. Garnet I is anhedral and poikiloblastic and is elongated within the composite fabric of the southern Khomas Trough with lengths/widths ratios of up to >10:1. The time of crystallization of this generation is somewhat uncertain but a pre-D₂ age is judged from textural relationships with syn-D₂ minerals and from subsequent garnet generations. Garnet II is subhedral to euhedral and shows internally snowball inclusion trails of opaque phases within the S_{0,1,2,3} composite fabric (Fig. 6.1,C) and the S₂ biotite fabric thus indicating synkinematic crystallization during D₂. Garnet III is also subhedral to euhedral and overgrows the S₃ cleavage but pre-dates the S₄ crenulation cleavage. Sizes of garnet porphyroblasts increase northwards.

Staurolite I crystallization prior to D_2 might be indicated in the southern Khomas Trough where staurolite porphyroblasts are wrapped-around by the composite cleavage (Fig. 6.1,D). Staurolite II porphyroblasts are anhedral, poikiloblastic and have formed syn- D_2 being associated with garnet II. In the north, staurolite III has crystallized post- D_3 shown by the overgrowth on the S_3 cleavage (Fig. 6.1,E).

Kyanite is only developed in the most Al-rich pelites in the southern Khoma Trough and occurs as xenomorphic grains which are strongly elongated in the composite cleavage. Contact relationships show that this kyanite generation pre-dates garnet II. Kyanite has also been observed together with quartz and chlorite in segregational spaces. Time constraints are lacking for this kyanite generation.

Andalusite occurs within a confined, about 3 km wide area in the centre of the Khomas Trough. Most of the andalusite has been replaced by muscovite and forms elongate aggregates of up to 10 cm length. The age of crystallization of the andalusite is uncertain since both orientation within S_2 cleavage domains and unorientated overgrowth on the S_2 fabric has been observed. Garnet III, however, occurs in an assemblage with the andalusite thus possibly constraining a syn- to post- D_3 growth of the andalusite.

Sillimanite occurs as fibrolite which is frequently intergrown with biotite. The fibrolite knots are elongated with their long axes parallel to both the S_2 and the S_3 biotite fabric. Although sillimanite is known to grow epitactic on earlier biotites which could be mistakenly interpreted as synkinematic growth, it has been observed that S_3 biotites are wrapped-around the fibrolite knots. Fibrolite is, however, mostly orientated within the S_3 cleavage. Further crystallization constraints come from contact relationships with post- D_3 staurolite III and garnet III indicating a post- D_3 growth of the sillimanite together with these minerals. Fibrolite bundles are deformed within the D_4 crenulation cleavage.

Scapolite is the major constituent of scapolitized psammites and pelites in the northern Khomas Trough. The scapolite forms a large proportion of the total rock volume in these areas and occurs most massively along veins and fractures thus proving discordant relationships (Fig. 6.1,F). The scapolite poikiloblasts are up to 1 cm across and enclose the S_2 and S_3 biotite fabrics which indicates post- D_3 crystallization (Fig. 6.1,G). The poikiloblasts enclose quartz, biotite, calcite and minor amounts of tourmaline and sphene. Plagioclase has not been observed in most massively scapolitized rocks but occurs in increasing amounts away from the scapolitized areas.

Fig. 6.1: Lithologies, mineral textures and deformational features.

(A) Photograph of graded turbidite bed showing the preferred crystallization of staurolite porphyroblasts in the pelitic top along the bedding plane (S_0) and within S_2 cleavage domains (indicated by arrows). The psammite at the base and the overlying psammite contain staurolite only scarcely. Locality is at the northern boundary of the farm Kaan 309.

(B) Photograph illustrating the pseudomorphism of muscovite after post- D_3 staurolite in the northern Khomas Trough. Locality is at the northern boundary of the farm Kaan 309.

(C) Photomicrograph (plane light) showing "snowball" garnet II within the $S_{0,1,2,3}$ composite cleavage in the southern Khomas Trough in a pelite of assemblage zone 1 (farm Usambara 304). The metamorphic mineral assemblage is garnet + biotite + plagioclase + quartz (specimen PK 855).


(D) Photomicrograph (plane light) showing early, possibly pre- D_2 , staurolite I wrapped around by the $S_{0,1,2,3}$ composite cleavage in a pelite of the southern Khomas Trough. The metamorphic mineral assemblage is staurolite + biotite + plagioclase + quartz, the staurolite is muscovitized (specimen PK 855, farm Usambara 304).

(E) Photomicrograph (plane light), illustrating the crystallization of staurolite III after the formation of the S_3 biotite fabric (indicated by arrow) in a pelite of assemblage zone 2 (specimen PK 838, farm Kaan 309).

(F) Photograph showing massive scapolitization along a fracture in psammitic schist (indicated by arrow). The amount of scapolite decreases away from this vein. Locality is at the southern scapolite schist on the farm Dagbreek 365. Pocket knife is 8.5 cm long.

(G) Photograph illustrating the post- D_3 crystallization of scapolite. The poikiloblasts enclose both the S_2 and S_3 biotite fabrics (indicated by arrows); pen is 14 cm long. Farm Dagbreek 365.

(H) Calc-silicate concretion in psammitic schist illustrating the crystallization of first generation amphiboles parallel to the S_2 fabric (parallel to long edge of photograph). The second amphibole generation overgrows fabrics discordantly (basal part of the concretion) constraining the syn- D_2 to post- D_3 growth of amphiboles during formation of the calc-silicate lithologies. Farm Kaan 309.



Graphite is a major constituent of the graphite schists which occur mostly in thin units (<10 m) at various points through the traverse. The amount of graphite ranges from about 20% to 80% of the total rock volume.

Accessory minerals in all pelitic rocks are tourmaline, zircon, apatite and opaques.

6.2.2 Calcareous lithologies

The constituents of the calc-silicates throughout the traverse are quartz, plagioclase, calcite, common and green amphibole, biotite, muscovite, chlorite, garnet, scapolite, epidote, clinozoisite and sphene. Minor amounts of diopside, apatite, tourmaline, rutile and opaques are also present. The calc-silicate layers and spindles (Chapter 3.5.5) are frequently zoned with light cores containing mainly quartz, plagioclase, calcite, garnet and scapolite and with dark rims consisting of amphiboles and epidote but scapolite sometimes occurs at the rims as well.

The timing of calc-silicate formation is best constrained by the amphiboles. The first amphibole generation is strongly aligned parallel to the S_2 cleavage but has also been bent along the spindle walls. This indicates that amphibole growth started syn-kinematically and lasted until post- D_2 . The second amphibole gen-

eration is poikiloblastic and overgrows the original spindle outline as well as the S_3 fabric thus indicating post- D_3 crystallization (Fig. 6.1,H; Table 6.2).

On the farm Kaan 309 a 1 m thick, heavily weathered tremolite schist has been found below the thick graphite schist (Fig. 6.2). The layer consists nearly exclusively of tremolite with only minor amounts (<5%) of quartz and biotite being present.

The 2 m thick marble horizon overlying the Matchless Amphibolite sequence comprises a recrystallized matrix of dolomitic carbonate which is confirmed by X-ray diffraction analysis and staining techniques. Only minor amounts of quartz are present as well as traces of white mica.

6.3 Mineral assemblages

The mineral assemblages encountered along the study traverse are diagnostic for medium-grade metamorphic terrains as classified by Winkler (1979). Assemblage zones have been defined on the basis of Al-silicate phase changes and reaction-isograds. The assemblage zones together with the respective assemblages (a) to (i) are shown in Figure 6.2. Furthermore, mineral assemblages are illustrated in AFM diagrams and their approximate position in the Al-silicate system as delineated by various experimentally determined reaction curves is shown in Figure 6.3.




Fig. 6.2 Map of the study area showing distribution of assemblage zones with respective mineral assemblages (a) to (i), and sample localities.


(a) Assemblage zone 1

Hoffer (1977) has pointed out that a large part of the southern Khomas Trough is characterized by assemblages comprising kyanite, staurolite, biotite and chlorite. The southern boundary of the study traverse, at the confluence of the Kuiseb and Koam rivers, is situated close to Hoffer's (op.cit.) isograd (3) which demarcates the "kyanite-in" reaction. The diagnostic mineral species in assemblage zone 1 of this study are garnet, kyanite, staurolite, muscovite, biotite, chlorite, plagioclase and quartz in the pelitic rocks. From south to north the following mineral assemblages are developed in this zone:

- (a) kyanite + garnet + biotite + plagioclase + quartz, (Fig. 6.3,II; Fig. 6.4,A),
- (b) chlorite + garnet + biotite + muscovite + plagioclase + quartz, (Fig. 6.3,I; Fig. 6.4,B), and
- (c) staurolite + garnet + biotite + plagioclase + quartz (Fig. 6.3,II).

Since assemblages are largely dependent on the respective bulk rock compositions sharp boundaries may not be drawn. Primary matrix chlorite, however, does not occur north of a line indicated in Figure 6.2, a geographical position which has also been sug-


gested by Hoffer (1977). The presence of assemblage (b) and the absence of chloritoid both indicate that chlorite may have formed according to the reaction



given by Spear and Cheney (1989). The formation of staurolite in the absence of chloritoid has been attributed by Hoffer (1977) to the reaction



which has been determined by Hoschek (1969). It is further notable that kyanite has only been observed in the southern part of this assemblage zone. Hoffer (1977) has suggested that kyanite formed according to the reaction



determined by Thompson and Norton (1968).




Fig. 6.3: P-T diagram showing the stability fields and assemblages for the assemblage zones 1 to 4. Upper stability limits of chloritoid + biotite + quartz + H_2O (1) after Spear and Cheney (1989); of chlorite + muscovite (2) after Hoschek (1969); of garnet + muscovite + chlorite (4) after Thompson (1976); of staurolite + muscovite + quartz (6) after Hoschek (1969); and of muscovite + quartz (9) after Chatterjee and Johannes (1974). The melting curve (S) is based on experimental data from the Khomas Trough after Hoffmann (1976) and Winkler (1983). Stability field of Al-silicates after Holdaway (1971).


The final decomposition of prograde chlorite in the centre of the traverse might indicate that conditions were appropriate for the reaction



determined by Thompson (1976).

(b) Assemblage zone 2

This zone has been subdivided into two subzones based on the occurrence of andalusite. Pelites include andalusite from the immediate footwall of the graphite schist on the farm Kaan 309 towards the north but only for about 3 km across strike in subzone 2A (Fig. 6.2). The critical assemblage found in subzone 2A is



Hoffer (1977) has argued that andalusite might have formed according to reaction (3), substituting kyanite, but under reduced pressures. Since staurolite decomposition (according to reaction (6)) has only been observed more than 20 km north of the andalusite zone, the reaction



after Carmichael (1970) is suggested for the formation of andalusite in the presence of staurolite.

Within subzone 2B no Al-silicate has been found and the characteristic assemblage occurring for about 10 km across strike up to assemblage zone 3 is

(e) staurolite + garnet + biotite + muscovite + plagioclase + quartz (Fig. 6.4,D).

(c) Assemblage zone 3

This zone is about 20 km wide and its southern boundary delimits the first occurrence of sillimanite. Assemblages include

(f) sillimanite + staurolite + garnet + muscovite + biotite + plagioclase + quartz (Fig. 6.3,IV; 6.4,E), and


(g) sillimanite + staurolite + biotite + plagioclase + quartz (Fig. 6.3,IV).

Also the assemblage (c) occurs within this zone.

Towards the north, staurolite decreases in abundance whilst sillimanite increases. Hoffer (1977) ascribed the sillimanite-formation to the reaction



experimentally determined by Hoschek (1969). Staurolite decomposition, however, has only been observed further north in assemblage zone 4. Since garnet occurs in assemblage with sillimanite and staurolite, also the reaction



after Guidotti (1970) might have formed. The occurrence of staurolite + sillimanite + biotite together over this wide zone is explained by Hoffer (1977) as being due to changing Fe and Mg contents of the pelites with increasing metamorphic grade.

(d) Assemblage zone 4

The last occurrence of staurolite is about 5 km south of the Donkerhoek Granite and the pelites show the assemblage



in this area (Fig. 6.3,V; Fig. 6.4,F). Textures show an intergrowth of fibrolite with biotite which confirms that ideal conditions were reached for the formation of the critical assemblage sillimanite + biotite according to reaction (6) in this area.

Fig. 6.4: Mineral assemblages.

(A) Photomicrograph (plane light) showing mineral assemblage (a) kyanite + garnet + biotite + plagioclase + quartz of the southernmost Khomas Trough (pelite specimen PK 86/86, farm Usambara 304).

(B) Photomicrograph (plane light) showing mineral assemblage (b) garnet III + chlorite (matrix) + biotite + plagioclase + quartz in assemblage zone 1 (pelite specimen PK 86/86, farm Usambara 304).

(C) Photomicrograph (cross polars) showing mineral assemblage (d) garnet + andalusite (strongly muscovitized) + biotite + plagioclase + quartz in pelitic schist in assemblage zone 2A (pelite specimen PK 278, farm Kaan 309).


(D) Photomicrograph (plane light) showing mineral assemblage (e) staurolite + garnet + biotite + plagioclase + quartz in assemblage zone 2B (pelite specimen PK 293, farm Kaan 309).

(E) Photomicrograph (plane light) showing mineral assemblage sillimanite + staurolite + garnet in assemblage zone 3 (pelite specimen PK 308, farm Dagbreek 365).

(F) Photomicrograph (plane light) showing fibrolite knot within the S_3 biotite fabric in association with biotite, plagioclase and quartz in the northern Khomas Trough (mineral assemblage (h), assemblage zone 4, pelite specimen PK 815, farm Keises 312).

(G) Kuiseb Formation migmatites at the northern margin of the study traverse. Hammer for scale (circled), Davetsaub river, farm Davetsaub 29.

(H) Photomicrograph (cross polars) of pelite in the immediate vicinity of the Donkerhoek Granite in the Kaan river showing mineral assemblage (i) muscovite + biotite + microcline + plagioclase + quartz in assemblage zone 4 (specimen PK 344, farm Noma-tsaus 28).



The highest metamorphic conditions are evident at the northern margin of the Khomas Trough where partial migmatization occurred (Fig. 6.4,G). Pelites in this area contain the assemblage

- (i) muscovite + biotite + K-feldspar (microcline) + plagioclase + quartz

(Plate 6.4,H) which indicates the formation of melt according to the reaction

- (8) muscovite + K-feldspar + albite + quartz + H_2O = melt;

determined by Thompson and Algor (1977).

In conclusion, the microscopic investigation confirms, to a large extent, the position of the metamorphic isograds proposed by Hoffer (1977) for the Khomas Trough. Pronounced features of the central and northern part of the traverse are characteristic changes from a narrow andalusite zone to a wide sillimanite zone, the decomposition of staurolite and finally partial melting. In the south, however, mineral phase changes are much more indistinct with specific mineral assemblages occurring over wide areas.

6.4 Mineral compositions

Within the framework of this study, mineral analyses were undertaken to confirm and support indirect P-T estimates which have

been derived from mineral assemblages. Of additional interest was the chemical composition of the scapolites in the northern part of the traverse. With regard to these aims six pelites from different assemblage zones were chosen. Sample numbers mark the locations shown in Figure 6.2, modal compositions are listed in Table 6.1 and analytical conditions and data may be found in Appendix III.

Plagioclases are mostly sericitized and untwinned. Four samples have been measured which did not show any significant degree of zonation. The plagioclases are generally oligoclases with An_{15} to An_{24} (Appendix II, A2).

The chemical analyses of white micas confirm that the bulk is close to end member muscovites "sensu stricto" (Appendix III, B). This is shown by Si cation values of close to 6.00 and by low octahedral cation values in excess of Al. Moderate phengitic white mica is indicated in sample 86/76 (chlorite-garnet schist) which might be due to the presence of chlorite as pointed out by Hoffer (1977). The analyses of different muscovite generations such as matrix muscovite (samples 146, 86/76), porphyroblastic muscovites (samples 146, 274, 109) and late muscovites which replace Al-silicates (sample 1) and staurolite have shown no significant differences in chemical compositions.

Biotite analyses of all six samples also show no significant variations in compositions between both fabric biotites and late porphyroblastic biotites. This is demonstrated in Appendix III, C with sample 146-1 representing matrix biotites and with sample 146-2 in which porphyroblastic biotites have been analysed. There is also no systematic change of Mg-contents of biotite with increasing metamorphic grade towards the north as has been observed by Hoffer (1977). However, Ti and Mn increase slightly towards the north. Sample 306 is from the scapolite schist sequence on the farm Dagbreek and shows a very different composition of biotites compared with other samples. These biotites are enclosed within the scapolite poikiloblasts.

Garnet III has been analysed from assemblage zones 1, 2 and 3 (Appendix III, D) and garnet II additionally in assemblage zone 1 (sample 146). Calculations based on 24 oxygens show good results of 6:4/4:6. In all samples almandine garnet forms the most frequent end member of the garnet series with more than 60 mol-%. It is followed by spessartine and pyrope. Grossular and andradite components vary considerably. With the exception of sample 274 all garnets are distinctly zoned with Ca- and Mn-rich cores and Fe- and Mg-rich rims, zonations which are common in pelites of many metamorphic terrains.

Prograde chlorite has been analysed in a garnet-chlorite schist (sample 86/76; Appendix III,E). The chlorites are SiO_2 poor and the X_{Mg} of 0.58 is below the value of 0.63 which Hoffer (1977) considered to be the lower limit within his "medium-grade" assemblage zone 3.

In view of indirect P-T estimates staurolite has been analysed in sample 308 to compare the composition with staurolites used for experimental studies by Hoschek (1969). The staurolite in this sample occurs in contact paragenesis with garnet and sillimanite and does not show any muscovite replacement. Ratios of $\text{Mg}/\text{Mg}+\text{Fe}$ are 0.17 (Appendix III,E) which is identical to those staurolites used by Hoschek (1969).

Scapolites have been analysed from the southern scapolite-schist sequence on the farm Dagbreek (Appendix III,E). Compositions are uniformly mizzonitic with a mejonite percentage of about 64% and equivalent anorthite of about 59 (Fig. 6.5; Appendix III,E). Chlorine contents of about 0.61 wt% are characteristic for scapolites of mizzonitic compositions (Fig. 6.5; Evans et al., 1969; Shaw, 1960). Employing the stoichiometry scheme of Evans et al. (1969) a general formula of $\text{Na}_{1.5}\text{Ca}_{2.5}\text{Al}_{4.6}\text{Si}_{7.4}\text{O}_{24}\text{Cl}_{0.2}(\text{CO}_3)_{0.8}$ (Na includes K, Ca includes Sr, and CO_3 includes SO_4) is suggested by the analytical results.




Fig. 6.5: Compositions of scapolite from the southern scapolite schist sequence on the farm Dagbreek 365 (sample 306, Fig. 6.2). The solid line represents the solid solution between marialite (MAR) and mizzonite (MIZZ) as suggested by Evans et al. (1969). Cl-atoms per unit cell are a function of %EqAn for natural scapolites; (MEI=meijonite).

6.5 The P-T evolution of metamorphism

6.5.1 Qualitative estimation of P-T conditions

Mineral assemblages and reaction-isograds allow some P-T estimations using experimentally determined reaction curves which are compiled in Figure 6.3. Judging from these reactions (and provided $P_{H_2O} = P_{tot}$) the relevant P-T fields for the four assemblage zones are shown in this figure. The Al-silicate triple point of

Holdaway (1971) has been employed because it fits best the evidence obtained from petrographic data and mineral analyses (see below).

The P-T field of assemblages in the southern Khomas Trough are framed by the equilibrium curve (1), by curve (2) which was experimentally determined at $540 \pm 15^\circ\text{C}$ at 4 kbar and $565 \pm 15^\circ\text{C}$ at 7 kbar water vapor pressure by Hoschek (1969), and by curve (4) determined by Thompson (1976) at $580^\circ\text{--}590^\circ$ at 3-6 kbar. The last occurrence of primary chlorite several kilometres south of the andalusite zone indicates that P-T conditions in this area are close to reaction curve (4). The resulting P-T conditions for the south, as determined by assemblages and the latter equilibrium curves within the kyanite field, are a temperature range of about $540\text{--}590^\circ\text{C}$ at water vapor pressures from 4.5 to about 9 kbars.


Conditions in the andalusite field are determined by: (i) reaction (4); (ii) the andalusite-sillimanite equilibrium curve; and (iii) reaction (6). Equilibrium curve (6) has been experimentally determined by Hoschek (1969) at $575 \pm 15^\circ\text{C}$ at 2 kbar and $675 \pm 15^\circ\text{C}$ at 5.5 kbar water vapor pressure (using a biotite with $\text{Mg}/\text{Mg}+\text{Fe} = 0.48$ and a staurolite with $\text{Mg}/\text{Mg}+\text{Fe} = 0.17$). A possible temperature range of $500\text{--}590^\circ\text{C}$ is given by curves (4) and (6), and by the intersection of curve (6) with the andalusite - sillimanite equilibrium curve. A pressure range of $<1\text{--}2.8$ kbar is

provided by the lower pressure limits of curves (4) and (6) and by the intersection of curve of (4) with the andalusite - sillimanite equilibrium curve (Fig. 6.3).

Assemblage zone 3 shows the widest possible P-T range with 550-650°C given by the intersection of curve (4) with the andalusite-sillimanite equilibrium curve, and of curve (6) with the granite solidus. A pressure range of about 2.4-6 kbar is given by the intersections of curve (6) with the andalusite - sillimanite equilibrium curve, and of the granite solidus with the kyanite-sillimanite equilibrium curve.

Further evidence for temperature conditions close to the southern boundary of zone 3 comes from scapolite stabilities (Fig. 6.6). The mineralogic composition of the scapolite indicates a minimum formation temperature of about 470°C and a maximum of about 650°C according to studies of Oterdoom and Wenk (1983). In comparison with cogenetic silicate phases it is more likely, however, that the scapolite formed above the minimum temperature of 550°C for CO₃-scapolite as indicated in Figure 6.6.

Constraints on the P-T conditions of assemblage zone 4 are provided from reaction curve (6) and from reaction



determined by Chatterjee and Johannes (1974).





Fig. 6.6: Diagram showing isobaric temperature - composition relations between scapolite, plagioclase and calcite as well as stability conditions for stable CO_3 - and Cl,CO_3 -scapolite (after Oterdoom and Wenk, 1983). The possible temperature range for the formation of mizzonitic scapolite in the Khomas Trough according to this diagram is demarcated by hatched and solid black areas. The most likely temperature range for the investigated samples is shown in solid black (for details see text).

Furthermore, melting experiments in Kuiseb schists, migmatites and granites in the vicinity of the study area were undertaken by Hoffmann (1976) and Winkler (1983). The experiments show initial

melting of Kuiseb pelites at 660-670°C at 4 kbar, of migmatites at 667°C-683°C at 4 kbar and of granite at 663°C at 4 kbar. Winkler (1983) obtained a granite solidus at 640-646°C at 5 kbar. These results are manifest in the solidus curve S in Figure 5.3 which demarcates a similar slope but at about 25°C higher to the solidus curve of Thompson and Algor (1977). The P-T conditions of the northern traverse are well constrained with experimental data providing a temperature range of 590-670°C and a pressure range of 2-4.5 kbar (Fig. 6.3). Further evidence for the pressure conditions at the northern margin comes from primary muscovite in the Donkerhoek Granite which indicates a lower pressure limit of about 3.5 kbar (experimentally determined by Storre and Karotke, 1971) for the crystallization of the granite.

An outstanding feature of the central and northern Komas Trough is the muscovitization of staurolite, andalusite and sillimanite (Fig. 6.1,B). Carmichael (1969) and Eugster (1970) have ascribed this phenomenon to retrograde alteration dependent on f_{H_2O} , pH, K^+ concentrations, and total pressure and temperature of the metamorphic fluids. These authors have formulated the reaction



to account for the muscovitization. Dependent on the above factors this process may be initiated from above 600°C during the cooling history of the terrain (Eugster, 1970).

6.5.2 Geothermometry and geobarometry

for a direct P estimation four samples were chosen from assemblage zones 1, 2 and 3 (sample localities are shown in Figure 6.2) which allow the application of garnet-biotite- and garnet-chlorite geothermometers as well as of a garnet-biotite-muscovite-plagioclase geobarometer. All phases used for thermobarometry are in contact paragenesis and garnets belong mostly to the late garnet III generation. An exception is sample 146 where also a spiral-shaped garnet II has been measured.

Garnet-biotite geothermometers used are those of Ferry and Spear (1978), Hodges and Spear (1982), Perchuk and Lavrent'Eva (1983), Indares and Martignole (1985), and Hoinkes (1986), taking into account that some of these have been calibrated for specific pressures. The garnet-chlorite geothermometer of Dickenson and Hewitt (1986) has been used for sample 86/76. Pressure estimations for samples 146 and 308 are based on the garnet-biotite-muscovite-plagioclase geobarometer of Ghent and Stout (1981).

The results of the initial P-T estimations are shown in Table 6.3. Temperature ranges result from the analysis of different minerals of the same generation. Figure 6.7 illustrates the inferred P-T conditions comprising reaction curves, mineral analyses of critical assemblages in AFM diagrams as well as X_{Alm} isopleths of garnet-biotite bearing pelites after Spear and Cheney (1989).

The general lack of agreement between the different garnet-biotite geothermometers proposed is confirmed by the data shown in Table 6.3. The experimental calibration of Ferry and Spear's (1978) thermometer is based on pure Fe-Mg solid solutions using Fe/Fe+Mg systems of about 0.9. The calibration of Hodges and Spear (1982) accounts for non-ideal garnet solid solution but only the grossular-pyrope crystalline solution was assumed to behave non-ideally. Perchuk and Lavrent'eva's (1983) experimental calibration uses Fe/Fe+Mg systems of about 0.6. Indares and Martignole (1985) have combined data of Ferry and Spear (1978) and natural biotite-garnet occurrences to derive an empirical thermometer which accounts for diluents such as Ti, Al, Ca and Mn. Hoinkes (1986) has found non-ideal mixing of grossular with almandine-pyrope solid solution in an empirical study.

For the southern Khomas Trough both garnet II and III (sample 146) are zoned and show a range of X_{Alm} from 0.90 (centre) to 0.85 (rim). According to the X_{Alm} isopleths given by Spear and Cheney (1989) this indicates a temperature range of about 550-570°C at pressures of 5-7.6 kbar. Mineral thermometry gave large errors with temperatures of 490-626°C at 6 kbar for garnet II-biotite pairs and of 442-533°C at 6 kbar for garnet III-biotite pairs (Table 6.3). The geobarometer of Ghent and Stout (1981) gives a range of 3.98-6.94 kbar at 550°C for garnet II. Garnet III shows 3.82-6.72 kbar at 550°C.

Table 6.3: Geothermometric and geobarometric data. Sample localities within the respective assemblage zones are shown in Figure 6.2. Modal compositions are given in Table 6.1.

SAMPLE	146	86/76	274	308
Gh&St (550°C): Ga II	3.98-6.94 (kb)			
Ga III	3.87-6.72			
Gh&St (620°C):				2.22-4.24 (kb)
F&S (6 kb): Ga II	490-519 (°C)			
Ga III	442-451		(2 kb): 531-550 (°C)	(4 kb): 601-605 (°C)
H (6 kb): Ga II	588-626			
Ga III	522-533		(2 kb): 579-599	(4 kb): 637-646
I&M (6 kb): Ga II	525-550			
Ga III	470-495		(2 kb): 560-580	(4 kb): 610-627
P&L (6 kb): Ga II	533-550			
Ga III	503-508			
H&S (6 kb): Ga II	490-519			
Ga III	442-451			(4 kb): 601-605
D&H (6 kb):		485-512 (°C)		
$K_D = (Fe/Mg)_{Bz} / (Fe/Mg)_{Ga}$	0.17		0.16	0.18
Abbreviations: Gh&St, Ghent & Stout (1981); F&S, Ferry and Spear (1978); H, Hoinkes (1986); I&M, Indares & Martignole (1985); P&L, Perchuk & Lavrent'eva (1983); H&S, Hodges & Spear (1982); D&H, Dickenson & Hewitt (1986).				

The distribution coefficient (K_D) value of 0.17 and the high X_{Ca} value of 0.12 of sample 146 compares best with the grossular-rich samples used by Hoinkes (1986). The presence of staurolite in this area and its commonly accepted formation temperature of at least 540°C at 4 kbar (Hoschek, 1969) from chlorite + muscovite (Fig. 6.3) further suggest that the data obtained from Hoinkes (1986) record the most accurate estimate of temperatures in this area.

The above thermometric data together with suitable reaction curves for this area suggest a P-T range from about 520° to 570°C at 4-7 kbar (Fig. 6.7).

Sample 86/76 represents a garnet-chlorite schist from an area in assemblage zone 1 where no staurolite has been observed. Geothermometers for this zone give a narrow temperature range of 485-512°C at 6 kbar pressure (Table 6.3).

The thermometric analyses from assemblage zone 2 just south of the first occurrence of sillimanite show a temperature of about 530-600°C at 2 kbar pressure which is support for the employment of the Holdaway Al_2SiO_5 triple point. The equilibrium curve andalusite - sillimanite is intersected at these temperatures at reasonable pressures, a result which is in contrast to the phase diagrams of Richardson et al. (1969) and Althaus (1969) which would hardly allow the formation of sillimanite at these temperatures. The lower Ca contents and the K_D values of garnet in this area compared with samples used by the above authors for thermometric calibrations suggest that the geothermometer of Indares and Martignole (1985) shows the most reliable results with 560-580°C at 2 kbar in this area (Table 6.3).

Thermometric data calculated for assemblage zone 3 garnet-biotite pairs give a narrow range of 600-630°C at 4 kbar, with the exception of Hoinkes' (1986) thermometer. It is conceivable that the

Ca-poor composition ($X_{Ca}=0.03$) of the garnets accounts now for the higher reliability of other thermometers compared to the calibration of Hoinkes (op.cit.) who used garnets with $X_{Ca} > 0.1$. Pressure estimates for this area gave 2.22-4.24 kbar at 620°C. Values of 0.84 for X_{Alm} confirm a P-T range of 590-630°C at 3.8-5.8 kbar respectively (Fig. 6.7).

6.5.3 Summary of the P-T conditions in the Khomas Trough

Previously Hoffer (1977) has interpreted a continuous development of the Al-polymorphs ~~wt~~ in the Khomas Trough from south to north showing decreasing pressure and increasing temperature conditions. This was largely an effect of the phase diagram of Althaus (1969) which permits a continuous P-T path from high-P/low-T to low-P/high-T along a simple prograde path. Additionally, the andalusite and sillimanite isograds are interpreted by Hoffer (1977) to be influenced by the Donkerhoek Granite.

Taking the findings of Hoffer (1977, 1983) into account, Behr et al. (1983) interpret from fluid inclusion data that the southern Khomas Trough has experienced 6-9 kbar at 480-580°C whereas the northern part only has been subjected to 4.5 kbar at 650°C. As a consequence of this, the latter authors show two distinct P-T paths for these areas and explain the difference by a rapid down-warping of the southern Khomas Trough in contrast to the north.

Sawyer (1981) and Preussinger (1990) have studied the metamorphic conditions of Kuiseb schists at the western end of the Khomas Trough in the Gorob mining area which is situated close to the Matchless Amphibolite. Sawyer (op.cit.) has estimated about 600°C at 6-9 kbar for the peak metamorphism in this area and Preussinger (op.cit.) has established 580-630°C at 5.5-6.5 kbar from sillimanite- and kyanite-bearing assemblages. Kasch (1983b) has estimated P-T conditions at the southern margin of the Khomas Trough, east of the study traverse. He obtained about 600°C at 9 kbar for a first metamorphic event (M1) and about 600°C at 7-8 kbar for a second event M2.

An interesting issue is the discussion of the peak conditions of regional or thermal metamorphism in the Khomas Trough. The migmatites which partially occur close to the Donkerhoek Granite as well as the sillimanite and andalusite isograds have been interpreted by several authors to represent a thermal aureole of the granite (e.g. Nieberding, 1976; Jacob, 1974; Hoffer, 1977). Smith (1965) and Faupel (1974) present arguments disfavouring a large thermal aureole on the basis of similar solidus temperatures for schists and granite.

The principal calculations of Jaeger (1957) on other granitic bodies have, however, shown the unlikelihood of a vast medium- to high-grade thermal aureole around a granitic pluton of 700 °C which intrudes a country rock of about the same temperature at a depth corresponding to 4 kbar. This study has presented struc-

tural evidence indicating that the migmatites occurring in the Davetsaub river profile are crosscut by granite apophyses (see Chapter 4). Furthermore, coarsely recrystallized grain sizes only occur up to about 1 km south of the granite and K-feldspar has formed in the schists only at the immediate contact in the Kaan river section. Migmatites on the other hand occur in well defined zones extending for several kilometres south of the granite-schist contact. Partly bent fibrolite knots within the S_2 cleavage domains and the possible formation of fibrolite syn- to post- D_3 according to reaction (6) also indicate that Al-silicates have formed prior to the intrusion.

In conclusion, the petrographic data and mineral analyses presented in this study indicate that the Kuiseb schists exposed along the study traverse do not show a coherent isograd pattern from low-grade in the south to high-grade in the north as postulated by Hoffer (1977). The metamorphic history of the Khomas Trough is therefore not easily explained by a single, prograde P-T evolution which was influenced in the centre and north by a post-tectonic granite intrusion.

The mineral analyses, obtained from widespread post- D_3 mineral phases, reveal a temperature variation of about 500-660°C from south to north but pressures vary considerably in the respective assemblage zones. Maximum conditions of 7 kbar at 570°C are indicated in assemblage zone 1 which is in good agreement with the studies cited above. In contrast to this only about 2 kbar at

570°C are recorded in the andalusite zone and, further north, pressures reach about 4 kbar at a maximum temperature of 660°C in the sillimanite zone. These pressures and temperatures correspond to geothermal gradients of about 20°C/km, 80°C/km and 45°C/km respectively (taking $P_{H_2O} = P_{lithostatic}$, and a mean rock density of 2.80 g/cm). An earlier syn-D₂ phase of mineral growth which is evident from some preserved garnets and staurolites suggests slightly elevated temperatures for garnet II compared with garnet III at about the same pressures. Peak metamorphic conditions in the northern Khomas Trough have led partially to the formation of migmatites which were subsequently intruded by the Donkerhoek Granite. Throughout the Khomas Trough late muscovites, biotites and amphiboles are evidence for elevated temperatures in a largely stress-free environment after the D₄ deformation and after the peak of metamorphism. Also at this late stage muscovitization of Al-silicates and staurolite occurred.

7. TECTONICS AND SEDIMENTATION OF A LATE PROTEROZOIC CONVERGENT CONTINENTAL MARGIN

7.1 Previous geodynamic models for the evolution of the inland branch of the Damara Orogen

Previous discussions on the geodynamic evolution of the inland branch of the Damara Orogen have concentrated mainly on whether or not oceanic crust had formed prior to subsequent subduction during continental convergence. Martin and Porada (1977) and later Porada (1983) propose an aulacogen model which initiates the development of the Damara Orogen with three symmetrical rift grabens induced by the cooling of an asthenolith. They suggest that this was followed by a downwarping stage and a final post-geosynclinal stage. The delamination model of Kröner (1982) is similar to the latter involving initial crustal stretching over a mantle plume situated underneath the Khomas Trough and leading to the extrusion of the Matchless Amphibolite. Further processes in this model involve lithospheric delamination, continental subduction, crustal underthrusting and high-level thrusting.

An ocean floor subduction model on the other hand, involving the subduction of a several thousand kilometres wide ocean, was constructed by Hartnady (1978), Kasch (1979) and Barnes and Sawyer (1980). The subduction of a narrow, Red Sea type ocean has been suggested by Miller (1983b) who interprets the Matchless Amphibolite as a remnant of a spreading centre which was covered

by clastic sediments. A small ocean basin model associated with strike-slip shear movements was proposed by Downing and Coward (1981) and Coward (1983). This involves the formation of pull-apart basins which are partly floored by oceanic crust in the inland branch, the oblique subduction of these basins and the late-stage movement of the Congo Craton towards the south-east. Bretkopf and Maiden (1987) have proposed a limited ocean basin model involving the fault-related development of subbasins in the Khomas Trough on both continental and oceanic crust. Blaine (1977) summarizes his structural investigations in the eastern Khomas Trough suggesting a possible fore-arc basin on the basis of contrasting tectonic styles with the Central Zone. This was partly supported by Miller et al. (1983), who argued on the basis of a geochemical maturity index that the Khomas Trough north of the Matchless Amphibolite contains fore-arc basin deposits and older spreading-phase deposits towards the south. Downing and Coward (1981) and Hoffmann (1983) speculated upon an accretionary prism setting for the Khomas Trough.

The pronounced sedimentological and structural asymmetries within the inland branch of the orogen have recently led Henry et al. (1990) to relate the early rifting phase to the development of two low-angle detachment systems. This ultimately resulted in the evolution of the Khomas Sea between the Kalahari and Congo Cratons.

7.2 The tectono-sedimentary evolution of the Khomas Trough

The Damara Orogen is part of the Pan-African mobile belt system and connects with the Zambezi and Mozambique Belts in Central Africa. Irrespective of which of the above geotectonic models is applied, the Khomas Trough represents a crucial area in interpreting the tectonics of the Late Proterozoic in Namibia. In previous chapters this thesis has investigated the structural, sedimentological, and metamorphic evolution as well as geochemical aspects of the Kuiseb Formation in the Khomas Trough. The synthesis of conclusions drawn from each of these aspects helps to discriminate between the various interpretations given above for the evolution of the inland branch of the Damara Orogen. Consequently the information gathered in this study is combined in a model which involves the convergence and collision of the Kalahari and Congo Cratons following a rifting and spreading phase. The model proposes that an accretionary prism, here named Khomas Hochland accretionary prism, of Late Proterozoic age developed in the Khomas Trough.

7.2.1 Rifting and spreading phase

The evolution of the Khomas Trough commenced with an initial rift system (Miller, 1983b) which probably developed from a north-west dipping detachment fault as suggested by Henry et al. (1990). Thick volcanic sequences of the Naauwpoort Formation in the northern Damara Orogen have been interpreted by Miller (1983b) to

represent the initiation of large-scale rifting in the inland branch at about 750 ± 65 Ma (U/Pb zircon data). There is no direct record of rift-related volcanic rocks or sediments in the Khomas Trough. Miller (1983b) however has reported very minor acid volcanic rocks of Nosib Group age occurring along the Okavango Lineament. Advanced rifting led to crustal thinning and the development of an oceanic spreading centre in the Khomas Sea. This generation of oceanic crust is confirmed by tholeiitic, mid-ocean ridge type metabasalts and pillow lavas of the Matchless Amphibolite. Breccias, metagabbros and ultramafic lithologies also occur within the oceanic sequence. The metabasic rocks are associated with pelagic and hemi-pelagic deep-sea lithologies such as pelitic schists and graphite schists but also with turbiditic greywackes. Massive sulphide ore deposits in the vicinity of the Matchless Amphibolite have formed as part of the hydrothermal system during spreading (Killick, 1983). A notable marble unit is likely to have originated by carbonate precipitation, probably induced by the hydrothermal convection cells along the spreading ridge. Stable isotope signatures of associated graphite schists, however, confirm that these are organic pelagic sediments. The intercalation of spreading ridge basalts and ore deposits with turbiditic and pelagic sediments has implications for the size of the Khomas Sea and the position of the mid-ocean ridge relative to the continental margin (see below). The amount of tectonic shortening calculated indicates that the basin has had a width of hundreds of kilometres minimum at the climax of spreading.

represent the initiation of large-scale rifting in the inland branch at about 750 ± 65 Ma (U/Pb zircon dates). There is no direct record of rift-related volcanic rocks or sediments in the Khomas Trough. Miller (1983b) however has reported very minor acid volcanic rocks of Nosib Group age occurring along the Okavango Lineament. Advanced rifting led to crustal thinning and the development of an oceanic spreading centre in the Khomas Sea. This generation of oceanic crust is confirmed by tholeiitic, mid-ocean ridge type metabasalts and pillow lavas of the Matchless Amphibolite. Breccias, metagabbros and ultramafic lithologies also occur within the oceanic sequence. The metabasic rocks are associated with pelagic and hemi-pelagic deep-sea lithologies such as pelitic schists and graphite schists but also with turbiditic greywackes. Massive sulphide ore deposits in the vicinity of the Matchless Amphibolite have formed as part of the hydrothermal system during spreading (Killick, 1983). A notable marble unit is likely to have originated by carbonate precipitation, probably induced by the hydrothermal convection cells along the spreading ridge. Stable isotope signatures of associated graphite schists, however, confirm that these are organic pelagic sediments. The intercalation of spreading ridge basalts and ore deposits with turbiditic and pelagic sediments has implications for the size of the Khomas Sea and the position of the mid-ocean ridge relative to the continental margin (see below). The amount of tectonic shortening calculated indicates that the basin has had a width of hundreds of kilometres minimum at the climax of spreading.

7.2.2 Early subduction phase

The next phase in the evolution was characterized by convergence and subduction of Khomas Sea oceanic crust beneath the Congo Craton. The palaeoenvironmental setting during the early stage of convergence is shown in Figure 7.1. Early structural vergences to the south-east confirm that subduction of the ocean and movement of the Kalahari Craton was down to the north-west. Subduction was probably initiated by extensive sediment loading along the Congo cratonic margin in a manner similar to that described by Cloetingh et al. (1982) for small ocean basins. The Kuiseb schists which are partly intercalated with Tinkas-Formation carbonate turbidites in the vicinity of the Okahandja Lineament (Porada and Wittig, 1983) may be regarded as remnants of these early clastic sediments entering the northern Khomas Sea. An oceanic trench developed consequently along the southern margin of the Congo Craton. Original sedimentary structures, turbidite facies, cyclic sedimentation and lateral extent of sedimentary marker units within the Khomas Trough indicate that the sedimentary precursors of the Kuiseb schists accumulated as turbidites on an elongate submarine fan. Palaeocurrents and lateral correlation suggest that it developed as a south-westward prograding elongate trench fan which incorporated large amounts of clastic sediments (Fig. 7.1). This indicates together with the relative uniformity of grain sizes (i.e. no conglomeratic material) that the main source area was situated a considerable distance to the north-east of the area of deposition. It is also conceivable that a volcanic arc north of the subduction zone has additionally con-

tributed towards the trench fill (Fig. 7.1). In any case geochemical signatures such as high contents of certain immobile elements suggest an active continental margin source for the precursor of the Kuiseb schists. Some of the metamorphosed carbonate-rich rocks (calc-silicates) in the Khomas Trough are associated with terrigenoclastic turbidites and have also been deposited by mass-flow processes.




Fig. 7.1: Depositional palaeoenvironments in the southern Damara Orogen during early continental convergence. The elongate trench fan transports large amounts of clastic sediment from a north-easterly source area along the trench axis. Pelagic and hemipelagic sedimentation dominates the basin plain. Ceasing carbonate sedimentation (platform carbonates and carbonate turbidites) characterizes the northern shelf and slope. Clastic deposition occurs on the southern cratonic shelf.

In large parts of the basin pelagic sediments accumulated and the intercalation of submarine fan lithologies and pelagic and hemi-pelagic sediments in the Khomas Trough confirms that these depositional processes were contemporaneous within the basin.

Adjacent to the Khomas Sea in the north at this early stage of subduction platform carbonates were still developed (Karibib Formation) as shown by the calcareous slope turbidites which were sedimented (Tinkas Formation; Fig. 7.1). These deposits were, however, soon to be totally replaced by immature terrigenous sediments of the Kuiseb Formation in the Central Zone. At the same time clastic terrigenous platform sediments were deposited on the southern passive continental margin of the Kalahari Craton.

7.2.3 Accretion phase

The further geotectonic development of the active continental margin is explained by accretion of the trench sediments against the Congo cratonic margin. This model is represented in Figure 7.2 which shows the Khomas Hochland accretionary prism evolving through the offscraping of submarine fan lithologies from the descending oceanic slab. The dominance of metasediments compared with basalts within the present-day Khomas Trough also confirms high sediment input into the oceanic trench. Clastic sediments were therefore preferentially accreted whereas oceanic basalts and pelagics were mostly subducted, similar to the mechanism suggested by Thornburg and Kulm (1987) from the Peru - Chile

Trench. It is thought that a continued high sediment input into the trench caused and maintained a shallow slab inclination as described by Karig et al. (1976) from recent subduction zones. This setting may have also included a narrow arc - trench gap and it may have inhibited the formation of a major fore-arc basin as described by Dickinson and Seely (1979) and Cross and Pilger (1982) from the Peru - Chile Trench.

ACCRETION PHASE : ANDEAN-TYPE MARGIN




Fig. 7.2: Tectonic setting of the southern Damara Orogen during late convergence of the Congo and Kalahari Cratons. The oceanic trench contains the elongate submarine fan and the accretionary prism evolves through the offscraping of sediment from the descending slab. Early (D_1) folding and thrusting occurs within the prism.

One possible explanation for the emplacement of the oceanic sequence represented by the Matchless Amphibolite is that it has been incorporated into the prism during the late stages of the accretionary processes by offscraping from an oceanic crustal high such as the mid-ocean ridge, an aseismic ridge or an oceanic plateau.

During accretion, early isoclinal folding, associated with cleavage formation and thrusting, occurred within the accretionary prism. These features are represented by the relict structures preserved from the D_1 phase of deformation in the Khomas Trough. Such early compressional stresses are also characteristic for low-angle subduction zones associated with young, buoyant oceanic lithosphere (Cross and Pilger, 1982; Park, 1988). Similarly early deformations involving thrusting and folding have been reported from modern accretionary prisms at the Aleutian Trench (Lewis et al., 1988) and at the Mariana and Yap Trenches off Japan (Kimura et al., 1989).

The backstop of the accretionary prism was located at the southern margin of the Congo Craton and it is suggested that this structure was the initial expression of the Okahandja Lineament (Fig. 7.2).

It has been objected previously that no obvious magmatic arc was associated with the proposed subduction zone. Miller (1983b) and Brandt (1987), however, record small amounts of pre-, syn-, and post-tectonic alkaline and calc-alkaline granites, diorites and metagabbros. The pre- and syn-tectonic magmatic rocks especially

have I-type character, shown by low initial $^{87}\text{Sr}/^{86}\text{Sr}$ ratios and by the presence of hornblende and sphene. The majority of these intrusions occurs in the southern Central Zone within 30 km of the Okahandja Lineament (Miller, 1983b).

The palaeoenvironmental setting during the later stages of subduction is illustrated in Figure 7.3. To the north of the Khomas Sea, a magmatic arc is shown situated close to the trench. The shelf area on the Congo Craton became unstable during continued accretion and the carbonates were superseded by clastic terrigenous sediments (Kuseb Formation; Badenhorst, 1987). It may therefore be speculated that the Central Zone developed as a back-arc basin at this stage (Fig. 7.3). The southern terrigenous platform of the Kalahari Craton maintained its stability with local fan sedimentation occurring (Porada and Wittig, 1983).

One aspect which has repeatedly been addressed with regard to the Khomas Trough is the question of preservation of both spreading- and subduction-phase sediments, their distribution and the nature of their contact (Miller, 1983a). Judging from the data presented in this study, the southern Khomas Trough may be regarded as the most likely position in which spreading-phase sediments may have been preserved. Largely basin plain and minor submarine fan associations may be found in the Matchless Amphibolite oceanic sequence and south thereof (Fig. 3.18). These deposits contrast with the thick trench fan associations in the central and northern Khomas Trough. With regard to the deformational patterns described previously a possible contact between these different depositional systems is most likely of tectonic origin.




Fig. 7.3: Palaeoenvironmental setting during late continental convergence. High sediment input into the trench maintain shallow subduction and a narrow arc - trench gap. Terrigenous-clastic sedimentation occurs on both adjacent shelves at this stage.

7.2.4 Collision phase

Post-D₁ deformation patterns in the Khomas Trough give evidence of the onset of major compressive stresses in the lithosphere. This is attributed to the next step in the geotectonic evolution which saw collisional processes between the two cratons (Fig. 7.4).


COLLISION PHASE

Fig. 7.4: Collision between the Congo and Kalahari Cratons. This was accompanied by strong south-east vergent folding and thrusting, late-tectonic metamorphism, and emplacement of the accretionary prism including the Matchless Amphibolite onto the Kalahari Cratonic Foreland. The post-tectonic Donkerhoek Granite intruded partially along the Okahandja Lineament.

Until this stage the accretionary prism had developed to considerable size. Initial collision led to the regional D₂ deformation in the Khomas Trough producing metre- to kilometre-scale isoclinal to open folds and a penetrative, axial planar metamorphic banding cleavage. Fold axes trend horizontally to subhorizontally to the north-east and structural vergences are

consistently to the south-east, indicating tectonic transport in this direction. Folds of the D_1 phase were refolded to develop D_2 downward-facing folds in restricted parts of the sequence. Also associated with this deformation was a major phase of thrusting.

The continuation of collision resulted in the D_3 deformation. This was characterized by a spaced cleavage and tight to isoclinal metre-scale F_3 folds both of which have preferentially developed in high-strain shear and thrust zones. The style and scale of folding and the subhorizontal to moderately plunging attitude of fold axes confirm the major role of simple shear processes during this deformation. In two of the thrust zones in the northern Khomas Trough late-tectonic scapolitization occurred, probably indicating the presence and the migration of Na- and Cl-rich fluids. This might confirm results from modern accretionary prisms which show that fluids participate actively during the development of shear zones (Peacock, 1987). The fluids are channelized and preserved in major pelagic horizons in the prism over a considerable time span (Moore, 1989). At this stage of the geotectonic evolution the structures within the accretionary prism manifested a northward steepening thrust pile with an overall imbricate fan geometry. The observed development from metamorphic banding cleavages (S_1 and S_2) which probably originated from pressure solution during dewatering processes (Behr et al., 1983) to a shear cleavage (S_3) conforms with theoretical considerations on the dynamics of thick orogenic wedges by Platt (1986).

The second possibility to explain the position of the Matchless Amphibolite occurred at this stage by structural emplacement during obduction of the accretionary prism onto the Kalahari Craton. This explanation is favoured and strengthened by the emplacement of Alpine-type ultramafic bodies close to and south of the Matchless Amphibolite (Fig. 7.4) and by tectonic interleaving of basement slices and ultramafic rocks in the Southern Margin Zone (Barnes, 1982). The latter occur together with a prominent rhyolite unit close to the Schlesien-Amerongen Line (Hartnady, 1978) or Us Pass Lineament (Hoffmann, 1983) along the northern margin of the Southern Margin Zone (Fig. 7.4). This Lineament has been interpreted to represent the continental suture zone (Hartnady, Hoffmann, op.cit.) which can probably be traced into the Mwembeshi shear zone of the Zambezi Belt (Unrug, 1990).

The continental collision and subduction of the Kalahari Craton beneath the Congo Craton resulted in crustal thickening and thermal relaxation. The processes associated with a collision-related, late-tectonic regional metamorphism are reflected in the metasediments and metabasic rocks of the Khomas Trough. Growth of critical metamorphic minerals such as kyanite, sillimanite, andalusite, staurolite, garnet and amphibole started mostly during D_2 and lasted until post- D_3 . Scapolite in the northern Khomas Trough has grown post- D_3 . There are indications, however, that biotite, garnet, kyanite and staurolite have also grown pre- D_2 . Geothermobarometric calculations on post- D_3 and some D_2

mineral assemblages show that P-T conditions within the amphibolite facies rocks vary considerably with about 7 kbar/570°C reached in the southern Khomas Trough, about 2 kbar/570°C in the centre and about 4 kbar/660°C in the north. Partial melting of the metasediments during regional metamorphism at about 660°C has occurred at the northern margin. U/Pb analyses on monazites indicate an age of about 525 Ma for this event which is also interpreted to represent the peak of metamorphism (Kukla, Kramm et al., 1990). The above pressures and temperatures correspond to geothermal gradients of about 20°C/km, 80°C/km, and 45°C/km from south to north and it is conceivable that these heterogeneous gradients are due to post-D₃ differential uplift of the Khomas Trough.

Late stages in the structural evolution comprise the formation of crenulation cleavages as well as kink folds in the southern Khomas Trough. Along the Okahandja Lineament, late dextral strike-slip movements produced a clockwise rotation of D₁ to D₄ structural elements. It is suggested that this opened a path for the ascent of the post-tectonic Donkerhoek Granite at about 505 Ma (U/Pb monazite ages; Kukla, Kramm et al., 1990). The retrograde path of metamorphism involved the growth of muscovite, chlorite and amphibole and textures suggest that this took place in a largely stress-free environment after the D₄ deformation.

The end of the main orogenic movements has been interpreted to be represented by the cooling of biotites below 300°C at about 485 Ma (Rb/Sr and K/Ar whole rock ages; Haack, 1983). Certainly an exception are late alaskite intrusions in the Central Zone with a Rb/Sr whole rock age of 458+/-8 Ma, obtained by Kröner and Hawkesworth (1977).

7.2.5 Ancient and modern analogues

Lithologies, structural styles, sedimentation patterns, time sequence of events and the size of the Khomas Hochland accretionary prism are most reminiscent of the Lower Palaeozoic Southern Upland accretionary prism (e.g. Leggett et al., 1979; Kemp, 1987) in view of: (i) series of imbricate thrust slices steepening towards the backstop (Southern Uplands Fault here compared with the Okavango Lineament); (ii) extreme lateral persistence (>150 km) of stratigraphic marker horizons and thrust slices; (iii) the predominance of lateral trench-fill turbidite sedimentation; (iv) no mélangé deposits are recognized; (v) the scarcity of arc-related magmatic rocks, and (vi) the low to medium pressure metamorphism.

The Chugach terrain in Alaska has been explained as a Cretaceous trench-fill deposit (Nilsen and Zuffa, 1982; Sample and Moore, 1987). Broad similarities with the Khomas Trough exist in terms of: (i) linear extent (2000 km long, 100 km wide); (ii) contained lithologies such as sandstones, siltstones, shales, limestones,

basalts, and ultramafics; (iii) late-phase granite intrusions towards the continental margin; and (iv) structural style comprising coaxial deformation "seawards" and noncoaxial deformation with rotation and strike-slip faulting "landwards".

The time sequence of events during deformation of the Shumagin region of the modern Aleutian Trench (Lewis et al., 1988) can be compared with the Khomas Trough involving successively: (i) early folding and thrust faulting; (ii) thrust faulting; and (iii) strike-slip faulting.

The inferred tectonic setting of the Khomas Sea during subduction is compared with the present situation of the southern Peru - Chile Trench (Cross and Pilger, 1982). There, the Chile Rise spreading centre passes obliquely into the trench which causes an intercalation of turbidite trench sediments with oceanic crust, pelagic sediments and spreading centre hydrothermal deposits, similar to that observed at the Matchless Amphibolite. The subduction of young, hot and buoyant oceanic crust causes shallow slab angles, an effect which is enhanced by high sediment input into the trench. This leads consequently to a narrow arc - trench gap with no major fore-arc basin developed and finally results in a complete cessation of arc magmatism because young lithosphere may be absorbed into the asthenosphere before low-density magma is produced (Cross and Pilger, 1982). This is the case on the South American Plate where arc magmatism has ceased in the area of the subducted Chile Rise (south of 43°S).

These mechanisms would explain the scarcity of arc related magmatism in the Central Zone of the Damara Orogen (see Fig. 7.3) as well as the inferred lack of fore-arc basin deposits.

8. REFERENCES

- Ahrendt, H., Hunziker, J.C. & Weber, K. (1977). Age and degree of metamorphism and time of nappe emplacement along the southern margin of the Damara Orogen/Namibia (SW-Africa). *Geol. Rdsch.*, 67, 719-742.
- Althaus, E. (1969). Das System Al_2O_3 - SiO_2 - H_2O . Experimentelle Untersuchungen und Folgerungen für die Petrogenese der metamorphen Gesteine. *N. Jb. Miner. Abh.*, 111, 74-161.
- Anderson, T.B. (1974). The relationship between kink bands and shear fractures in the experimental deformation of slate. *J. geol. Soc. Lond.*, 130, 367-382.
- Arthur, M.A., Dean, W.E. & Stow, D.A.V. (1984). Models for the deposition of Mesozoic-Cenozoic fine-grained organic-carbon-rich sediment in the deep sea. In: Stow, D.A.V. & Piper, D.J.W., Eds., *Fine-grained sediments: deep-water processes and facies*. Spec. Publ. geol. Soc. Lond., 15, 527-560.
- Badenhorst, F.P. (1987). Lithostratigraphy of the Damara Sequence in the Omaruru area of the northern Central Zone of the Damara Orogen and a proposed correlation across the Omaruru Lineament. *Communs geol. Surv. S.W.Afr./Namibia*, 3, 3-8.
- Baier, B., Berckhemer, H., Gajewski, D., Green, R.W., Grimsel, Ch., Prodehl, C. & Vees, R. (1983). Deep seismic sounding in the area of the Damara Orogen, Namibia, South West Africa, 885-900. In: Martin, H. & Eder, F.W., Eds., *Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia*. Springer-Verlag, Berlin, 945pp.
- Barnes, N.E. & Normark, W.R. (1983/84). Diagnostic parameters for comparing modern submarine fans and ancient turbidite systems. *Geo-Marine Lett.*, 3, Map.
- Barnes, S.-J. (1982). Serpentinities in central South West Africa/Namibia - a reconnaissance study. *Mem. geol. Surv. S.W.Afr./Namibia*, 8, 90pp.
- Barnes, S.-J. & Sawyer, E.W. (1980). An alternative model for the Damara Mobile Belt. Ocean crust subduction and continental convergence. *Precambrian Res.*, 13, 297-336.
- Behr, H.-J., Horn, E.E. & Porada, H. (1983). Fluid Inclusions and Genetic Aspects of the Damara Orogen, 611-654. In: Martin, H. & Eder, F.W., Eds., *Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia*. Springer-Verlag, Berlin, 945pp.
- Berner, R.A. & Honjo, S. (1981). Pelagic sedimentation of aragonite: its geochemical significance. *Science*, 211, 940-942.

- Bhatia, M.R. (1983). Plate tectonics and geochemical composition of sandstones. *J. Geol.*, 91, 611-627.
- Bhatia, M.R. & Crook, K.A.W. (1986). Trace element characteristics of greywackes and tectonic setting discrimination of sedimentary basins. *Contr. Miner. Petrol.*, 92, 181-193.
- Blaine, J.L. (1977). Tectonic evolution of the Waldau Ridge structure and the Okahandja Lineament in part of the Central Damara Orogen, west of Okahandja, South West Africa. *Bull. Precambrian Res. Unit, Univ. Cape Town*, 21, 99pp.
- Blaxland, A., Gohn, E., Haack, U. & Hoffer, E. (1979). Rb/Sr ages of late-tectonic granites in the Damara Orogen, Southwest Africa/Namibia. *N. Jb. Miner. Mh.*, 11, 498-508.
- Bouma, A.H. (1962). Sedimentology of some flysch deposits: a graphic approach to facies interpretation. Elsevier, Amsterdam, 168pp.
- Bouma, A.H., Normark, W.R. & Barnes, N.E., Eds., (1985). Submarine fans and related turbidite systems. Springer-Verlag, New York, 351pp.
- Bowles, F.A., Ruddiman, W.F. & Jahn, W.H. (1978). Acoustic stratigraphy, structure and depositional history of the Nicobar fan, eastern Indian ocean. *Marine Geology*, 26, 269-288.
- Boyer, S.E. & Elliot, D. (1982). Thrust systems. *Bull. Amer. Assoc. Petrol. Geol.*, 66, 1196-1230.
- Brandt, R. (1987). Evolution of the Pan-African granitic rocks of the Damara Orogen, Namibia, 121-125. In: Matheis, G. & Schandelmeyer, H.S., Eds., *Current research in African earthsciences*. Balkema, Rotterdam.
- Breitkopf, J.H. (1986). Iron formations and associated amphibolites in the southern part of the Damara Orogen of South West Africa/Namibia. Ph. D. thesis (unpubl.), Univ. Witwatersrand, Johannesburg, 350pp.
- Breitkopf, J.H. & Maiden, K.J. (1987). Geochemical patterns of metabasites in the southern part of the Damara Orogen, SWA/Namibia: applicability to the recognition of tectonic environment. In: Pharach, T.C., Beckinsale, R.D. & Rickard, D., Eds., *Geochemistry and Mineralization of Proterozoic Suites*, Spec. Publ. geol. Soc. Lond., 33, 355-361.
- Breitkopf, J.H. & Maiden, K.J. (1988). Tectonic setting of the Matchless pyritic copper deposits, Namibia. *Econ. Geol.*, 83, 710-723.

- Brigueu, L., Lancelot, J.P., Valois, J.P. & Walgenwitz, F. (1980). Géochronologie U-Pb et genèse d'un type de minéralisation uranifère: les alaskites de Goanikontes (Namibie) et leur encaissant. Bull. Cent. Rech. Explor.-Prod., Elf-Aquitaine, 4, 759-811.
- Carmichael, D.M. (1969). On the mechanism of prograde metamorphic reactions in quartz-bearing pelitic rocks. Contr. Miner. Petrol., 20, 244-267.
- Carmichael, D.M. (1970). Intersecting isograds in the Whetstone Lake area, Ontario, Petrology, 11, 147-181.
- Carmichael, I., Turner, F. & Verhoogen, J. (1974). Igneous Petrology. McGraw Hill, New York, 739pp.
- Chatterjee, N.D. & Johannes, W. (1974). Thermal stability and standard Thermodynamics Properties of synthetic 2M₁ muscovite, $KAl_2[AlSi_3O_{10}(OH)_2]$. Contr. Miner. Petrol., 48, 89-114.
- Clifford, T.N. (1967). The Damara episode in the Upper Proterozoic - Lower Paleozoic structural history of southern Africa. Spec. Pap. geol. Soc. Amer., 92, 100pp.
- Cloetingh, S.A.P.L., Wortel, M.J.R. & Vlaar, N.J. (1982). Evolution of passive continental margins and initiation of subduction zones. Nature, 297, 139-142.
- Cocker, J.D., Griffin, B.J. & Muehlenbachs, K. (1982). Oxygen and carbon isotope evidence for sea-water-hydrothermal alteration of the Macquarie Island ophiolite. Earth Planet. Sci. Lett., 61, 112-122.
- Condie, K.C. (1982). Plate tectonics and crustal evolution. 2nd ed., Pergamon, New York, 310pp.
- Coney, P.J. (1989). Structural aspects of suspect terranes and accretionary tectonics in western North America. J. Struct. Geol., 11, 107-125.
- Cook, H.E., Field, M.E. & Gardner, J.V. (1982). Characteristics of sediments on modern and ancient continental slopes. In: Scholle, P.A. & Spearing, D., Eds., Sandstone depositional environments. Mem. Amer. Assoc. Petrol. Geol., 31, 329-364.
- Cordani, U.G., Figueiredo, M.C.H., Teixeira, W., Bassal, M.A.S. & Soliani Jr., E. (1990). Geotectonic evolution of the Dom Feliciano Belt in South America. Abstr. Geocongress '90, Geol. Soc. S. Afr., 111.

- Corner, B. (1983). An interpretation of aeromagnetic data covering the western portion of the Damara Orogen in South West Africa/Namibia. Spec. Publ. geol. Soc. S. Afr., 11, 339-354.
- Coumes, F., Delteil, G.H., Ravenne, C. & Cremer, M. (1983). Cap Ferret Deep-Sea Fan. In: Watkins, J.S. & Drake, C.L., Eds., Studies in continental margin geology. Mem. Amer. Assoc. Petrol. Geol., 34, 583-592.
- Coward, M.P. (1983). The tectonic history of the Damara Belt. Spec. Publ. geol. Soc. S. Afr., 11, 409-421.
- Cox, K.G., Bell, J.D. & Pankhurst, R.J. (1979). The interpretation of igneous rocks. Allan and Unwin, London, 450pp.
- Crook, K.A.W. (1974). Lithogenesis and geotectonics: the significance of compositional variations in flysch arenites (greywackes). In: Dott, R.H. & Shaver, R.H., Eds., Modern and Ancient Geosynclinal sedimentation. Spec. Publ. Soc. Econ. Paleont. Miner., 19, 304-310.
- Cross, T.A. & Pilger, R.H. Jr. (1982). Controls on subduction geometry, location of magmatic arcs, and tectonics of arc and back-arc regions. Bull. geol. Soc. Amer., 93, 545-562.
- Davis, E.E., Goodfellow, W.D., Bornhold, B.D., Adshead, J., Blaise, B., Villinger, H. & Le Cheminant, G.M. (1987). Massive sulfides in a sedimented rift valley, northern Juan de Fuca ridge. Earth Planet. Sci. Lett., 82, 49-61.
- De Kock, G.S. (1985). Die geologie van 'n gebied suidoos van Karibib, Suidwes-Afrika/Namibie. Commun. geol. Surv. S.W. Afr./Namibia, 1, 45-55.
- De Kock, W.P. (1934). The Geology of the Western Rehoboth, an explanation of sheet F33-W3. Mem. Dept. Mines, S.W.Afr., 1, 148pp.
- De Waal, S.A. (1966). The Alberta Complex, a metamorphosed layered intrusion north of Nauchas, South West Africa, the surrounding granites and repeated folding in the younger Damara System. D.Sc. thesis (unpubl.), Univ. Pretoria, 207pp.
- Dickenson, M.P. & Hewitt, D.A. (1986). A garnet-chlorite geothermometer. Geol. Soc. Amer. Abstracts with Programs, 18, 584.
- Dickinson, W.R. & Seely, D.R. (1979). Structure and stratigraphy of forearc regions. Bull. Amer. Assoc. Petrol. Geol., 63, 2-31.
- Donath, F.A. (1961). Experimental study of shear failure in anisotropic rocks. Bull. geol. Soc. Amer., 72, 985-990.

- Downing, K.N. (1983). The stratigraphy and palaeoenvironment of the Damara Sequence in the Okavango Lineament area. Spec. Publ. geol. Soc. S. Afr., 11, 37-41.
- Downing, K.N. & Coward, M.P. (1981). The Okavango Lineament and its significance for Damaran tectonics in Namibia. Geol. Rdsch., 70, 972-1000.
- Ellis, D.E. (1978). Stability and phase equilibria of chloride and carbonate bearing scapolites at 750°C at 4.000 bar. Geochim. Cosmochim. Acta, 42, 1271-1281.
- Esquevin, J. & Menendez, R. (1975). Radiodation sur roches du permis Diana. S.N.P.A Rep. for Elf Aquitaine S.W.Afr., Mineral Exploration (unpubl.), 12pp.
- Eugster, H.P. (1970). Thermal and ionic equilibria among muscovite, K-feldspar and aluminosilicate assemblages. Fortschr. Miner., 47, 106-123.
- Evans, B.W., Shaw, D.M. & Haughton, D.R. (1969). Scapolite stoichiometry. Contr. Miner. Petrol., 24, 293-301.
- Faupel, J. (1974). Geologisch-mineralogische Untersuchungen am Donkerhoek-Granit (Karibib-Distrikt, Südwestafrika). Göttinger Arb. Geol. Palaeont., 15, 95pp.
- Faure, G. (1986). Principles of isotope geology. J. Wiley & Sons, New York, 589pp.
- Ferry, J.M. & Spear, F.S. (1978). Experimental calibration of the partitioning of Fe and Mg between biotite and garnet. Contr. Miner. Petrol., 66, 113-117.
- Finnemore, S.H., (1978). The geochemistry and origin of the Matchless amphibolite belt, Windhoek district, South West Africa. Spec. Publ. geol. Soc. S. Afr., 4, 433-477.
- Fluty, M.J. (1964). The description of folds. Proc. Geol. Assoc. Lond., 75, 461-492.
- Floyd, P.A. & Winchester, J.A. (1975). Magma type and tectonic setting discrimination using immobile elements. Earth Planet. Sci. Lett., 27, 211-218.
- Frets, D.C. (1969). Geology and structure of the Huab-Welwitschia area, South West Africa. Bull. Precambrian Res. Unit, Univ. Cape Town, 5, 235pp.
- Garcia, M.O. (1978). Criteria for the identification of ancient volcanic rocks. Earth-Sci. Rev., 14, 147-165.
- Gevers, T.W. (1931). An ancient tillite in South West Africa. Trans. geol. Soc. S. Afr., 34, 1-17.

- Gevers, T.W. (1963). Geology along the northwestern margin of the Khomas Highlands between Otjimbingwe-Karibib and Okahandja, South West Africa. Trans. and Proceed. geol. Soc., S. Afr., 66, 199-258.
- Ghent, E.D. & Stout M.Z. (1981). Geobarometry and geothermometry of plagioclase-biotite-garnet-muscovite assemblages. Contr. Miner. Petrol., 76, 92-97.
- Goldsmith, J.R & Newton, R.C. (1977). Scapolite-plagioclase stability relations at high pressures and temperatures in the system $\text{NaAlSi}_3\text{O}_8$ - $\text{CaAl}_2\text{Si}_2\text{O}_8$ - CaCO_3 - CaSO_4 . Amer. Miner., 62, 1063-1081.
- Gorsline, D.S. (1984). A review of fine-grained sediment origins, transport and deposition. In: Stow, D.A.V. & Piper, D.J.W., Eds., Fine-grained sediments: deep-water processes and facies. Spec. Publ. geol. Soc. Lond., 15, 17-34.
- Graham, S.A. & Bachman, S.B. (1983). Structural controls on submarine-fan geometry and internal architecture: upper La Jolla fan system, offshore Southern California. Bull. Amer. Assoc. Petrol. Geol., 67, 83-96.
- Green, R.W.E. (1983). Seismic refraction observations in the Damara Orogen and flanking craton and their bearing on deep seated processes in the orogen: Spec. Publ. geol. Soc. S. Afr., 11, 355-367.
- Gressly, A. (1838). Observations géologiques sur le Jura Soleurois. Neue Denkschr. Allg. Schweiz. Ges. Naturwiss., 2, 1-112.
- Guidotti, C.V. (1970). The mineralogy and petrology of the transition from the lower to upper sillimanite zone in the Oquossoc Area, Maine. J. Petrol., 11, 277-336.
- Haack, U. (1983). Reconstruction of the cooling history of the Damara Orogen by correlation of radiometric ages with geography and altitude, 873-884. In: Martin, H. & Eder, F.W., Eds., Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia. Springer-Verlag, Berlin, 945pp.
- Haack, U. & Martin, H. (1983). Geochronology of the Damara-Orogen - A Review, 839-846. In: Martin, H. & Eder, F.W., Eds., Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia. Springer Verlag, Berlin, 945pp.
- Hälbich, I.W. (1970). The geology of the western Windhoek and Rehoboth Districts, a stratigraphic-structural analysis of the Damara System. D.Sc. thesis (unpubl.), Univ. Stellenbosch, 199pp.

- Hälbich, I.W. (1977). Structure and tectonics along the southern margin of the Damara mobile belt, South West Africa. *Annale Univ. Stellenbosch, Ser. Al(Geol)*, 2, 149-247.
- Häussinger, H. (in prep.). Geochemische und petrologische Untersuchungen an metasedimentären Nebengesteinen und assoziierten Metabasiten der Sulfiderzvorkommen von Gorob, Damara Orogen, Namibia. Ph.D. thesis (unpubl.), Univ. Würzburg.
- Häussinger, H. & Kukla, P.A. (1990). The interpretation of geochemical data from metaturbidites using the TiO_2/Zr ratio. *Europ. J. Miner.*, 2, Beih. 1, 87.
- Hahn-Weinheimer, P. (1966). Die isotopische Verteilung von Kohlenstoff und Schwefel in Marmor und anderen Metamorphiten. *Geol. Rdsch.*, 55, 197-209.
- Hartmann, O., Hoffer, E. & Haack, U. (1983). Regional metamorphism in the Damara Orogen: interaction of crustal motion and heat transfer. *Spec. Publ. geol. Soc. S. Afr.*, 11, 233-241.
- Hartnady, C.J. (1978). The stratigraphy and structure of the Naukluft nappe complex. 14th and 15th an. Rep. Precambrian Res. Unit, Univ. Cape Town, 163-170.
- Hartnady, C.J., Joubert, P. & Stowe, C. (1985). Proterozoic crustal evolution in southwestern Africa. *Episodes*, 8, 236-244.
- Hawkesworth, C.J., Kramers, K.D. & Miller, R. McG. (1981). Old model Nd ages in Namibian Pan-African rocks. *Nature*, 289, 278-282.
- Hawkesworth, C.J., Gledhill, A.R., Roddick, J.C., R. McG. Miller, & Kröner, A. (1983). Rb/Sr and Ar/Ar Studies bearing on Models for the Thermal Evolution of the Damara Belt, Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 323-339.
- Heath, K.C. & Mullins, H.T. (1984). Open-ocean, off-bank transport of fine-grained carbonate sediment in the Northern Bahamas. In: Stow, D.A.V. & Piper, D.J.W., Eds., *Fine-grained sediments: deep-water processes and facies*. *Spec. Publ. geol. Soc. Lond.*, 15, 199-208.
- Henry, G., Stanistreet, I.G. & Maiden, K.J. (1986). Preliminary results of a sedimentological study of the Chuos Formation in the Central Zone of the Damara Orogen: evidence for mass flow processes and glacial activity. *Communs geol. Surv. S.W.Afr./Namibia*, 2, 75-92.

- Henry, G., Clendenin, C.W., Stanistreet, I.G. & Maiden, K.J. (1990). A multiple detachment model for the early rifting stage of the Late Proterozoic Damara Orogen in Namibia. *Geology*, 18, 67-71.
- Hiscott, R.N. & Middleton, G.V. (1979). Depositional mechanics of thick-bedded sandstones at the base of a submarine slope, Tourelle Formation (Lower Ordovician), Quebec, Canada. *Spec. Publ. Soc. Econ. Paleont. Miner.*, 27, 307-326.
- Hobbs, B.E., Means, W.D. & Williams, P.F. (1976). An outline of structural geology. John Wiley, New York, 571pp.
- Hodges, K.V. & Spear, F.S. (1982). Geothermometry, geobarometry and the Al_2SiO_5 tripple point at Mt. Moosilauke, New Hampshire. *Amer. Miner.*, 67, 1118-1134.
- Hoefs, J. (1980). Stable isotope geochemistry. Springer-Verlag, Berlin, 208pp.
- Hoffer, E. (1977). Petrologische Untersuchungen zur Regionalmetamorphose Al-reicher Metapelite im südlichen Damara-Orogen (Südwest-Afrika). Habilitationsschrift (unpubl.), Univ. Göttingen, 150pp.
- Hoffer, E. (1983). Compositional Variations of Minerals Involved in Low to Medium Grade Isograd Reactions in the Southern Damara Orogen, Namibia, South West Africa, 745-767. In: Martin, H. & Eder, F.W., Eds., *Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia*, Springer Verlag, Berlin, 945pp.
- Hoffmann, C. (1976). Granites and migmatites of the Damara Belt, South West Africa. Petrography and melting experiments. *Geol. Rdsch.*, 65, 939-966.
- Hoffmann, K.H. (1983). Lithostratigraphy and facies of the Swakop Group of the Southern Damara Belt, SWA/Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 43-63.
- Hoffmann, K.H. (1987). Stratigraphic subdivision and sedimentary facies of the Duruchaus Formation in the Geelkop Dome and Nauaspoort-Wortelpoort area north of Rehoboth, southern Damara Belt. *Communs geol. Surv. S.W.Afr./Namibia*, 3, 9-18.
- Hoinkes, G. (1986). Effect of grossular-content in garnet on the partitioning of Fe and Mg between garnet and biotite. *Contr. Miner. Petrol.*, 92, 393-399.
- Holdaway, M.J. (1971). Stability of andalusite and the aluminium silicate phase diagram. *Amer. J. Sci.*, 271, 97-131.

- Hoschek, G. (1969). The stability of staurolite and chloritoid and their significance in metamorphism of pelitic rocks. *Contr. Miner. Petrol.*, 22, 208-232.
- Indares, A. & Martignole, J. (1985). Biotite-garnet geothermometry in the granulite facies: the influence of Ti and Al in biotite. *Amer. Miner.*, 70, 272-278.
- Jacob, R.E. (1974). Geology and metamorphic petrology of part of the Damara Orogen along the lower Swakop river, South West Africa. *Bull. Precambrian Res. Unit, Univ. Cape Town*, 17, 185pp.
- Jaeger, J.C. (1957). The temperature in the neighbourhood of a cooling intrusive sheet. *Amer. J. Sci.*, 255, 306-318.
- Karig, D.E., Caldwell, J.G. & Parmentier, E.M. (1976). Effects of accretion on the geometry of the descending lithosphere. *J. geophys. Res.*, 81, 6281-6291.
- Kasch, K.W. (1975). A preliminary report on the geology of the southern margin of the Damara Orogen around Omitara, South West Africa. 13th an. Rep. *Precambrian Res. Unit, Univ. Cape Town*, 102-138.
- Kasch, K.W. (1979). A continental collision model for the tectono-thermal evolution of the (southern) Damara belt. 16th an. Rep. *Precambrian Res. Unit, Univ. Cape Town*, 101-107.
- Kasch, K.W. (1983a). Continental Collision, Suture Progradation and Thermal Relaxation: A Plate Tectonic Model for the Damara Orogen in Central Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 423-429.
- Kasch, K.W. (1983b). Regional P-T variations in the Damara Orogen with particular reference to early high-pressure metamorphism along the southern margin. *Spec. Publ. geol. Soc. S. Afr.*, 11, 243-253.
- Kasch, K.W. (1983c). Folding and thrust tectonics in the south-eastern portion of the Damara Orogen around Omitara, Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 175-184.
- Kasch, K.W. (1986). Tectonic subdivision, lithostratigraphy and structural geology of the Upper Black Nossob River area. *Communs geol. Surv. S.W.Afr./Namibia*, 2, 117-129.
- Kasch, K.W. (1987). Metamorphism of pelites in the Upper Black Nossob River area of the Damara Orogen. *Communs geol. Surv. S.W.Afr./Namibia*, 3, 63-81.

- Kemp, A.E.S. (1987). Tectonic development of the Southern Belt of the Southern Uplands accretionary complex. *J. geol. Soc. Lond.*, 144, 827-838.
- Killick, A.M. (1983). Sulphide mineralization at Gorob and its genetic relationship to the Matchless Member, Damara Sequence, SWA/Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 381-384.
- Kimura, G., Koga, K. & Fujioka, K. (1989). Deformed soft sediments at the junction between the Mariana and Yap Trenches. *J. Struct. Geol.*, 11, 463-472.
- Klemm, R. & Okrusch, M. (1990). Phase relationships and fluid-inclusion characteristics of the metamorphosed, stratiform sulfide deposit Matchless, Namibia. *Geol. Rdsch.*, 79, 433-449.
- Klemm, R., Maiden K.J. & Okrusch, M. (1987). The Matchless copper deposit SWA/Namibia: A deformed and metamorphosed massive sulfide deposit. *Econ. Geol.*, 82, 163-171.
- Klemm, R., Maiden K.J., Okrusch, M. & Richter, P. (1989). Geochemistry of the metamorphosed massive sulphide deposit Matchless, South West Africa/Namibia: wallrock alteration during submarine ore-forming processes. *Econ. Geol.*, 84, 603-617.
- Kröner, A. (1982). Rb-Sr Geochronology and Tectonic Evolution of the Pan-African Damara Belt of Namibia, Southwestern Africa. *Amer. J. Sci.*, 282, 1471-1507.
- Kröner, A. & Hawkesworth, C. (1977). Late Pan-African emplacement ages for Rössing alaskitic granite (Damara Belt) and Rooi Lapel bostonite (Gariep Belt) in Namibia and their significance for the timing of metamorphic events. 20th an. Rep. Res. Inst. Afr. Geol., Univ. Leeds, 14-17.
- Kukla, C. (in prep.). Geochronological and isotope geochemical studies on the Kuiseb Formation metasediments in the southern Damara Orogen, Central Namibia. Ph.D. thesis (unpubl.), Univ. Würzburg.
- Kukla, C., Kramm, U., Okrusch, M. & Grauert, B. (1990). Isotope studies and their implication for the metamorphic processes in the Kuiseb Formation of the southern Damara Orogen, Namibia: Ext. Abstract, Geocongress '90, *Geol. Soc. S. Afr.*, 305-308.
- Kukla, P.A., Opitz, C., Stanistreet, I.G. & Charlesworth, E.G. (1988). New aspects of the sedimentology and structure of the Kuiseb Formation in the western Khomas Trough, Damara Orogen, SWA/Namibia. *Communs geol. Surv. S.W.Afr./Namibia*, 4, 33-42.

- Kukla, P.A., Charlesworth, E.G., Stanistreet, I.G. & Kukla, C. (1989). Downward-facing structures in the Khomas Trough of the Damara Orogen, Namibia. *Communs geol. Surv. Namibia*, 5, 53-57.
- Kukla, P.A., Kukla, C., Stanistreet, I.G. & Okrusch, M. (1990). Unusual preservation of sedimentary structures in sillimanite-bearing metaturbidites of the Damara Orogen, Namibia. *J. Geol.*, 98, 91-99.
- Land, L.S. (1980). The isotopic and trace element geochemistry of dolomite: the state of the art. *Spec. Publ. Soc. Econ. Paleont. Miner.*, 28, 87-110.
- Lash, G.G. (1986). Sedimentology of channelized turbidite deposits in an ancient (early Palaeozoic) subduction complex, central Appalachians. *Bull. geol. Soc. Amer.*, 97, 703-710.
- Leggett, J.K., McKerrow, W.S. & Eales, M.H. (1979). The Southern Uplands of Scotland; a Lower Palaeozoic accretionary prism. *J. geol. Soc. Lond.*, 136, 755-770.
- Lewis, S.D., Ladd, J.W. & Bruns T.R. (1988). Structural development of an accretionary prism by thrust and strike-slip faulting: Shumagin region, Aleutian Trench. *Bull. geol. Soc. Amer.*, 100, 767-782.
- Löffler, T. & Porada, H. (1987). Fazielle Untersuchungen an Metapsammiten der Duruchaus Formation (Geelkop-Aufwölbung, südliches Damara Orogen, Namibia/Südwestafrika). *Communs geol. Surv. S.W.Afr./Namibia*, 3, 119-127.
- Lowe, D. R. (1982). Sediment gravity flows: II. Depositional models with special references to the deposits of high density turbidity currents. *J. sedim. Petrol.*, 52, 279-297.
- MacKinnon, T.C. & Howell, D.G. (1983/84). Turbidite facies in an ancient subduction complex: Torlesse Terrane, New Zealand. *Geo-Marine Lett.*, 3, 211-216.
- Maldonado, A. & Stanley, D.J. (1978). Nile Cone depositional processes and patterns in the Late Quaternary, 239-257. In: Stanley, D.J. & Kelling, G., Eds., *Sedimentation in submarine canyons, fans, and trenches*. Dowden, Hutchinson and Ross, Stroudsburg, Pennsylvania., 395pp.
- Martin, H. (1965). The Precambrian Geology of South West Africa and Namaqualand. *Precambrian Res. Unit, Univ. Cape Town*, 159pp.

- Martin, H. (1983). Overview of the Geosynclinal, Structural and Metamorphic Development of the Intracontinental Branch of the Damara Orogen, 473-502. In: Martin, H. & Eder, F.W., Eds., Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia. Springer Verlag, Berlin, 945pp.
- Martin, H. & Porada, H. (1977). The intracratonic branch of the Damara Orogen in South West Africa. I. Discussion of the geodynamic models. II. Discussion of relationships with the Pan-African Mobile Belt system. *Precambrian Res.*, 5, 311-357.
- Mattes, B.W. & Mountjoy, E.W. (1980). Burial dolomitization of the Upper Devonian Miette Buildup, Jasper National Park, Alberta. *Spec. Publ. Soc. Econ. Paleont. Miner.*, 28, 259-297.
- McWilliams, M.O. & Kröner, A. (1981). Paleomagnetism and tectonic evolution of the Pan-African Damara belt, southern Africa. *J. geophys. Res.*, 86, 5147-5162.
- Menzies, M. (1976). Rare-earth geochemistry of fused ophiolitic and alpine lherzolites, 1. Othris, Lanzo and Troodos. *Geochim. Cosmochim. Acta*, 40, 645-656.
- Middleton, G.V. & Hampton, M.A. (1973). Sediment gravity flows: mechanics of flow and deposition. In: Middleton, G.V. & Bouma, A.H., Eds., *Turbidites and deep water Sedimentation: Soc. Econ. Paleont. Miner., Pacific sect., Short course*, Anaheim, California, 1-38.
- Middleton, G.V. & Hampton, M.A. (1976). Subaqueous sediment transport and deposition by sediment gravity flows, 197-217. In: Stanley, D.G. & Swift, D.J., Eds., *Marine sediment transport and environmental management*. John Wiley, New York, 602pp.
- Miller, R.McG. (1979). The Okavango Lineament, a fundamental tectonic boundary in the Damara Orogen of South West Africa/Namibia. *Trans. geol. Soc. S. Afr.*, 82, 349-361.
- Miller, R.McG., Ed., (1983a). Evolution of the Damara Orogen of South West Africa/Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 515pp.
- Miller, R.McG. (1983 b). The Pan-African Damara Orogen of South West Africa/Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 431-515.
- Miller, R.McG. (1983 c). Tectonic Implications of the Contrasting Geochemistry of Damara Mafic Volcanic Rocks, South West Africa/Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 115-139.

- Miller, R.McG. & Hoffmann, K.H. (1981). Geology of the Damara Belt. Excursion Guide, Geocongress '81, Geol. Soc. S. Afr., 115pp.
- Miller, R.McG. & Burger, A.J. (1983). U-Pb zircon age of the early Damaran Naauwpoort Formation. Spec. Publ. geol. Soc. S. Afr., 11, 267-272.
- Miller, R.McG. & Grote, W. (1988). Geological Map of the Damara Orogen 1: 500 000. Geol. Soc. S. Afr., Johannesburg.
- Miller, R.McG., Barnes, S.-J. & Balkwill, G. (1983). Possible Active Margin Deposits within the Southern Damara Orogen: The Kuiseb Formation between Okahandja and Windhoek. Spec. Publ. geol. Soc. S. Afr., 11, 73-88.
- Miyashiro, A. & Shido, F. (1975). Tholeiitic and calc-alkalic series in relation to the behaviours of titanium, vanadium, chromium and nickel. Amer. J. Sci., 275, 265-277.
- Moore, J.C. (1989). Tectonics and hydrogeology of accretionary prisms: role of the décollement zone. J. Struct. Geol., 11, 95-106.
- Morton, J.L., Holmes, M.L. & Koski, R.A. (1987). Volcanism and massive sulfide formation at a sedimented spreading centre, Escabana Trough, offshore northern California. EOS, Trans. Amer. geophys. Union, 67, 769-772.
- Mottl, M.J., Lawrence, J.R. & Keigwin, L.D. (1983). Elemental and stable-isotope composition of pore waters and carbonate sediments from deep-sea drilling project sites 501/504 and 505. Init. Repts. DSDP, 69, 461-473.
- Muhongo, S. (1990). Late Proterozoic collision tectonics in the Mozambique Belt of East Africa. Abstr. 15th Colloquium on African Geology, Nancy, 276.
- Mutti, E. & Sonnino, M. (1981). Compensation cycles: A diagnostic feature of turbidite sandstone lobes. Abstr. 2nd European Regional Meeting of IAS, Bologna, 120-123.
- Mutti, E. & Ricci Lucchi, F. (1972). Le torbiditi dell' Appennino settentrionale: introduzione all' analisi di facies. Mem. Soc. geol. Ital., 11, 161-199.
- Mutti, E. & Ricci Lucchi, F. (1975). Turbidite facies and facies associations. In: Mutti, E. et al., Eds., Examples of turbidite facies and associations from selected formations of the Northern Apennines. Field Trip Guidebook A-11, 9th IAS Congress, Nice, 21-36.
- Nelson, C.H. (1983/84). The Astoria Fan: An Elongate Type Fan. Geo-Marine Lett., 3, 65-70.

- Nelson, C.H. & Nilsen, T. (1974). Depositional trends of modern and ancient deep-sea fans. In: Dott, R.H. & Shaver, R.H., Eds., *Modern and Ancient Geosynclinal Sedimentation*. Spec. Publ. Soc. Econ. Paleont. Miner., 19, 54-76.
- Nelson, C.H. & Nilsen, T. (1984). Modern and ancient deep-sea fan sedimentation. Soc. Econ. Paleont. Miner. Short course, 14, 404pp.
- Neumann, A.C. & Land, L.S. (1975). Lime mud deposition and calcareous algae in the Bight of Abaco, Bahamas. *J. sedim. Petrol.*, 51, 999-1013.
- Nieberding, F. (1976). Die Grenze der Granitzone südwestlich Otjimbingwe (Karibib-District, Südwestafrika): Intrusionsverband, Tektonik, Petrographie. *Göttinger Arb. Geol. Palaeont.*, 19, 78pp.
- Nilsen, T.H. & Zuffa, G.G. (1982). The Chugach Terrane, a Cretaceous trench-fill deposit, southern Alaska. In: Leggett, J.K., Ed., *Trench-Forearc Geology*. Spec. Publ. Geol. Soc. Lond., 10, 213-227.
- Normark, W.R. (1970). Growth patterns of deep-sea fans. *Bull. Amer. Assoc. Petrol. Geol.*, 54, 2170-2195.
- Normark, W.R. & Piper, D.J.W. (1972). Sediments and growth pattern of Navy deep-sea fan, San Clemente Basin, California Borderland. *J. Geol.*, 80, 192-223.
- Normark, W.R., Mutti, E. & Bouma, A.H., Eds., (1983/84). *Geo-Marine Lett.*, 3. Springer-Verlag, New York, 224pp.
- Orville, P.M. (1975). Stability of scapolite in the system Ab-An-NaCl-CaCO₃ at 4 kb and 750°C. *Geochim. Cosmochim. Acta*, 39, 1091-1105.
- Oterdoom, W.H. & Wenk, H.-R. (1983). Ordering and composition of scapolite: Field observations and structural interpretations. *Contr. Miner. Petrol.*, 83, 330-341.
- Park, R.G. (1988). *Geological structures and moving plates*. Blakie & Sons, Glasgow and London, 337pp.
- Peacock, S.M. (1987). Thermal effects of metamorphic fluids in subduction zones. *Geology*, 15, 1057-1060.
- Pearce, J.A. (1975). Basalt geochemistry used to investigate post tectonic environment on Cyprus. *Tectonophysics*, 25, 41-67.
- Pearce, J.A. (1976). Statistical analysis of major element patterns in basalts. *J. Petrol.*, 17, 15-43.

- Pearce, J.A. & Cann, J.R. (1973). Tectonic setting of basic volcanic rocks determined using trace element analyses. *Earth Planet. Sci. Lett.*, 19, 290-300.
- Pearce, J.A. & Norry, M.J. (1979). Petrogenetic implications of Ti, Zr, Y and Nb variations in volcanic rocks. *Contr. Miner. Petrol.*, 69, 33-47.
- Perchuk, L.L. & Lavrent'eva IV (1983). Experimental investigation of exchange equilibria in the system cordierite-garnet-biotite, 199-239. In: Saxena, S.K., Ed., *Kinetics and equilibrium in mineral reactions*. Springer-Verlag, Berlin-Heidelberg-New York, 273pp.
- Pettijohn, F.J. (1963). Chemical composition of sandstones - excluding carbonate and volcanic sands. *Geol. Surv. Prof. Pap.*, 440-S, 1-21.
- Pettijohn, F.J. (1975). *Sedimentary rocks*. Harper and Row, New York, 628pp.
- Pfurr, N., Ahrendt, H. & Weber, K. (1990). U/Pb and Rb/Sr isotopic study of red granitic gneisses and associated metavolcanics in the area of the Rostock Massifs, Southern Margin Zone of the Damara Orogen, Namibia and their implications for the Lithostratigraphy of this crustal segment. *Abstr. 15th Colloquium on African Geology*, Nancy, 185.
- Phillips, G.N., Groves, D.I. & Reed, .. (1989). Geochemical evolution of the Kuiseb schists, Windhoek, Namibia. *Commun. geol. Surv. Namibia*, 5, 19-30.
- Pickering, K.T. (1981). Two types of outer fan lobe sequence from the Late Precambrian Kongsfjord Formation submarine fan, Finnmark, North Norway. *J. sedim. Petrol.*, 367, 77-104.
- Pickering, K.T. (1984). Facies, facies associations and sediment transport/deposition processes in a late precambrian upper basin-slope/pro-delta, Finnmark, N. Norway. In: Stow, D.A.V. & Piper, D.J.W., Eds., *Fine-grained sediments: deep-water processes and facies*. Spec. Publ. geol. Soc. Lond., 15, 343-362.
- Pickering, K.T. (1985). Kongsfjord turbidite system, Norway, 237-244. In: Bouma, A.H., Normark, W.R. & Barnes, N.E., Eds., *Submarine fans and related turbidite systems*. Springer-Verlag, New York, 351pp.
- Pickering, K.T. & Hiscott, R.N. (1985). Contained (reflected) turbidity currents from the Middle Ordovician Cloridorme Formation, Quebec, Canada: an alternative to the antidune hypothesis. *Sedimentology*, 32, 373-394.

- Pickering, K.T., Stow, D.A.V., Watson, M.P. & Hiscott, R.N., (1986). Deep-water facies processes and models: a review and classification scheme for modern and ancient sediments. *Earth-Sci. Rev.*, 23, 75-174.
- Piper, D.J.W. (1978). Turbidite muds and silts on deep-sea fans and abyssal plains, 163-176. In: Stanley, D.J. & Kelling, G., Eds., *Sedimentation in submarine canyons, fans, and trenches*. Dowden, Hutchinson and Ross, Stroudsburg, Pennsylvania.
- Piper, J.D.A., Briden, J.C. & Lomax, K. (1973). Precambrian Africa and South America as a single continent. *Nature*, 245, 244-248.
- Platt, J.P. (1986). Dynamics of orogenic wedges and the uplift of high-pressure metamorphic rocks. *Bull. geol. Soc. Amer.*, 97, 1037-1053.
- Porada, H. (1973). Tektonisches Verhalten und geologische Bedeutung von Kalksilikatifels-Lagen und Spindeln im Damara-Orogen Südwest-Afrikas. *Geol. Rdscr.*, 62, 918-938.
- Porada, H. (1979). The Damara-Ribeira orogen of the Pan-African Brasiliano cycle in Namibia (South-West Africa) and Brazil as interpreted in terms of continental collision. *Tectonophysics*, 57, 237-265.
- Porada, H. (1983). Geodynamic Model for the Geosynclinal Development of the Damara Orogen, Namibia, South West Africa, 503-541. In: Martin, H. & Eder, F.W., Eds., *Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia*, Springer-Verlag, Berlin, 945pp.
- Porada, H. & Wittig, R. (1975). Zur Tektonik des südlichen Damara-Belts. *Ber. Sond. Forsch. Bers.* 48 (unpubl.), Univ. Göttingen, 51-70.
- Porada, H. & Wittig, R. (1983). Turbidites in the Damara Orogen, 543-576. In: Martin, H. & Eder, F.W., Eds., *Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia*, Springer-Verlag, Berlin, 945pp.
- Preussinger, H. (1987). Die geologische Situation der Erzlinse Vendome im Gorob-Bezirk, SWA/Namibia. Diploma thesis (unpubl.), Univ. Würzburg, 137pp.
- Preussinger, H. (1990). Host-rock geology of the metamorphosed massive sulfide deposits at Gorob in the Pan-African Damara Orogen, Namibia. *Afr. J. Earth Sci.*, 10, 717-732.

- Preussinger, H., Maiden, K. & Okrusch, M. (1987). Contrasting styles of sedimentation in metasediments of the Kuiseb Formation near Gorob, SWA/Namibia. *Communs geol. Surv. S.W.Afr./Namibia*, 3, 105-109.
- Ramsay, I.G. (1967). *Folding and Fracturing of Rocks*. McGraw-Hill, New York, 568pp.
- Ramsay, I.G. & Huber M.J. (1987). *The techniques of modern structural geology*. Vol. 2: folds and fractures. Academic press, London, 391pp.
- Reeves, C.V. (1978). Interpretation of the reconnaissance aeromagnetic survey of Botswana. *Rep. geol. Surv. Botswana*, 199pp.
- Reuning, E. (1923). Pegmatit und Pegmatitmineralien in Südwestafrika. *Zeitschr. Kristall.*, 58, 448-459.
- Ricci Lucchi, F. & Valmori, E. (1980). Basin-wide turbidites in a Miocene, over-supplied deep-sea plain: a geometrical analysis. *Sedimentology*, 27, 241-270.
- Richardson, S.W., Gilbert, M.C. & Bell, P.M. (1969). Experimental determination of kyanite-andalusite and andalusite-sillimanite equilibria: The aluminium silicate triple point. *Amer. J. Sci.*, 267, 259-272.
- Rona, P.A. (1988). Hydrothermal mineralization at oceanic ridges. *Can. Miner.*, 26, 431-465.
- Roser, B.P. & Korsch, R.J. (1986). Determination of tectonic setting of sandstone-mudstone suites using SiO_2 content and $\text{K}_2\text{O}/\text{Na}_2\text{O}$ ratio. *J. Geol.*, 94, 635-650.
- Sample, J.C. & Moore, J.C. (1987). Structural style and kinematics of an underplated slate belt, Kodiak and adjacent islands, Alaska. *Bull. geol. Soc. Amer.*, 99, 7-20.
- Sanderson, D.J. & Marchini, W.R.D. (1984). Transpression. *J. Struct. Geol.*, 66, 449-458.
- Saquaque, A., Admou, H., Karson, J., Hefferan, K. & Keuber, I. (1989). Precambrian accretionary tectonics in the Bou Azzer-El Graara region, Anti-Atlas, Morocco. *Geology*, 17, 1107-1110.
- Sawyer, E.W. (1981). Damaran structural and metamorphic geology of an area southeast of Walvis Bay, SWA/Namibia. *Mem. geol. Surv. S.W.Afr./Namibia*, 7, 94pp.
- Sawyer, E.W. (1983). Structures in the contact strain aureole of the Donkerhoek Granite, Gross Barmen area, South West Africa/Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 209-217.

- Schalk, K. (1970). Some late Precambrian formations in central South West Africa. *Annale geol. Surv. S. Afr.*, 8, 29-47.
- Schmidt, A. & Wedepohl, K. (1983). Chemical composition and genetic relations of Matchless Amphibolite (Damara Orogenic Belt). *Spec. Publ. geol. Soc. S. Afr.*, 11, 139-145.
- Schneider, A. (1983). The chemical composition of the common metamorphic sediments of the Damara Orogen, 655-677. In: Martin, H. & Eder, F.W., Eds., *Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia*. Springer-Verlag, Berlin, 945pp.
- Selley, R.C. (1976). Subsurface environmental analysis of North Sea sediments. *Bull. Amer. Assoc. Petrol. Geol.*, 66, 1489-1498.
- Shackleton, R.M. (1976). Pan-African structures. *Phil. Trans. R. Soc. Lond.*, A 280, 491-497.
- Shackleton, R.M. & Ries, A.C. (1984). The relation between regionally consistent stretching lineations and plate motions. *J. Struct. Geol.*, 6, 111-117.
- Shanmugam, G. & Moiola, R.J. (1988). Submarine fans: Characteristics, models, classification, and reservoir potential. *Earth-Sci. Rev.*, 2, 383-428.
- Shanmugam, G., Moiola, R.J., McPherson, J.G. & O'Connell, S. (1988). Comparison of turbidite facies associations in modern passive-margin Mississippi fan with ancient active-margin fans. *Sedim. Geol.*, 58, 63-77.
- Shaw D.M. (1960). The geochemistry of scapolite. *J. Petrol.*, 1, 218-285.
- Smith, D.A.M. (1965). The geology of the area around the Khan and Swakop rivers in South West Africa. *Mem. geol. Surv. S. Afr.*, S.W.Afr. Ser., 3, 113pp.
- South African Committee for Stratigraphy (SACS), (1980). *Stratigraphy of South Africa. Part 1* (Comp. L.E. Kent). Lithostratigraphy of the Republic of South Africa, South West Africa/Namibia and the Republics of Bophuthatswana, Transkei and Venda. *Handb. geol. Surv. S. Afr.*, 8, 690pp.
- Spear, F.S. & Cheney, J.T. (1989). A petrogenetic grid for pelitic schists in the system $\text{SiO}_2\text{-Al}_2\text{O}_3\text{-FeO-MgO-K}_2\text{O-H}_2\text{O}$. *Contr. Miner. Petrol.*, 101, 149-164.
- Spry, A. (1963). The chronological analysis of crystallization and deformation of some Tasmanian Precambrian rocks. *J. geol. Soc. Australia*, 10, 193-209.

- Stanley, D.J. (1981). Unifites - structureless muds of gravity flow origin in Mediterranean basins. *Geo-Marine Lett.*, 1, 77-83.
- Stokke, P., Carson, B. & Baker, E. (1977). Comparison of the bottom nepheloid layer and Late Holocene deposition of Nitinat fan: Implications for lutite dispersal and deposition. *Bull. geol. Soc. Amer.*, 88, 1586-1592.
- Storre, B. & Karotke, E. (1971). Experimentelle Anatexis von Glimmerschiefern in Modellsystemen. *Fortschr. Miner.*, 49, 56-58.
- Stow, D.A.V. (1984). Turbidite facies, associations, and sequences in the southeastern Angola Basin. In: Hay, W.W., Sibuet, J.-C. et al., Eds., *Init. Repts. DSDP*, 75, 785-799.
- Stow, D.A.V. (1985). Deep-sea clastics: where are we and where are we going?. In: Branchley, P.J. & Williams, B.P.J., Eds., *Sedimentology: Recent developments and applied aspects. Spec. Publ. geol. Soc. Lond.*, 18, 67-93.
- Stow, D.A.V. (1986). Deep clastic seas, 399-444. In: Reading, H.G., Ed., *Sedimentary environments and facies. Blackwell, London*, 615pp.
- Stow, D.A.V. & Bowen, A.J. (1978). Origin of lamination in deep-sea fine-grained sediments. *Nature*, 274, 324-328.
- Stow, D.A.V. & Bowen, A.J. (1980). A physical model for the transport and sorting of fine-grained sediment by turbidity currents. *Sedimentology*, 27, 31-46.
- Stow, D.A.V. & Dean, W.E. (1984). Middle Cretaceous black shales at site 530 in the southeastern Angola Basin. In: Hay, W.W., Sibuet, J.-C. et al., Eds., *Init. Repts. DSDP*, 75, 809-817.
- Stow, D.A.V. & Piper, D.J.W. (1984). Deep-water fine-grained sediments: facies models. In: Stow, D.A.V. & Piper, D.J.W., Eds., *Fine-grained sediments: deep-water processes and facies. Spec. Publ. geol. Soc. Lond.*, 15, 611-646.
- Stow, D.A.V. & Shanmugam, G. (1980). Sequence of structures in fine-grained turbidites: Comparison of recent and ancient flysch sediments. *Sedim. Geol.*, 2, 23-42.
- Stow, D.A.V., Howell, D.G. & Nelson, C.H. (1983/84). Sedimentary, tectonic, and sea level controls on submarine fan and slope-apron turbidite systems. *Geo-Marine Lett.*, 3, 57-64.
- Taira, A., Okada, H., Whitaker, J.H.McD. & Smith, A.J. (1982). The Shimanto Belt of Japan: Cretaceous-lower Miocene active margin sedimentation. In: Leggett, J.K., Ed., *Trench-Forearc Geology. Spec. Publ. geol. Soc. Lond.*, 10, 537-550.

- Thompson, A.B. (1976). Mineral reactions in pelitic rocks: II. Calculations of some P-T-X (Fe-Mg) phase relations. *Amer. J. Sci.*, 276, 401-454.
- Thompson, A.B. & Algor, J.R. (1977). Model systems for anatexis of pelitic rocks. I. Theory of melting reactions in the system $KAlO_2 - NaAlO_2 - Al_2O_3 - SiO_2 - H_2O$. *Contr. Miner. Petrol.*, 63, 247-269.
- Thompson, A.B. & Norton, S.A. (1968). Paleozoic regional metamorphism in New England and adjacent areas, 319-327. In: Zen E-an, White, W.S., Hadley, J.B. & Thompson, J.B., Jr, Eds., *Studies of the Appalachian geology, northern and maritime*. Wiley, New York.
- Thornburg, T.M. & Kulm, L.D. (1987). Sedimentation in the Chile trench: Depositional morphologies, lithofacies, and stratigraphy. *Bull. geol. Soc. Amer.*, 98, 33-52.
- Thornton, S.E. (1984). Basin model for hemipelagic sedimentation in a tectonically active continental margin: Santa Barbara Basin, California Continental Borderland. In: Stow, D.A.V. & Piper, D.J.W., Eds., *Fine-grained sediments: deep-water processes and facies*. Spec. Publ. geol. Soc. Lond., 15, 377-394.
- Tissot, B., Demaison, G., Masson, P., Delteil, J.R. & Combaz, A. (1980). Paleoenvironment and petroleum potential of middle Cretaceous black shales in Atlantic basins. *Bull. Amer. Ass. Petrol. Geol.*, 64, 2051-2063.
- Turner, F.J. & Weiss, L.E. (1963). *Structural analysis of metamorphic tectonites*. McGraw-Hill, New York, 545pp.
- Underwood, M.B. & Bachman, S.B. (1982). Sedimentary facies associations within subduction complexes. In: Leggett, J.K., Ed., *Trench-Forearc Geology*. Spec. Publ. geol. Soc. Lond., 10, 537-550.
- Unrug, R. (1990). The Transcontinental Schlesien-Mwembeshi-Chimaliro Dislocation Zone of South-Central Africa. Abstr. 15th Colloquium on African Geology, Nancy, 175.
- Valley, J.W. (1984). Fluid heterogeneity during granulite facies metamorphism in the Adirondacks: stable isotope evidence. *Contr. Miner. Petrol.*, 85, 158-173.
- Veizer, J. & Hoefs, J. (1976). The nature of $\delta^{18}O/\delta^{16}O$ secular trends in sedimentary carbonate rocks. *Geochim. Cosmochim. Acta*, 40, 1387-1395.
- Walker, R.G. (1976). Facies models, 2. Turbidites and associated coarse clastic deposits. *Geosci. Can.*, 3, 25-36.

- Walker, R.G. (1978). Deep-water sandstone facies and ancient submarine fans; models for exploration for stratigraphic traps. *Bull Amer. Assoc. Petrol. Geol.*, 62, 932-966.
- Ward, J.D. (1987). The Cenozoic succession in the Kuiseb Valley, Central Namib Desert. *Mem. geol. Surv. S.W.Afr./Namibia*, 9, 124pp.
- Weber, K., Ahrendt, H. & Hunziker, J.C. (1983). Geodynamic aspects of structural and radiometric investigations on the northern and southern margins of the Damara Orogen, South West Africa/Namibia. *Spec. Publ. geol. Soc. S. Afr.*, 11, 307-319.
- Williams, P.F. (1985). Multiply deformed terrains-problems of correlation. *J. Struct. Geol.*, 7, 269-280.
- Wimmenauer, W. (1984). Das prävariskische Kristallin im Schwarzwald. *Fortschr. Miner., Beih.*, 62, 69-86.
- Winkler, H.G.F., (1979). Petrogenesis of metamorphic rocks. Springer-Verlag, Berlin, 348pp.
- Winkler, H.G.F. (1983). A survey of granitic rocks of the Damara Orogen and considerations on their origin, 817-837. In: Martin, H. & Eder, F.W., Eds., *Intracontinental Fold Belts - Case Studies in the Variscan Belt of Europe and the Damara Belt in Namibia*. Springer Verlag, Berlin, 945pp.
- Woodcock, N.H. (1976). Ludlow series slumps and turbidites and the form of the Montgomery Trough, Powys, Wales. *Proc. geol. Assoc.*, 87, 169-182.

APPENDIX I,A

Appendix I,A: Table of XRF-analyses of psammites (major elements) along the study traverse, (samples are arranged from north to south, nd = not determined).

SAMPLE NO	SiO ₂	TiO ₂	Al ₂ O ₃	Fe ₂ O ₃	FeO	MnO	MgO	CaO	Na ₂ O	K ₂ O	P ₂ O ₅	H ₂ O	Loi	TOTAL	Remarks
PK 348	73.29	1.03	10.54	5.52	nd	.08	1.87	1.38	2.11	2.68	.19	nd	1.21	99.90	Nomansun
86/1	72.45	.77	11.48	5.34	nd	.07	2.02	1.51	2.80	2.14	.17	nd	.46	99.22	Kelass
86/4	73.76	.94	10.27	5.30	nd	.09	1.95	1.58	2.43	1.94	.12	nd	.60	99.00	
PK/814	74.20	.71	10.91	5.33	nd	.12	2.02	1.71	2.59	2.04	.17	nd	.31	100.30	
PK/816	74.02	.76	10.77	5.07	nd	.06	1.81	1.48	2.56	1.97	.16	nd	.66	99.31	
86/5	74.52	.70	10.73	4.33	nd	.09	1.73	2.37	1.97	1.64	.16	nd	.69	98.96	
PK 114	72.88	.77	12.05	4.88	nd	.07	2.03	.73	2.73	3.40	.18	nd	.92	100.64	
86/6	70.33	1.13	11.44	6.11	nd	.06	2.09	1.06	2.05	3.95	.24	nd	.58	99.03	
86/7	70.80	1.09	11.55	5.76	nd	.09	1.97	1.47	2.63	2.27	.25	nd	.51	98.58	
86/14	73.07	.94	11.01	5.08	nd	.09	1.82	1.47	3.18	1.89	.26	nd	.52	99.32	Bagbrook
86/15	73.06	.95	10.95	5.13	nd	.07	1.99	1.03	2.37	2.57	.19	nd	.84	99.13	
86/16	71.09	1.01	11.03	5.58	nd	.09	2.03	1.52	2.85	2.14	.24	nd	.79	98.37	
PK 312	74.14	.74	11.21	4.54	nd	.11	2.06	2.61	2.50	1.65	.14	nd	.85	100.62	
86/19	71.80	.68	11.33	5.07	nd	.06	2.20	.76	3.36	2.19	.19	nd	.90	98.53	
PK 356	73.17	.94	11.51	4.87	nd	.08	1.75	1.21	3.01	2.83	.23	nd	.59	100.09	
PK 334	73.61	.74	10.62	4.69	nd	.09	1.71	1.59	3.00	2.06	.17	nd	.52	98.80	
PK 364	72.34	.91	12.19	5.31	nd	.08	2.45	1.59	2.93	2.10	.21	nd	.72	100.83	Kaen
PK/803	71.17	1.02	11.70	5.90	nd	.09	3.48	.90	1.62	2.42	.20	nd	1.07	99.57	
PK/805	71.78	.82	11.90	4.94	nd	.14	3.08	1.57	2.84	2.19	.19	nd	.69	99.73	
PK/806	71.55	1.03	12.34	5.35	nd	.10	2.99	1.53	2.88	2.19	.22	nd	.68	99.85	
86/24	73.90	.86	10.86	4.80	nd	.09	1.81	2.06	2.19	1.76	.23	nd	.47	99.02	
86/25	71.48	.76	11.31	4.86	nd	.06	1.82	.97	2.05	2.85	.21	nd	2.92	99.46	
86/26	72.27	.71	11.78	4.75	nd	.06	1.98	1.12	2.41	2.83	.17	nd	.81	98.88	
86/27	70.07	.93	12.35	5.67	nd	.07	2.11	1.05	3.30	2.65	.23	nd	.63	99.29	
86/29	72.55	.85	10.88	5.07	nd	.07	1.66	1.11	2.52	2.50	.21	nd	.73	98.15	
86/30	70.62	.68	12.80	5.10	nd	.08	2.29	2.00	3.43	2.04	.16	nd	.55	99.15	
86/31	73.68	.67	10.51	4.23	nd	.08	1.77	1.83	3.03	1.53	.19	nd	.58	98.09	
86/34	72.25	.85	11.36	5.01	nd	.06	1.69	.71	2.85	2.85	.19	nd	.98	98.50	
86/37	71.89	1.00	11.31	4.61	nd	.06	1.94	1.17	2.39	2.51	.26	nd	1.49	98.81	
86/39	73.16	.71	10.96	4.99	nd	.08	2.20	1.44	3.72	1.78	.15	nd	.53	99.74	
86/40	68.65	.72	13.11	5.44	nd	.09	2.47	1.71	3.23	2.25	.17	nd	.71	98.72	
86/41	70.12	.96	12.27	5.44	nd	.08	2.24	1.57	3.94	2.20	.23	nd	.83	99.38	
86/42	75.65	.49	9.38	3.35	nd	.14	1.39	2.83	2.59	1.31	.14	nd	1.55	98.83	Tanahlat
86/44	73.47	.79	10.47	4.40	nd	.07	1.64	1.00	3.34	1.87	.18	nd	.62	97.85	
86/45	71.40	.76	12.05	5.16	nd	.08	1.81	.75	2.52	2.86	.23	nd	.96	98.58	
86/48	74.65	.67	11.20	4.51	nd	.08	1.86	2.02	3.56	1.68	.17	nd	1.48	101.80	
86/50	73.31	.79	10.94	4.70	nd	.07	1.54	1.57	3.33	2.56	.20	nd	1.17	100.17	
86/51	73.59	.83	11.02	4.79	nd	.07	1.70	1.10	2.89	2.61	.21	nd	.87	99.67	Kaen Dam
86/52	72.91	1.13	11.10	4.63	nd	.07	1.86	1.48	3.06	2.22	.23	nd	.65	99.37	
86/53	74	.99	10.82	4.77	nd	.07	1.83	.86	2.37	2.42	.27	nd	.97	99.37	
86/54	70.17	.69	11.91	5.80	nd	.07	2.43	1.79	3.01	2.08	.15	nd	.73	98.80	
PK/871	72.31	.81	12.10	5.16	nd	.08	2.09	1.09	2.66	2.36	.17	nd	1.67	100.50	
86/55	70.13	.71	12.51	5.93	nd	.07	2.31	1.72	2.72	2.45	.18	nd	.90	99.62	
86/59	71.07	1.19	11.17	6.08	nd	.06	1.94	.98	2.46	2.64	.20	nd	.94	98.76	
86/60	69.53	.88	12.49	5.84	nd	.09	2.40	.94	3.15	1.95	.22	nd	1.44	98.92	Amalie
86/62	72.97	.96	10.90	5.80	nd	.08	1.73	1.84	3.27	1.68	.20	nd	.50	99.73	
86/65	68.12	.89	12.63	6.34	nd	.15	2.63	2.95	2.68	1.90	.27	nd	.60	99.16	
PK 209	72.71	1.16	13.93	5.86	nd	.07	2.05	1.99	2.18	2.64	.19	nd	1.40	101.18	Kobos
PK 199	71.67	1.02	11.79	5.51	nd	.06	2.20	2.48	3.28	1.72	.21	nd	.77	100.71	
PK 535	71.46	.69	11.16	3.85	nd	.15	2.78	1.26	3.46	1.26	.10	nd	4.21	100.48	
PK/824	72.65	.58	10.00	4.65	nd	.11	1.98	3.07	2.11	1.41	.22	nd	1.31	100.50	Amalie
PK 196	73.98	.73	11.23	3.89	nd	.09	2.07	1.79	3.12	1.77	.16	nd	.92	99.75	Okeanus
PK 197	74.48	.68	10.67	4.85	nd	.09	2.15	1.83	3.19	1.85	.19	nd	1.15	101.31	
86/71	71.97	.72	11.53	4.20	nd	.10	2.19	1.47	2.33	2.48	.17	nd	1.19	98.34	
PK 193	72.18	1.03	10.32	5.76	nd	.11	2.26	1.79	2.64	1.97	.20	nd	1.28	99.53	
PK/821	73.42	.74	9.95	4.55	nd	.08	1.48	1.84	2.48	1.90	.14	nd	1.42	100.00	
PK/822	72.52	.66	9.94	4.14	nd	.12	1.51	2.97	3.14	1.63	.13	nd	2.96	99.71	
86/72	72.64	.79	10.95	4.90	nd	.08	1.98	1.58	3.03	1.97	.18	nd	.75	98.85	
PK 189	75.43	.94	9.33	4.40	nd	.09	1.80	2.04	2.56	1.51	.14	nd	.98	99.24	
86/73	69.44	.92	10.71	5.24	nd	.12	2.14	3.26	2.73	1.83	.19	nd	2.74	99.31	Uezabara
86/74	72.37	.80	10.62	4.81	nd	.07	1.71	1.67	2.9	2.18	.17	nd	1.52	98.85	
PK 182	73.39	.76	10.83	4.27	nd	.08	1.75	2.05	3.00	2.26	.15	nd	2.00	100.54	
86/75	73.14	.80	11.60	5.09	nd	.08	1.98	1.96	3.54	2.02	.18	nd	1.49	101.76	
86/80	70.94	.68	10.78	4.55	nd	.11	1.80	3.54	2.52	1.84	.15	nd	2.57	99.50	
86/81	70.34	1.14	10.99	5.92	nd	.10	2.17	2.52	2.62	1.87	.21	nd	1.06	98.94	
86/84	73.80	.77	10.99	4.94	nd	.06	1.82	1.63	2.77	2.11	.15	nd	.76	99.78	
86/85	72.65	1.02	10.77	5.44	nd	.07	1.95	1.58	2.84	2.07	.19	nd	.56	99.14	
PK/856	74.78	.69	10.65	4.78	nd	.06	2.00	1.80	2.23	1.99	.14	nd	.84	99.97	
PK 152	72.49	.93	11.26	5.64	nd	.03	1.96	2.20	2.55	2.14	.16	nd	1.02	100.43	
PK 149	72.49	1.10	11.27	5.87	nd	.06	2.18	2.07	2.53	2.22	.19	nd	1.04	100.82	

APPENDIX I, B

Appendix I, B: Table of XRF-analyses of psammites (trace elements) along the study traverse, (samples are arranged from north to south; nd = not determined; bd = below detection limit).

SAMPLE NO	Rb	Sr	Y	Zr	Nb	Sa	V	Cr	Co	Bi	Cu	Zn	Furumane
PK 345	119	121	42	335	14	498	105	78	10	23	34	65	Komatsushima
86/1	81	131	28	181	9	463	104	76	11	27	bd	71	Kelso
86/4	75	109	32	272	9	457	102	80	9	26	12	69	
PK/814	88	119	36	193	10	272	82	68	11	26	53	74	
PK/816	83	114	32	217	11	331	86	71	11	24	30	70	
86/5	66	118	27	187	9	401	85	65	7	25	36	62	
PK 114	119	109	31	229	12	949	92	69	12	28	6	75	
86/6	112	118	35	347	9	731	119	91	10	28	bd	73	
86/7	86	135	37	332	12	610	108	96	11	30	bd	76	
86/14	74	117	33	289	11	317	97	84	12	26	9	69	Dagbrook
86/15	83	101	34	273	11	599	87	80	10	24	37	62	
86/16	75	143	39	317	10	331	93	87	11	29	bd	73	
PK 312	86	141	37	222	12	252	85	68	12	28	9	66	
86/19	81	82	26	169	8	341	87	69	14	48	6	114	
PK 356	127	144	37	273	13	704	101	78	10	25	19	68	
PK 334	95	153	37	256	12	428	87	67	12	23	7	66	
PK 344	89	339	34	304	12	607	111	82	14	26	23	71	Kaori
PK/803	105	240	34	351	14	653	98	90	13	35	21	98	
PK/805	99	302	34	235	12	505	107	80	15	34	53	83	
PK/806	100	396	37	350	13	646	124	95	12	33	142	77	
86/24	75	190	29	255	9	399	93	83	10	24	41	77	
86/25	91	106	31	198	10	624	101	75	16	51	bd	115	
86/26	94	104	26	180	9	655	94	71	13	27	bd	74	
86/27	111	162	33	257	11	505	117	86	18	43	bd	119	
86/29	9X	112	32	264	9	545	96	77	18	47	bd	72	
86/30	82	136	29	172	8	286	103	70	11	44	11	97	
86/31	65	116	32	187	8	242	77	63	12	25	bd	72	
86/34	82	77	29	243	9	546	98	79	13	23	10	75	
86/37	82	119	34	301	10	432	98	85	12	26	bd	72	
86/39	67	126	29	178	9	395	89	69	13	24	8	70	
86/40	87	135	26	140	9	582	106	81	11	28	bd	86	
86/41	75	134	33	226	11	538	105	87	13	30	42	61	
86/42	54	338	17	125	4	417	72	60	10	24	bd	60	Tamafala
86/44	70	119	31	227	9	370	96	79	13	14	16	13	
86/45	100	236	29	267	10	717	115	75	9	24	9	71	
86/48	65	132	22	167	7	403	91	70	12	31	bd	82	
86/50	91	223	28	275	8	829	92	71	10	24	bd	47	
86/51	96	140	29	261	10	484	96	81	13	27	9	62	Kaori Dam
86/52	83	131	40	371	12	465	106	93	11	27	bd	74	
86/53	86	77	31	303	11	454	94	86	16	42	21	121	
86/54	81	146	27	156	9	443	98	77	9	25	bd	69	
PK/871	87	121	33	212	10	513	104	81	12	26	17	37	
86/55	88	144	30	155	9	419	108	70	10	23	bd	59	
86/59	93	82	37	366	12	558	112	101	11	28	8	71	
86/60	68	88	31	200	11	331	113	84	12	25	bd	66	Annelie
86/62	75	146	32	255	10	353	97	89	15	31	bd	52	
86/63	84	75	34	187	11	307	118	88	13	31	bd	60	
PK 209	107	58	45	374	15	502	121	92	11	27	bd	67	Koboa
PK 199	95	238	38	319	11	423	110	83	12	27	16	72	
PK 955	95	157	31	174	11	185	95	65	11	23	132	87	
PK/824	34	346	38	300	13	775	70	75	9	28	26	81	Annelie
PK 196	86	151	33	213	10	302	95	63	10	32	27	71	Okasuma
PK 197	81	115	34	267	12	314	106	72	10	22	6	70	
86/71	92	87	29	179	9	391	108	70	15	29	bd	83	
PK 193	93	124	41	384	13	303	101	79	12	21	bd	80	
PK/821	82	119	29	218	10	343	88	64	11	22	5	57	
PK/822	65	138	29	190	11	296	89	65	10	20	bd	56	
86/72	74	107	30	196	10	397	111	80	12	25	17	68	
PK 189	64	124	38	290	12	283	92	70	10	20	20	65	
86/73	84	116	31	253	11	284	106	72	15	29	18	85	Usanbara
86/74	83	124	29	199	9	506	103	72	11	24	bd	66	
PK 182	101	170	34	221	11	528	99	69	9	21	bd	62	
86/75	74	122	30	175	8	426	104	75	10	24	bd	65	
86/80	73	123	27	159	8	399	99	68	11	24	bd	67	
86/81	76	163	38	297	11	496	116	89	13	28	bd	82	
86/84	74	117	30	184	8	487	100	64	12	24	bd	67	
86/85	77	90	35	291	11	374	100	93	11	27	bd	78	
PK/856	98	192	28	178	9	429	85	63	12	27	bd	40	
PK 152	104	139	40	269	13	531	100	73	11	27	bd	64	
PK 149	110	158	41	381	15	463	110	87	12	27	6	46	

APPENDIX I,C

Appendix I,C: Table of XRF-analyses (major elements) of pelites along the study traverse, (samples are arranged from north to south; nd = not determined).

SAMPLE NO	SiO ₂	TiO ₂	Al ₂ O ₃	Fe ₂ O ₃	FeO	MnO	MgO	CaO	Na ₂ O	K ₂ O	P ₂ O ₅	H ₂ O	Loi	TOTAL	Remarks
PK 349	68.23	1.02	13.35	6.54	nd	.09	3.34	.70	.80	3.43	.22	nd	1.59	99.31	Komatsus
86/2	56.32	.96	18.87	9.23	nd	.12	4.32	1.33	1.81	4.98	.22	nd	1.72	99.09	Kelasa
PK/815	56.05	1.13	19.81	9.25	nd	.11	4.15	.51	1.25	5.34	.25	nd	2.32	100.16	
PK 109	57.12	.93	19.96	9.82	nd	.09	3.89	.31	.59	6.23	.16	nd	2.66	101.76	
86/8	60.88	.93	17.60	7.72	nd	.08	3.75	.88	1.19	4.36	.23	nd	2.47	100.07	
PK 327	59.26	.86	16.48	7.55	nd	.15	4.59	5.28	1.05	3.29	.21	nd	.86	99.58	
PK 328	61.92	.97	17.65	7.55	nd	.09	3.83	.87	1.42	4.88	.22	nd	2.19	100.79	
PK/849	54.84	1.08	20.83	9.51	nd	.10	4.75	.64	1.17	4.64	.26	nd	2.49	100.32	
PK 324	54.74	.86	20.63	8.85	nd	.05	4.77	.66	.95	6.69	.19	nd	2.50	100.89	
PK/883	50.49	1.18	21.71	9.83	nd	.14	4.95	.69	1.41	6.66	.30	nd	2.79	100.14	Dagbreak
PK/881	50.02	1.16	23.08	8.58	nd	.07	4.67	.43	.90	7.87	.21	nd	2.39	99.37	
PK/843	46.44	1.24	25.30	6.71	nd	.06	5.68	1.67	2.93	7.26	.23	nd	2.56	100.00	
PK 315	60.76	.88	17.55	8.28	nd	.08	3.73	.35	1.07	5.18	.17	nd	2.06	100.11	
86/18	54.44	1.04	19.25	8.90	nd	.10	4.04	.78	1.81	5.83	.24	nd	2.23	98.64	
PK 357	51.97	1.07	21.04	9.31	nd	.12	4.81	1.34	2.60	5.41	.28	nd	2.23	100.18	
PK 355	58.66	.87	18.07	7.62	nd	.08	4.01	1.64	4.31	3.33	.22	nd	1.34	100.15	
PK 358	53.47	.83	16.76	7.54	nd	.08	7.31	5.21	1.26	4.66	.20	nd	1.57	98.89	
PK 359	52.00	.87	15.80	7.57	nd	.07	7.88	7.76	1.38	3.46	.20	nd	1.61	98.27	
PK 360	45.44	1.15	23.16	9.90	nd	.07	6.79	5.90	1.43	5.10	.24	nd	1.20	100.38	
86/22	60.53	.70	15.71	7.16	nd	.09	4.52	5.37	.68	3.55	.19	nd	1.14	99.70	Kaan
86/23	57.98	.93	17.66	8.82	nd	.07	3.62	.96	1.38	5.49	.22	nd	1.84	98.98	
PK/804	67.64	.91	14.45	5.59	nd	.09	3.58	1.35	2.69	2.55	.20	nd	1.02	100.06	
PK 299	59.56	.91	18.08	8.23	nd	.06	3.64	.93	1.38	5.67	.18	nd	1.77	100.41	
PK/880	60.26	.92	17.68	8.01	nd	.09	3.62	.59	1.90	4.41	.14	nd	2.49	100.10	
PK/879	60.11	.93	17.21	8.32	nd	.08	3.48	.86	2.04	4.87	.13	nd	2.05	100.07	
PK 277	56.31	.91	17.80	8.22	nd	.05	4.07	2.05	2.33	4.97	.25	nd	3.27	100.43	
86/38	62.49	.88	17.69	2.50	nd	.01	1.25	.15	.62	5.16	.07	nd	7.11	97.93	
PK/807	57.92	.89	18.37	8.01	nd	.09	3.82	.86	.93	6.07	.16	nd	2.72	99.84	
PK/808	58.98	.94	18.09	7.98	nd	.08	3.72	.82	.94	5.99	.19	nd	2.33	100.05	
PK/835	48.82	1.13	22.12	10.87	nd	.15	5.27	.75	1.57	5.47	.24	nd	3.73	100.12	Tauvika
PK/874	59.67	.93	17.82	7.88	nd	.12	3.68	1.40	2.02	3.98	.17	nd	2.35	100.03	
86/47	58.35	.95	17.80	7.74	nd	.12	3.60	1.38	1.96	3.97	.20	nd	2.53	98.59	
PK 352	65.19	.94	15.81	1.42	nd	.02	.67	.11	.69	5.03	.09	nd	9.30	99.26	Kuogfontein
PK/873	58.56	.86	18.20	8.96	nd	.08	3.68	.38	1.29	5.08	.13	nd	2.80	100.00	Kaan Dam
PK/872	56.03	.95	19.32	9.16	nd	.10	4.34	.42	1.14	5.27	.17	nd	3.65	100.55	
86/57	60.37	.97	17.08	7.73	nd	.10	3.36	.90	1.91	3.69	.23	nd	2.65	98.99	
PK 248	49.22	1.19	22.75	10.20	nd	.11	5.51	.65	1.39	5.39	.35	nd	4.63	101.39	Annelie
PK 246	57.43	.92	19.03	8.19	nd	.09	5.01	.45	.92	4.56	.18	nd	3.68	100.46	
PK/870	55.77	1.08	20.33	8.36	nd	.09	4.07	.44	1.15	5.70	.20	nd	3.34	100.51	Bergkrans
PK/869	57.64	1.00	18.03	7.65	nd	.09	4.00	2.03	2.39	4.41	.21	nd	1.95	99.59	Kobos
PK/954	63.76	.91	16.44	4.78	nd	.08	3.62	.49	1.78	3.95	.07	nd	4.57	100.45	Annelie
PK 215	56.76	1.06	17.94	8.69	nd	.13	4.97	2.38	1.55	3.52	.21	nd	3.17	100.38	Kobos
PK 208	49.43	1.13	20.43	10.70	nd	.15	6.55	1.70	1.38	4.40	.26	nd	3.84	99.99	
PK 131	63.94	.82	13.49	6.86	nd	.08	2.05	8.86	3.10	.32	.16	nd	1.08	100.76	
PK 130	55.57	1.04	18.85	9.97	nd	.11	4.98	.81	.87	4.47	.23	nd	3.50	100.41	
PK 198	58.11	1.03	17.67	9.10	nd	.10	4.59	.73	1.14	4.88	.24	nd	2.71	100.10	
PK 210	59.08	1.03	16.75	8.84	nd	.09	4.84	1.65	1.57	3.11	.23	nd	2.51	99.70	
PK 195	62.25	.96	16.09	7.29	nd	.11	3.76	2.03	2.35	3.09	.20	nd	1.79	99.92	Okasume
PK 190	57.69	.99	18.32	8.60	nd	.08	4.50	.91	1.39	5.22	.24	nd	2.54	100.48	
PK 183	60.70	1.17	17.13	7.99	nd	.08	3.77	.51	1.24	4.59	.28	nd	2.68	100.14	Uambara
86/76	39.93	1.55	25.90	12.11	nd	.16	6.38	.61	.91	6.70	.26	nd	4.55	99.06	
PK/862	54.87	1.16	19.23	8.46	nd	.10	4.38	.51	1.46	4.74	.24	nd	3.30	98.48	
PK/863	66.83	.93	13.96	6.83	nd	.07	3.27	.92	1.68	3.47	.20	nd	1.71	99.93	
PK/864	66.58	.94	13.39	6.62	nd	.12	3.17	1.87	3.30	2.79	.21	nd	1.02	100	
PK/861	47.81	1.29	21.88	10.64	nd	.18	5.78	1.53	3.07	1.78	.24	nd	3.78	100.00	
86/79	65.35	.78	13.77	8.11	nd	.08	3.89	.91	1.25	3.03	.21	nd	2.06	99.43	
PK/858	54.63	1.16	19.61	9.37	nd	.15	4.85	.73	1.01	5.40	.25	nd	2.93	100.06	
86/83	63.20	1.04	15.27	7.17	nd	.17	3.92	1.37	2.05	3.35	.23	nd	1.41	99.17	
PK 153	65.21	.81	15.22	8.08	nd	.12	3.29	1.88	2.20	3.37	.26	nd	.09	100.53	
86/87	58.40	1.35	15.73	7.96	nd	.18	4.13	4.83	2.70	2.26	.29	nd	.95	97.88	
PK/855	54.50	1.05	19.15	9.55	nd	.11	5.14	1.09	2.15	4.97	.19	nd	2.51	100.42	
PK/854	49.54	1.17	21.39	11.96	nd	.15	5.44	.69	.78	6.37	.20	nd	2.24	99.91	

APPENDIX I,D

Appendix I,D: Table of XRF-analyses (trace elements) of pelites along the study traverse, (samples are arranged from north to south; nd = not determined; bd = below detection limit).

SAMPLE NO	Rb	Sr	Y	Zr	Nb	Ba	V	Cr	Co	Ni	Cu	Zn	Farfame
PK 349	137	61	47	291	15	724	131	89	16	36	bd	97	Komatsou
86/2	180	97	37	170	11	732	204	125	19	51	bd	144	Kelias
PK/815	203	80	44	216	17	849	202	148	20	61	bd	150	
PK 509	258	60	36	208	15	769	197	138	21	63	91	145	
86/8	144	75	33	179	10	647	196	127	10	26	bd	71	
PK 327	169	206	48	208	15	394	147	91	16	50	6	122	
PK 328	160	63	40	221	16	557	177	121	19	50	10	70	
PK/849	185	50	43	217	16	682	221	150	21	99	27	159	
PK 324	279	93	36	160	17	765	199	123	21	61	35	163	
PK/883	226	73	52	225	18	1255	244	149	20	68	20	183	Dagbrook
PK/881	381	40	39	238	17	1148	223	152	20	62	bd	51	
PK/843	324	184	47	240	11	1486	262	166		38	46	48	
PK 315	218	67	34	191	15	686	165	111	19	46	49	119	
86/18	185	82	38	198	13	1023	237	134	12	28	bd	77	
PK 337	220	179	43	233	18	1169	270	174	22	68	bd	134	
PK/355	164	228	38	185	15	478	204		17	50	21	90	
PK 358	244	160	34	171	15	491	171		17	49	7	32	
PK 359	208	162	36	182	13	550	137	109	13	45	35	63	
PK 360	215	297	26	210	20	1187	211	160	18	53	186	169	
86/22	175	151	36	152	10	254	136	96	16	24	13	67	
86/23	208	215	33	169	9	787	222	120	10	23	bd	71	Keen
PK/804	108	388	64	208	13	742	139	94	17	43	234	104	
PK 299	253	228	40	186	16	599	180	130	20	56	bd	129	
PK/880	175	80	36	192	13	562	170	120	18	49	bd	137	
PK/879	218	91	34	196	15	590	160	114	17	48	30	134	
PK 277	269	188	42	196	10	812	199	126	16	54	9	42	
86/38	149	94	32	169	9	984	165		11	29	bd	82	
PK/807	205	78	30	173	14	1167	189		17	48	8	103	
PK/808	222	84	31	183	12	843	185		17	51	8	59	
PK/833	199	99	30	215	13	1152	195	142	24	59	56	102	Taswits
PK/874	161	119	31	190	13	467	181	125	13	43	32	121	
86/47	134	104	26	178		648	190	130	11	36	bd	88	
PK 852	136	116	32	190	14	733	156	120	6	bd	bd	14	Kuaggafontein
PK/873	214	81	32	166	12	753	186	128	20	52	26	150	
PK/872	201	78	31	182	13	842	194	137	20	51	60	91	Keen Dam
86/57	112	85	33	183	11	771	154	110	12	24	bd	69	
PK 248	175	99	53	231	11	1152	240	157	19	58	46	158	
PK 246	176	67	39	194	13	674	223	144	19	62	25	152	Annelie
PK/870	186	65	43	199	18	1153	229	145	11	47	22	114	
PK/869	192	170	42	207	19	761	175	123	16	48	14	69	Bergkrans
PK/934	154	109	34	201	14	499	140	102	17	35	27	89	Kobos
PK 215	125	56	39	209	14	619	205	129	21	56	43	143	Annelie
PK 208	147	46	43	220	14	958	240	146	27	69	131	171	Kobos
PK 131	14	338	38	175	14	79	140	91	13	44	11	59	
PK 130	174	44	45	214	16	563	211	130	23	60	14	159	
PK 198	202	41	36	215	14	796	214	126	20	56	31	143	
PK 210	104	70	53	228	17	642	164	109	19	54	7	127	
PK 195	133	119	42	214	15	493	173	110	19	45	21	120	
PK 190	205	80	47	188	16	864	200	123	17	56	34	141	Okasumo
PK 183	192	93	44	270	17	859	182	113	20	52	36	127	
86/76	184	68	32	238	11	1427	304	187	32	79	121	194	Usenbara
PK/862	146	83	42	215	14	911	219	142	18	53	20	141	
PK/863	128	70	32	189	12	563	121	88	17	38	52	108	
PK/864	128	171	31	178	12	425	136	92	17	36	7	107	
PK/861	133	138	58	269	15	745	194	117	26	70	18	193	
86/79	103	80	33	161	6	505	127	85	20	45	119	130	
PK/858	181	63	43	215	16	782	228	144	22	60	22	153	
86/83	122	124	34	191	10	105	183	116	19	46	15	116	
PK 153	148	124	38	171			112	97	18	49	43	63	
86/87	70	118	42	213		879	157	108	16	41	19	98	
PK/855	188	79	40	195	13	593	217	136	23	64	16	151	
PK/854	228	55	46	214	16	856	249	144	24	74	68	212	

APPENDIX II

Appendix II: Table of XRF-analyses of amphibolites and meta-gabbros from the Matchless Amphibolite sequence. Sample localities are indicated in Figure 5.2; (nd=not determined).

SAMPLE NO	267	230	228	221	222	219	220	217	214	213
SiO ₂	51.57	41.47	44.51	46.21	44.47	52.87	50.81	49.32	43.43	48.19
TiO ₂	1.46	2.37	1.90	1.52	1.95	1.85	1.90	1.68	1.43	1.59
Al ₂ O ₃	13.39	14.97	14.65	13.24	13.78	15.03	13.99	13.35	11.95	14.97
Fe ₂ O ₃	10.65	13.54	11.68	9.62	11.91	12.20	11.81	11.20	11.11	11.76
FeO	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd
MnO	.22	.22	.17	.16	.20	.18	.15	.19	.21	.18
MgO	5.18	6.57	4.23	6.84	6.11	6.21	5.63	8.27	7.91	7.55
CaO	19.74	13.99	18.50	12.35	10.89	7.81	10.04	10.82	14.94	13.13
Na ₂ O	3.14	2.14	.79	2.27	2.43	2.58	3.23	.86	1.80	3.15
K ₂ O	.14	.23	.87	.25	.28	.22	.26	.15	.21	.17
P ₂ O ₅	.13	.30	.25	.17	.22	.19	.20	.21	.12	.18
H ₂ O	nd	nd	nd	nd	nd	nd	nd	nd	nd	nd
Loss	3.43	5.00	3.44	7.41	6.49	2.05	1.67	6.85	7.40	.00
TOTAL	99.88	101.14	102.19	100.84	100.90	101.19	99.74	100.90	100.51	100.88
Rb	3	10	6	12	8	8	10	5	7	6
Sr	134	239	134	192	142	107	175	39	143	143
Y	34	42	35	31	37	39	34	35	33	35
Zr	28	165	134	104	139	123	130	110	77	87
Nb	2	28	26	14	15	8	9	13	4	11
Ba	74	61	37	52	48	26	44	22	42	41
V	313	341	376	310	312	384	339	316	299	343
Cr	239	215	150	198	131	199	147	215	222	278
Co	39	42	20	29	33	32	39	31	37	36
Ni	88	134	80	75	61	61	70	95	82	67
Cu	91	7	11	7	5	5	33	8	56	62
Zn	108	110	62	61	84	84	87	95	99	89

amphibolite type II type I type I type II type II type I type II breccia type II type I

SAMPLE NO	26/66	26/68	201	205
SiO ₂	46.31	50.25	56.62	50.45
TiO ₂	1.64	1.67	1.86	1.71
Al ₂ O ₃	14.98	13.10	13.27	13.32
Fe ₂ O ₃	11.19	12.56	13.23	11.97
FeO	nd	nd	nd	nd
MnO	.15	.19	.27	.21
MgO	7.21	7.61	7.63	8.24
CaO	12.35	10.16	8.84	9.20
Na ₂ O	2.35	3.14	1.45	2.87
K ₂ O	.19	.24	.19	.22
P ₂ O ₅	.20	.16	.19	.14
H ₂ O	nd	nd	nd	nd
Loss	1.15	1.05	3.62	1.35

TOTAL 99.71 101.62 101.17 100.29

Rb	3	3	8	7
Sr	183	162	91	168
Y	24	31	42	33
Zr	109	98	121	94
Nb	13	3	9	3
Ba	29	24	45	58
V	315	334	360	340
Cr	290	204	270	240
Co	9	13	38	36
Ni	19	28	102	112
Cu	0	4	11	34
Zn	31	75	175	88

amphibolite gabbro gabbro gabbro gabbro
type

APPENDIX III,A

Appendix III.A1. Analytical conditions for microprobe analyses

Analyses were made on a CAMECA SX 50 electron microprobe at the Mineralogical Institute of the University of Würzburg/FRG. Acceleration potential used was 15 kV and a sample current of 10 nA. Counting time for each mineral was 10s per spot (number of spots are given with analyses in Appendices III,A-F). Natural crystalline and synthetic standards, feldsparglasses, and metals were used for calibration. Only minerals were analysed which are in direct contact parageneses but avoiding edge effects. H₂O in biotite, muscovite, chlorite, and staurolite has been calculated from stoichiometry. Calculations and corrections were made with the Camca "Geo" software (based on PAP).

Appendix III,A2. Table of average plagioclase analyses

SAMPLE	146	86/76	308	109
SiO ₂	61.09	62.83	61.53	63.55
Al ₂ O ₃	24.07	22.81	23.97	22.47
MgO	.02	0	0	.01
CaO	4.63	3.70	4.97	3.04
MnO	.02	.02	0	.01
FeO	.12	.16	.12	.16
BaO	.06	.01	.02	.04
Na ₂ O	8.76	9.45	8.68	9.63
K ₂ O	.28	.07	.14	.13
Total	99.03	99.05	99.44	99.04
Atomic proportions based on 8 <O>				
Si	2.74	2.81	2.74	2.83
Al	1.27	1.20	1.26	1.18
	4.01	4.00	4.01	4.01
Mg	0	0	nd	0
Ca	.22	.18	.24	.15
Mn	0	0	nd	0
Fe2+	0	.01	.01	.01
Ba	0	0	0	0
Na	.77	.82	.75	.83
K	.02	0	.01	.01
	1.01	1.01	1.01	.99
Total	5.02	5.01	5.01	5.00
An	22	18	24	15
grains/points	3/10	3/8	2/7	1/4

APPENDIX III, B

Appendix III, B. Table of average muscovite analyses

SAMPLE	146	86/76	274	308	109
SiO ₂	44.59	45.81	45.15	44.47	45.16
TiO ₂	.44	.44	.19	.33	.41
Al ₂ O ₃	36.24	33.55	37.33	37.04	36.19
MgO	.74	1.24	.54	.55	.67
CaO	.01	0	.03	.01	.01
MnO	.03	0	.05	.01	.01
FeO	1.03	3.03	.87	.85	1.11
BaO	.21	.23	.10	.40	.21
Na ₂ O	.98	.86	1.37	1.27	.80
K ₂ O	9.84	9.84	9.46	9.39	9.98
H ₂ O	4.45	4.45	4.51	4.47	4.47
Total	98.56	99.45	99.60	98.78	99.02
Atomic proportions based on 22 <O>					
Si	6.00	6.17	5.99	5.97	6.05
Ti	.05	.06	.02	.04	.05
Al	5.75	5.33	5.84	5.86	5.71
Mg	.15	.25	.11	.11	.13
Ca	0	0	0	0	0
Mn	0	0	0	0	0
Fe	.12	.34	.10	.10	.13
Ba	.01	.01	0	.02	.01
Na	.26	.23	.35	.33	.21
K	1.69	1.69	1.60	1.61	1.71
Tetr. Z	8	8	8	8	8
Oct. Y	4.08	4.15	4.06	4.07	4.07
Interl. X	1.96	1.93	1.95	1.96	1.94
Total	14.03	14.08	14.01	14.03	14.01
grains/ points	4/11	1/2	1/3	2/5	4/11

APPENDIX III, C

Appendix III, C. Table of average biotite analyses

SAMPLE	146-1	146-2	86/76	274	336	308	109
SiO ₂	34.69	34.28	35.05	34.33	37.07	35.01	34.00
TiO ₂	1.59	1.56	1.61	1.60	1.82	1.48	1.96
Al ₂ O ₃	18.69	18.66	18.10	19.28	16.73	19.68	19.73
MgO	10.34	10.39	11.59	10.34	15.48	10.93	9.13
CaO	.03	.01	.01	.01	.02	0	.01
MnO	.10	.08	.13	.12	.14	.17	.20
FeO	19.88	19.66	18.36	19.50	13.85	18.26	20.14
BaO	.06	.09	.05	.03	.04	.07	.01
Na ₂ O	.20	.22	.24	.18	.09	.09	.24
K ₂ O	9.22	9.33	9.12	9.18	9.32	9.25	9.00
H ₂ O	2.90	3.87	3.92	3.90	4.02	3.95	3.89
Total	98.68	98.14	98.17	98.47	98.64	98.89	98.31
Atomic proportions based on 22 <O>							
Si	5.31	5.28	5.36	5.26	5.51	5.30	5.22
Ti	.23	.23	.23	.23	.25	.21	.28
Al	3.38	3.40	3.26	3.42	2.93	3.51	3.57
Mg	2.36	2.39	2.64	2.36	3.43	2.47	2.09
Ca	0	0	0	0	0	0	0
Mn	.01	.01	.02	.02	.02	.02	.03
Fe	2.55	2.54	2.34	2.50	1.72	3.31	2.59
Ba	0	.01	0	0	0	0	0
Na	.06	.06	.07	.05	.03	.03	.07
K	1.80	1.84	1.78	1.79	1.78	1.79	1.76
Tetr. Z	8	8	8	8	8	8	8
Oct. Y	5.84	5.84	5.85	5.84	5.86	5.82	5.78
Interl. X	1.87	1.91	1.85	1.85	1.81	1.82	1.84
Total	15.70	15.75	15.70	15.69	15.67	15.64	15.62
grains/ points	3/7	3/6	3/8	2/6	2/6	2/6	4/11

146-1 = matrix biotites

146-2 = late, porphyroblastic biotites

APPENDIX III, D

Appendix III, D. Table of average garnet analyses

SAMPLE	146 Ga II		146 Ga III		86/76 Ga III		274	308 Ga III	
	rim	centre	rim	centre	rim	centre	Ga III	rim	centre
SiO ₂	35.77	36.07	35.73	35.64	36.11	36.10	35.42	36.29	36.61
TiO ₂	.01	.05	.06	.11	.03	.06	.07	0	.07
Al ₂ O ₃	21.51	21.70	21.76	21.59	21.11	21.18	21.58	21.64	21.78
Cr ₂ O ₃	0	0	0	0	0	0	0	0	0
Fe ₂ O ₃	2.37	1.75	1.77	1.37	1.57	1.31	1.09	.27	.58
MgO	3.11	2.07	3.05	1.83	2.61	2.62	2.64	3.38	2.89
CaO	4.70	5.51	4.26	4.85	1.72	2.12	1.85	1.19	1.75
MnO	.90	2.17	1.37	5.87	8.19	9.90	7.08	6.42	9.05
FeO	32.26	31.92	32.38	28.89	29.28	26.94	29.77	30.28	28.28
Total	100.63	101.23	100.39	100.18	100.60	100.23	99.50	99.77	101.31
Atomic proportions based on 24 <O>									
Si	5.736	5.768	5.741	5.772	5.836	5.842	5.777	5.876	5.858
Ti	.001	.006	.007	.013	.004	.007	.009	0	.008
Al	4.065	4.090	4.121	4.119	4.021	4.040	4.149	4.130	4.108
Cr	0	0	0	0	0	0	0	0	0
Fe ³⁺	.286	.210	.215	.167	.191	.160	.134	.033	.069
Mg	.743	.493	.730	.442	.627	.632	.642	.816	.689
Ca	.803	.944	.733	.841	.298	.368	.323	.206	.300
Mn	.122	.294	.186	.805	1.121	1.357	.978	.881	1.227
Fe ²⁺	4.326	4.269	4.351	3.912	3.955	3.646	4.060	4.100	3.785
XFe ³⁺	.85	.90	.86	.90	.86	.85	.86	.83	.85
XMn ²⁺	.02	.06	.04	.16	.20	.24	.17	.15	.22
Total Z	6	6	6	6	6	6	6	6	6
Oct. Y	4.09	4.08	4.08	4.07	4.05	4.05	4.07	4.04	4.04
X	6.00	6.00	6.00	6.00	6.00	6.00	6.00	6.00	6.00
Al	16.09	16.08	16.08	16.07	16.05	16.05	16.07	16.04	16.04
AD	7.18	5.41	5.54	4.52	4.86	4.18	3.57	.83	1.94
GR	6.28	10.32	6.68	9.51	.11	1.95	1.82	2.61	3.06
AL	72.11	71.14	72.50	65.20	65.89	60.74	67.63	68.30	63.07
SP	2.04	4.90	3.11	13.42	18.68	22.61	16.29	14.67	20.44
PY	12.39	8.22	12.17	7.36	10.47	10.53	10.69	13.59	11.49
grains/ points	1/10		1/7		2/16		3/14	3/14	

APPENDIX III, E

Appendix III, E. Table of average staurolite, scapolite and chlorite analyses.

STAUROLITE		SCAPOLITE		CHLORITE	
SAMPLE	308	SAMPLE	306	SAMPLE	86/76
SiO ₂	26.39	SiO ₂	47.37	SiO ₂	23.88
TiO ₂	.46	Al ₂ O ₃	26.51	TiO ₂	.08
Al ₂ O ₃	55.43	TiO ₂	.02	Al ₂ O ₃	22.61
MgO	1.36	FeO	.06	MgO	17.32
MnO	.52	MgO	0	CaO	.02
FeO	11.96	MnO	.03	MnO	.39
ZnO	1.23	CaO	15.76	FeO	22.25
H ₂ O	2.13	Na ₂ O	4.71	Na ₂ O	.02
F	.03	K ₂ O	.41	K ₂ O	.04
Cl	.02	Cl	.61	H ₂ O	11.36
		F	.01		
Total	99.53	SO ₃	.21	Total	97.97
Atomic proportions based on 24 <O, OH, F, Cl>		Total	95.71	Atomic proportions based on 36 <O, OH>	
Si	3.68	Atomic proportions based on 12 <Si+Al>		Si	5.04
Al	9.11	Si	7.23	Ti	.02
Ti	.05	Al	4.77	Al	5.63
Mg	.28		12.00	Mg	5.45
Mn	.06			Ca	0
Fe	1.40	Ti	0	Mn	.07
Zn	.13	Fe	.01	Fe	3.93
Total	14.71	Mg	0	Na	0
Mg/(Mg+Fe)	.17	Mn	0	K	.01
grains/ points	1/10	Ca	2.58	Total	20.18
		Na	1.39	X _{Mg}	.58
		K	.08	grains/ points	1/17
		Cl	.13		
		F	0		
		S	.04		
		cat ^a	4.07		
		± Me _j ^b	63.75		
		EqAn ^c	59.05		
		grains/ points	1/8		
		a = (Ti+Fe+Mg+Mn+Ca+Na+K)			
		b = Shaw (1960)			
		c = 100(Al-3)/3 Orville (1975)			

APPENDIX IV: List of candidate's publications**(a) Scientific publications**

- Kukla, P.A. & Stanistreet, I.G. (in press). Record of the Damaran Khomas Hochland accretionary prism in Central Namibia: Refutation of an "ensialic" origin of a Late Proterozoic orogenic belt. *Geology*, 19.
- Kukla, P.A. & Stanistreet, I.G. (1990). Tectonic setting of the Late Proterozoic Khomas Hochland accretionary prism of the Damara Orogen, Central Namibia. *Econ. Geol. Res. Unit Info. Circ.*, 220, Univ. of the Witwatersrand, 22pp., Johannesburg.
- Kukla, P.A. & Stanistreet, I.G. (1990). The Khomas Hochland accretionary prism of the Damara Orogen, Central Namibia. Extended Abstract. 23rd Earth Science Congress, Geol. Soc. S. Afr., University of Cape Town, Cape Town, 309-312.
- Kukla, P.A., Opitz, C. & Stanistreet, I.G. (1988). Cyclic sedimentation and palaeoenvironments in the Kuiseb schist turbidites of the Khomas Trough, Damara Sequence, SWA/Namibia. Extended Abstract. 22nd Earth Science Congress, Geol. Soc. S. Afr., University of Natal, Durban, 351-354.
- Kukla, P.A., Opitz, C., Stanistreet, I.G. & Charlesworth, E.G. (1988). New aspects of the sedimentology and structure of the Kuiseb Formation in the western Khomas Trough, Damara Orogen, SWA/Namibia. *Communs geol. Surv. S.W.Afr./Namibia*, 4, 33-42.
- Kukla, P.A., Charlesworth, E.G. Stanistreet, I.G. & Kukla, C. (1989). Downward-facing structures in the Khomas Trough of the Damara Orogen, Namibia. *Communs geol. Surv. Namibia*, 5, 53-57.
- Kukla, P.A., Kukla, C., Stanistreet, I.G. & Okrusch, M. (1990). Unusual preservation of sedimentary structures in sillimanite-bearing metaturbidites of the Damara Orogen, Namibia. *J. Geol.*, 98, 91-99.


(b) Conference abstracts

- Kukla, P.A. (1990). Unusual scapolitization of Late Proterozoic deep-sea fan sequences in an amphibolite grade metamorphic terrain, Damara Orogen, Central Namibia. Abstract. 68th meeting of the German Mineralogical Society, Würzburg, Germany, *Europ. J. Miner.*, 2, Beih. 1, 145-146.
- Kukla, P.A. & Stanistreet, I.G. (1990). The Late Proterozoic Khomas Hochland accretionary prism of the Damara Orogen, Central Namibia. 68th meeting of the German Mineralogical Society, Würzburg, Germany, *Europ. J. Miner.*, 2, Beih. 1, 147.

APPENDIX IV (CONT.)

- Kukla, P.A. & Stanistreet, I.G. (1990). Evolution and fan facies of a Late Proterozoic accretionary prism in the Khomas Trough, Damara Orogen, Namibia. "Sediments 1990", 13th International Sedimentological Congress, Nottingham, United Kingdom, abstract volume, 286-287.
- Kukla, P.A. & Stanistreet, I.G. (1990). Tectonics and sedimentation of a Late Proterozoic (Damaran) accretionary prism, Central Namibia. 15th Colloquium on African Geology, Nancy, France, abstract volume, 267.
- Häussinger, H. & Kukla P.A. (1990). The TiO_2/Zr ratio: A tool to interpret geochemical data from metaturbidites. 68th meeting of the German Mineralogical Society, Würzburg, Germany, Europ. J. Mineral., 2, Beih. 1, 87.





Author: Kukla Peter Alfred.

Name of thesis: Tectonics and sedimentation of a Late Proterozoic Damaran convergent continental margin, Khomas Hochland, Central Namibia.

PUBLISHER:

University of the Witwatersrand, Johannesburg

©2015

LEGALNOTICES:

Copyright Notice: All materials on the University of the Witwatersrand, Johannesburg Library website are protected by South African copyright law and may not be distributed, transmitted, displayed or otherwise published in any format, without the prior written permission of the copyright owner.

Disclaimer and Terms of Use: Provided that you maintain all copyright and other notices contained therein, you may download material (one machine readable copy and one print copy per page) for your personal and/or educational non-commercial use only.

The University of the Witwatersrand, Johannesburg, is not responsible for any errors or omissions and excludes any and all liability for any errors in or omissions from the information on the Library website.